Cell 2 Composite Liner Design Certification

SWEPCO – John W. Turk, Jr. Power Plant Class 3N Landfill

Permit No. 0311-S3N-R1

AFIN: 29-00506

July 16, 2018 Project No. 35177127



A unit of American Electric Power

Prepared for:

Southwestern Electric Power Company 502 North Allen Avenue Shreveport, Louisiana 71101

Prepared by:

Terracon Consultants, Inc. 25809 Interstate 30 South Bryant, Arkansas 72022 (501) 847-9292

terracon.com



Environmental Facilities Geotechnical Materials

Table of Contents

1.0	OBJECTIVE	1
2.0 E	BACKGROUND INFORMATION	1
	1 FACILITY LOCATION DESCRIPTION	1
3.0 S	SUMMARY AND PE CERTIFICATION	2
3.	1 SUMMARY	2
BIBL	.IOGRAPHY	3
Figu	ires	
1	I. Site Location Map	
2	2. Plant and CCR Unit Location Map	
3	3. Site Layout Map	
4	1. Typical Details 1	
5	5. Typical Details 2	

Cell 2 - Composite Liner Design Certification

John W Turk, Jr ■ Class 3N Landfill Project No. 35177127 ■ July 2018



1.0 Objective

The purpose of this Liner and Leachate Design Certification Report is to evaluate compliance with the requirements of 257.70 for the liner and leachate collection design at the SWEPCO – John W. Turk, Jr Power Plant Class 3N Landfill (Permit No. 0311-S3N-R1) facility. Southwestern Electric Power Company (SWEPCO) is a unit of American Electric Power (AEP).

2.0 Background Information

2.1 Facility Location Description

Southwestern Electric Power Company owns and operates a coal-fired power plant (John W. Turk, Jr. Power Plant) with a Class 3 Non-Commercial (3N) solid waste facility (Class 3N Landfill) associated with the Power Plant. The site is located approximately 2.2 miles north of Fulton (Hempstead County), Arkansas. The Power Plant produces up to 600 Megawatts (MW) of electrical power utilizing western subbituminous coal. The Class 3N Landfill is used for disposal of fly ash, bottom ash, and other byproducts from the coal-fired Power Plant. The waste materials are non-hazardous and non-putrescible. (**FIGURE 1 & 2**)

2.2 Cell 2 Design Criteria for New CCR Lateral Expansion (§ 257.70)

The Turk Class 3N Landfill consists of 5 cells (**FIGURE 3**). All 5 Cells consist of a composite liner system and leachate collection and removal system (**FIGURE 4 & 5**). As per § 257.70 (a)&(d), all new CCR landfills and any lateral expansions must be designed, constructed, operated, and maintained with a composite liner system and a leachate collection and removal system.

2.2.1 Composite Liner System Requirements (§ 257.70 (b) (1-4)

The Cell 2 composite liner system consists of a 60 mil HDPE geomembrane that is installed above a 2-foot clay liner system that has a hydraulic conductivity of no more than 1 x 10⁻⁷ cm/sec. The liner system will be constructed past the limits of waste placement so that the surrounding earth will not be likely to be in contact with CCR or leachate (2011 Permit Application, Volume 3, Appendix B Design Drawings, Terracon Consultants Inc., February 2011)¹. The HDPE geomembrane protects the clay liner from being in contact with the waste. The composite liner system was modeled for slope stability in the previously mentioned Volume 3, Appendix E Landfill Stability Calculations¹. The liner system was also modeled for settlement in Volume 3, Appendix D Landfill Settlement Calculations. The liner system design complies with the requirements of 257.70(b) and this information can be found in the 2011 Permit Application, Volume 3, Appendix B Design Drawings, Appendix D Landfill Settlement Calculations, and Appendix E Landfill Stability Calculations.

John W Turk, Jr ■ Class 3N Landfill Project No. 35177127 ■ July 2018



2.2.2 Leachate Collection and Removal System (§ 257.70 (d) (1-3)

The Cell 2 leachate collection and removal system consists of a double sided geocomposite above the 60-mil HPDE liner. On-site soil will be used for protective cover. Chimney drains will be installed into the protective cover to allow the leachate access to the double-sided geocomposite. The collection piping will also be made from HDPE material. The collection system was designed according to § 257.70 (d) (1-3) and this information can be found in the 2011 Permit Application, Volume 3, Appendix B Design Drawings, Appendix F Leachate Generation Study, Appendix G Leachate Collection Piping Components Calculation, and Appendix H Leachate Collection Pond Capacity Calculations and the 2015 Minor Modification Application, Attachment C Help Model Comparison, Attachment D Revised Permit Drawings, and Attachment E Slope Stability Analysis Report².

3.0 Summary and PE Certification

3.1 Summary

Southwestern Electric Power Company owns and operates a coal-fired power plant (John W. Turk, Jr. Power Plant) with a Class 3 Non-Commercial (3N) solid waste facility (Class 3N Landfill) associated with the Power Plant. The facility consists of a permitted approximately 73-acre disposal area. The facility meets the requirements of 40 CFR 257.70 Design Criteria for new CCR Landfills and any lateral expansion of a CCR landfill.

3.2 Limitations

The findings and conclusions resulting from this investigation are based upon information derived from the on-site activities and other services performed under the scope of work as described in this report; such information is subject to change over time if additional information is obtained. Please note that Terracon does not warrant the work of laboratories, regulatory agencies or other third parties supplying information used in the preparation of the report.

John W Turk, Jr ■ Class 3N Landfill Project No. 35177127 ■ July 2018



3.3 PE Certification

Name:

Date:

7.16,18

Company:

Expiration Date:

12/31/2019

Date:

ARKANSAS

REGISTERED PROFESSIONAL ENGINEER


No. 9199


Stamp


Bibliography

- 1. 2011 Permit Application, Volume 3, Design Basis/Design Analysis, Class 3N Landfill, Terracon Consultants Inc., January 2011.
- 2. 2015 Minor Modification Application, Terracon Consultants Inc., December 2015.











CELL 2 COMPOSITE LINER DETAIL CERTIFICATION


AMERICAN ELECTRIC POWER
JOHN W. TURK, JR. POWER PLANT
FULTON
ARKANSAS PLANT & CCR UNIT LOCATION MAP

Consulting Engineers and Scientists

NOTE: FUTURE CELLS ARE NOT PART OF THE CURRENT CCR UNIT.









TYPICAL CLEANOUT FOR NON-PAVED AREAS

DETAIL 3
SCALE: NTS




TYPICAL PRECAST MANHOLE

DETAIL 4
SCALE: NTS



DETAIL 6

NOTE: CONTRACTOR SHALL PROVIDE PRE-ASSEMBLED AND TESTED/ CERTIFIED PIPE BOOTS FOR EACH PIPE PENETRATION AS PER THE SPECIFICATIONS



PERFORATIONS BUILT TO MANUFACTURER STANDARI

LEACHATE PIPE PERFORATION LOCATION (TYPICAL)

DETAIL 5
SCALE: NTS

NOTES:

 1. REFER TO SPECIFICATION TABLES IN THE CQA PLAN FOR MATERIAL SPECIFICATIONS. ALL MATERIALS WILL BE INSTALLED ACCORDING TO THE CQA PLAN. CELL 2 COMPOSITE LINER DESIGN CERTIFICATION
AMERICAN ELECTRIC POWER
JOHN W. TURK, JR. POWER PLANT

FIGURE

Consulting Engineers and Scientists

25809 1-30 SOUTH

BRYANT, AR 72022
PH. (501) 847-9292
FAX. (501) 847-9210

FULTON