



engineers | scientists | innovators

GROUNDWATER MONITORING NETWORK EVALUATION

Big Sandy Fly Ash Pond Louisa, Kentucky

Prepared for

American Electric Power

1 Riverside Plaza Columbus, Ohio 43215-2372

Prepared by

Geosyntec Consultants, Inc. 500 West Wilson Bridge Road, Suite 250 Worthington, Ohio 43085

Project Number: CHA8500B

December 2016

Revision 1 - October 2023



TABLE OF CONTENTS

1.	OBJ	ECTIV.	E	1					
	1.1	Organ	ization of Report	1					
	1.2	Coord	inate System and Datum	1					
2.	BAG		OUND INFORMATION						
	2.1		ty Description						
	2.2	Descri	iption of CCR Unit						
		2.2.1	Overview of Pre-Closure Conditions	2					
		2.2.2	Overview of Final Closure Plan and Current (Closed) Conditions	2					
		2.2.3	Embankment Configuration	3					
		2.2.4	Area and Volume of CCR Unit	3					
		2.2.5	Construction and Operational (Through Closure) History	3					
		2.2.6	Surface Water Control	4					
	2.3	Previo	ous Investigations and Studies	4					
	2.4	Hydro	geologic Setting	6					
		2.4.1	Climate and Water Budget	6					
		2.4.2	Regional and Local Geologic Setting	7					
		2.4.3	Regional and Local Hydrogeologic Setting	8					
		2.4.4	Surface Water and Surface Water-Groundwater Interactions	9					
		2.4.5	Water Users	9					
3.	MONITORING NETWORK EVALUATION								
	3.1	Hydro	static Units	10					
		3.1.1	Horizontal and Vertical Position Relative to CCR Unit						
		3.1.2	Overall Flow Conditions	10					
	3.2	Upper	most Aquifer	11					
		3.2.1	CCR Rule Definition	11					
		3.2.2	Identified On-Site Hydrostratigraphic Units – Uppermost Aquifer	11					
	3.3	Overv	iew of Groundwater Monitoring System Regulatory Requirements	11					
	3.4	Revie	w of Existing Monitoring Network	12					
		3.4.1	Previous Monitoring Network	12					
		3.4.2	Revised Monitoring Network	12					
		3.4.3	Compliance Assessment						
4.	CER	TIFIC <i>A</i>	ATION BY QUALIFIED PROFESSIONAL ENGINEER	14					



LIST OF TABLES

Table 1: Timeline of Big Sandy Power Plant and BSFAP History

Table 2: Nearby Groundwater Withdrawal Wells

Table 3: Monitoring Network Well Construction Summary

LIST OF FIGURES

Figure 1: Site Location Map

Figure 2: Plant and CCR Unit Location Map

Figure 3: CCR Unit Layout and Boring/Monitoring Well Locations

Figure 4: Surface Geology Map

Figure 5: Nearby Groundwater Withdrawal Wells

Figure 6: Groundwater Elevation Map – Uppermost Aquifer

Figure 7: Previous Groundwater Monitoring Well Network of the Uppermost Aquifer

Figure 8: Revised Groundwater Monitoring Well Network of the Uppermost Aquifer

LIST OF ATTACHMENTS

Attachment A: Record of Changes

Attachment B: References

Attachment C: Geologic Cross Sections

Attachment D: Boring Logs and Monitoring Well Construction Diagrams



ACRONYMS AND ABBREVIATIONS

AEP American Electric Power

ASD alternative source demonstration

BSFAP Big Sandy Fly Ash Pond
CCR coal combustion residuals
CFR code of federal regulations

gpm gallons per minute

GWPS groundwater protection standards

H:V horizontal to vertical

KAR Kentucky Administrative Regulation

KPDES Kentucky Pollutant Discharge Elimination System

KYPCo Kentucky Power Company

MSL above mean sea level

MW megawatt

NAD83 North American Datum of 1983

NAVD88 North American Vertical Datum of 1988

PE professional engineer
PG professional geologist
PVC polyvinyl chloride

SSI statistically significant increase

SSL statistically significant level

USEPA United States Environmental Protection Agency



1. OBJECTIVE

This report provides an assessment of the groundwater monitoring network associated with the Fly Ash Pond at the American Electric Power (AEP) Big Sandy Power Plant for compliance with the United States Environmental Protection Agency's (USEPA's) Coal Combustion Residual (CCR) Rule (Code of Federal Regulations [CFR] Title 40, Section 257.91).

A certified groundwater monitoring network for the Big Sandy Fly Ash Pond (BSFAP) was originally developed by Geosyntec in 2016 (Geosyntec 2016b). Since that time, the BSFAP has been closed in place, including installation of a final cover system in accordance with a Closure Plan that was prepared in accordance with the more stringent of the applicable closure provisions of the Kentucky Administrative Regulations (KAR) for CCR units (401 KAR 46:120) and 40 CFR 257.102. BSFAP closure activities were completed by October 2021 (AECOM 2021), and the BSFAP is now closed and in its minimum 30-year post-closure care period.

Based on changes in site conditions associated with the BSFAP closure and data collected from recent investigations, the groundwater monitoring network is reevaluated herein. This report is intended to document the basis for certification of a revised groundwater monitoring network reflecting the post-closure conditions at the BSFAP. A Record of Changes between the 2016 certified network report and this report is provided in Attachment A.

This report was prepared by Holly Duff, Professional Geologist (PG) (Indiana). The overall groundwater monitoring network evaluation contained herein was performed by Scott M. Graves, Professional Engineer (PE) (Kentucky; No. 21274).

1.1 Organization of Report

This report is organized as follows:

- Section 2 presents background information on the power plant and the CCR unit.
- Section 3 presents an evaluation of the previous monitoring network and the modifications incorporated into the monitoring program.
- Section 4 provides certification from a qualified PE.

A list of the references that are cited in this report is provided in Attachment B. Supporting documentation is provided in Attachments C and D.

1.2 Coordinate System and Datum

The horizontal coordinate values provided in this report are based upon the North American Datum of 1983 (NAD83), Kentucky North Zone. The vertical datum utilized for reporting the elevations within this report is the North American Vertical Datum of 1988 (NAVD88).



2. BACKGROUND INFORMATION

2.1 Facility Description

The Kentucky Power Company (KYPCo), a business unit of AEP, operates the Big Sandy Plant, a former 1,060-megawatt (MW) coal-fired power-generating station in Lawrence County, Kentucky, approximately 4.5 miles north of Louisa, Kentucky (Figure 1). The Big Sandy Plant is located along the Kentucky side of the Big Sandy River, which forms the border with West Virginia.

AEP permanently ceased burning coal at the Big Sandy Plant in November 2015 and transitioned to a 278 MW natural-gas-fired power plant facility. As a result, CCR wastes are no longer being generated, operation of the fly ash pond for disposal of CCR waste has ceased, and the BSFAP closure activities have been completed as of October 2021 (AECOM 2021).

2.2 Description of CCR Unit

2.2.1 Overview of Pre-Closure Conditions

The CCRs formerly generated by the Big Sandy Plant were disposed of in a nearby surface impoundment (i.e., a CCR unit) known as the BSFAP, which is the subject of this groundwater monitoring network evaluation report. As shown (Figures 1 and 2), the BSFAP is located approximately 1.3 miles northwest of the Big Sandy Power Plant and about 4.5 miles northnorthwest of Louisa, Kentucky. The BSFAP formerly received wet-sluiced fly ash from the coalburning process as well as bottom ash that was periodically transferred from the bottom ash ponds next to the main plant area.

The BSFAP was formed by constructing a dam (Main Dam) across the valley of Horseford Creek, and it has therefore sometimes been referred to as the Horseford Creek Site. Figure 2 presents a layout map of the BSFAP and its immediate area.

Additionally, the BSFAP was formed by constructing another dam (Saddle Dam) to span across a small pass (or "saddle") between peaks on a ridgeline on the southeastern side of the BSFAP. Along with these dams, the rest of the now-closed BSFAP is contained by the valley floor and side slopes. The valley floor is composed of alluvium soil overlying bedrock. The valley side slopes range in steepness from approximately 2 horizontal to 1 vertical (2H:1V) to 5H:1V (URS 2013c), and consist of a thin veneer of residual soil (residuum) or weathered bedrock, with some outcrops of sandstone, coal, and shale.

2.2.2 Overview of Final Closure Plan and Current (Closed) Conditions

A notification of intent was submitted to the Kentucky Department for Environmental Protection in 2016 detailing the closure plan designed for BSFAP. The Initial Closure Plan was completed in October 2016 and described the in-place closure design (AEP 2017). The closure included installation of a final cover system (i.e., "cap") having a low-permeability flexible geomembrane system overlain by 2-feet of soil fill consisting of an 18" soil infiltration layer and 6" of earthen material capable of sustaining native plant growth. Prior to the completion of the cap, all free water in the impoundment was removed and the ash was dewatered to sufficient depth to provide a stable



surface. The final cover system was graded with slopes at a minimum of 2% and maximum of 3H:1V to prevent ponding of water and promote surface water runoff.

As part of closure, the height of the Main Dam was lowered and the Saddle Dam removed to preclude the future impoundment of water, sediment, or slurry. A new concrete spillway was installed over the lowered Main Dam, and a spillway structure was installed at the location formerly occupied by the Saddle Dam.

As mentioned, closure activities were completed in 2021. A revised Post Closure Plan was submitted to KYPCo in January 2022. Post closure activities will be conducted for at minimum a 30-year period, during which scheduled inspections of the surface drainage system, cap, and dam will be conducted. Maintenance will be performed if there are any concerns noted during inspections, and the groundwater monitoring system will be maintained during the post closure period (AEP 2022).

2.2.3 Embankment Configuration

Prior to closure when the BSFAP was operational, the Main Dam was composed of an approximately 171-foot-tall, zoned earth-and-rock-fill dam with downstream slopes varying from 1.75H:1V to 2.25H:1V and upstream slopes varying from 2H:1V to 2.75H:1V. The crest of the Main Dam was at an elevation of 711 feet above mean sea level (MSL), but as mentioned, the height of the Main Dam has been lowered as part of the now-completed closure activities. The remaining Main Dam is founded on a stratum of alluvium (approximately 17 feet thick on average) that overlies bedrock. The Main Dam also has a compacted clay keyway that cuts through the alluvium and is founded on bedrock. Under current closed conditions, the Main Dam is equipped with a concrete spillway channel that passes through the lowered dam and releases water on the downstream side of the dam.

Prior to closure when the BSFAP was operational, the Saddle Dam was composed of an approximately 55-foot tall earthen dam of compacted clay, bottom ash, and fly ash. The dam had an upstream slope of 2.75H:1V and a downstream slope of 1.75H:1V, and was founded primarily on bedrock, along with some stiff residuum clays. The crest of the Saddle Dam was at an elevation of 711 feet MSL, but as mentioned, the dam has been removed as part of the now-completed closure activities.

2.2.4 Area and Volume of CCR Unit

The now-closed BSFAP currently occupies approximately 145 acres (AEP 2017). The 2021 Annual Dam and Dike Inspection Report (AEP 2021) indicates that the approximate in-place volume of CCR is 8,275 acre-feet.

2.2.5 Construction and Operational (Through Closure) History

The history of construction and operations at the Big Sandy Power Plant and BSFAP is provided in Table 1. Unit 1 of the Big Sandy Power Plant began operation in 1963. From 1968 to 1970, the BSFAP was created with the construction of the original portion of the Main Dam. Initially, the Main Dam was built with a crest elevation of 625 feet MSL (85 feet tall). Rock-fill berms were also constructed adjacent to the toe of slope of both the upstream and downstream portions of the Main Dam to further buttress the dam. Piezometers were installed in 1969 to monitor performance.



A second phase of construction was completed in 1979 in which the Main Dam was raised to a crest at elevation 675 feet MSL (135 feet tall). This phase also included the construction of an initial saddle dam and emergency spillway. During the second phase, an instrumentation system consisting of deformation monuments, piezometers, and flow measurement weirs was installed at the Main Dam to monitor performance.

The third phase of BSFAP expansion, which was constructed in controlled stages from 1993 to 2011 and now represents current existing conditions, involved raising the crest of the Main Dam to elevation 711 feet MSL (171 feet tall) and constructing the current Saddle Dam with a new adjacent emergency spillway.

The Big Sandy Power Plant ceased burning of coal in 2015, and the BSFAP was closed in place and final capped, with closure activities completed in October 2021. At that time, the BSFAP was transitioned to closed status, and the CCR unit is now in its 30-year post-closure care period.

2.2.6 Surface Water Control

Following the closure of the BSFAP, stormwater runoff from the installed cap and areas surrounding the BSFAP (as described below) is redirected to three outfalls permitted under the Kentucky Pollutant Discharge Elimination System (KPDES): Outfall 001, Outfall 018, and Outfall 021.

Outfall 001 receives runoff from approximately 77 acres on the northern side of the capped pond. The discharged water then flows into Blaine Creek, which in turn flows into the Big Sandy River. Outfall 018 discharges water from a sump placed at the toe of the closed pond. The sump is supplied with runoff water from nearby toe drains located at the base of the former BSFAP. Outfall 021 receives runoff water from approximately 851 acres of the south and west portions of the capped BSFAP. This discharge water is released into a nearby tributary of Blaine Creek.

2.3 Previous Investigations and Studies

Several site investigations and studies have been conducted during the operational and closure/post-closure care history of the BSFAP. The following reports containing hydrogeologic and groundwater-quality characterizations and assessments were used to provide information to support this groundwater monitoring well network evaluation:

- Final Report Hydrogeologic Site Investigation, AEP Big Sandy, Horseford Creek (URS 2013a)
- Report Groundwater Monitoring Plan, AEP Big Sandy, Horseford Creek (URS 2013b)
- Kentucky Power Company, Big Sandy Power Plant Ash Pond Closure Drawings, 100% Submittal (URS 2013c)
- Big Sandy Fly Ash Pond: Report on Hydrogeology and Groundwater Quality (Geosyntec 2015)
- Monitoring Well Installation Report: Fly Ash Pond (Geosyntec 2016a)



- Groundwater Monitoring Network Evaluation (Geosyntec 2016b)
- Closure Plan, CFR 257.102(b), Fly Ash Pond, Big Sandy Plant, Louisa, Kentucky (AEP 2017)
- Fly Ash Pond Closure Phase I (AEP 2018a).
- Fly Ash Pond Closure Phase II and III (AEP 2018b)
- Fly Ash Pond Closure Phase III and IV (AEP 2019a)
- Alternative Source Demonstration Report for Beryllium, Cobalt, and Lithium, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2019a)
- Alternative Source Demonstration Addendum Report for Beryllium, Cobalt, and Lithium, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2019b)
- Alternative Source Demonstration Addendum Report for 2019 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2020)
- Fly Ash Pond Closure Phase IV 2020 and 2021 and Final Closure;
- Alternative Source Demonstration Addendum Report for the March and June 2020 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky. (EHS Support, LLC 2021a)
- Alternative Source Demonstration Addendum Report for the October 2020 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2021b)
- Alternative Source Demonstration Addendum Report for the March and June 2021 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2021c)
- Alternative Source Demonstration Addendum Report for the October 2021 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2022a)
- Alternative Source Demonstration Addendum Report for the March and June 2022 Monitoring Data, Closed Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2022b)
- Alternative Source Demonstration Addendum Report for the October 2022 Monitoring Data, Closed Big Sandy Fly Ash Pond, Louisa, Kentucky (EHS Support, LLC 2023)

Previous hydrogeologic investigations at the BSFAP included the installation of 6 groundwater monitoring wells (MW-1007 through MW-1012) in 2010. A total of 20 borings were advanced as part of the April 2012 subsurface exploration program by URS Corporation. These borings include 8 pond borings (PB-1 through PB-8), 5 soil borings (SB-3, SB-4, SB-6, SB-7, and SB-8), and 7 hydrogeological borings (HB-1 through HB-7) that were subsequently converted into groundwater monitoring wells (MW-1201 through MW-1207). Monitoring wells MW-1206 and MW-1207 were abandoned in December 2015 and January 2016 in accordance with 401 KAR 6:350, Section 11. In 2016, 11 borings were advanced and 7 groundwater monitoring wells (MW-1601 through MW-1607) were installed. The locations of the initial monitoring wells, borings, and other



sampling points are shown on Figure 3. Geologic cross sections from the 2010, 2012, and 2016 investigations are provided in Attachment C. Boring logs and monitoring well construction diagrams may be found in Attachment D.

The hydrogeologic investigations involved drilling; soil, rock, and ash sampling; hydraulic testing; borehole geophysics; well water gauging; and groundwater sampling. In addition, surface water samples and samples from groundwater seeps were collected as part of the groundwater investigation in 2012. The results of these investigations are summarized in the above-referenced documents.

In 2017, a statistical analysis plan was developed to evaluate the monitoring well network for potential exceedances (Geosyntec 2017). Eight sampling events were completed prior to the initial detection monitoring sampling to establish background concentrations for Appendix III and Appendix IV parameters under the CCR rule.

The first detection monitoring sampling event took place in September and October 2017. Statistical analysis of the samples from this detection monitoring event concluded that there were statistically significant increases (SSIs) for boron, calcium, chloride, fluoride, and total dissolved solids. As a result of these SSIs, the BSFAP moved into assessment monitoring. Two assessment monitoring events were completed in 2018, during which statistically significant levels (SSLs) were identified for beryllium, cobalt, and lithium.

Following the results from the 2018 assessment monitoring sampling, an alternative source demonstration (ASD) was conducted in 2018 to address concentrations of beryllium, cobalt, and lithium above the groundwater protection standard (GWPS) at MW-1603. Results from the 2018 ASD indicated that the exceedances were due to the intersection of MW-1603 with a coal seam rather than a release from the BSFAP (EHS Support, LLC 2019a).

Additional ASDs were completed for the same GWPS exceedances at MW-1603 from 2019 to 2023. Constituents detected above the GWPS during this time interval remained consistent except in the ASDs completed in 2020, 2022, and 2023, during which concentrations of combined radium 226 and 228 were also reported above the GWPS. All ASDs concluded that the intersection of the coal seam at MW-1603 was the cause for the exceedances and that BSFAP was not the source of the contaminants (EHS Support, LLC 2019a; 2019b; 2020; 2021a; 2021b; 2021c; 2022a; 2022b; 2023).

2.4 Hydrogeologic Setting

2.4.1 Climate and Water Budget

The average annual precipitation at the site is approximately 47 inches, with monthly totals averaging between about 3.1 inches in the driest months (October and November) to about 5.4 inches in the wettest month (July) (National Oceanic and Atmospheric Administration 2023). Temperatures range from the mid to upper 80s degrees Fahrenheit in July to the mid-40s degrees Fahrenheit in January (Lloyd and Lyke 1995).

¹ National Oceanic Atmospheric Administration, Louisa 5W weather station.



Under previous operating conditions, when the Big Sandy Plant was burning coal, water was used to sluice and transfer fly ash and miscellaneous waste to the BSFAP. As mentioned, AEP permanently ceased burning coal at the Big Sandy Plant in November 2015. The Big Sandy Plant continued to send sluice water from non-CCR sources to the BSFAP up to about 2018. Water previously detained in the BSFAP was released through the principal spillway structure at the Main Dam (Figure 2), where it was discharged to the KPDES—permitted Outfall 001 on the downstream side of the Main Dam. Closure of the BSFAP has been completed (Section 2.2.2), and operation of the fly ash pond for disposal of CCR waste has ceased. Accordingly, CCR sluice water is no longer generated.

As described in Section 2.2.6, stormwater runoff from the installed cap and areas surrounding the closed BSFAP is managed via KPDES outfalls (Outfall 001, Outfall 018, and Outfall 021). Outfall 001 is located on the downstream side of the Main Dam at the end of the concrete spillway channel installed through the lowered dam during closure activities, and discharges flow from stormwater runoff on the installed cap and from adjacent contributing drainage areas of the local watershed, at a variable rate that fluctuates in response to runoff after precipitation events. Outfall 018 is located on the downstream side of the Main Dam and receives and discharges flow from a seepage collection system sump at a rate of approximately 3 to 10 gallons per minute (gpm). Outfall 018 also receives stormwater from toe drains at the BSFAP, with a combined average flow rate of approximately 90 gpm. Outfall 021 receives stormwater from the south and west portions of the BSFAP, at a variable rate that fluctuates in response to runoff after precipitation events.

2.4.2 Regional and Local Geologic Setting

The regional geology of the site consists of relatively flat-lying Pennsylvanian-age rock of the Monongahela, Conemaugh, and Breathitt formations in the upland areas and relatively thin Quaternary-age alluvial deposits in the stream valleys (Lloyd and Lyke 1995). A regional geology map is presented on Figure 4. The Monongahela, Conemaugh, and Breathitt formations are the result of sedimentary deposition in a fluvial-deltaic environment and consist of cyclic sequences of sandstone, siltstones, shales, and coals. Alluvial material in the region is present along streams and consists of unconsolidated deposits of silt, sand, and gravel derived from present-day stream processes (Lloyd and Lyke 1995). A relatively thin layer of residual soils (residuum), generally consisting of clay and sand derived from the weathering of underlying bedrock, is present at the ground surface at higher elevations (URS 2013b).

The local bedrock geology at the capped BSFAP consists of siltstones, sandstones, shales, and coals of the Monongahela, Conemaugh, and Breathitt formations (URS 2013a). Quaternary-age alluvium is present overlying the bedrock at the base of the BSFAP and along the floodplain of the Blaine Creek. Geologic cross sections illustrating the site subsurface lithologic units and groundwater in relation to the ash are presented in the supporting documentation in Attachment C.

Borings advanced within the BSFAP footprint prior to closure revealed ash thickness in the pond of up to 130 feet, with the ash thickness increasing downstream from 15 feet at PB-1 location to 133 feet at PB-8 location (the locations of pond borings are shown in URS [2013c] and Figure 4.2c in Attachment C). The alluvial deposit that occurs at the bottom of the Horseford Creek valley is composed of sandy lean clay to silty sand and gravel. The thickness of the alluvium varies from approximately 10 feet upstream (at PB-1 location) to 26 feet in the middle section of the pond (at



PB-6 location) to 19 feet downstream (at PB-8 location). The alluvium was also encountered downstream of the Main Dam in MW-1606 and MW-1607 and in the floodplain of Blaine Creek (in MW-1604 and MW-1605) (Section 3).

The Monongahela formation, present at elevations roughly above 910 feet MSL, consists of sandstones, siltstones, and shales. Only the lowest cross-bedded sandstone member of the Monongahela formation is present on-site, as a resistant cap on the highest ridge lines (Attachment C).

Underlying the Monongahela formation is the Conemaugh formation, which consists of sandstone, siltstone, and shale with some limestone and coal beds demarcating the upper and lower portions of the formation. A 2- to 3-foot-thick Brush Creek limestone member, located at approximately 780 feet MSL separates the upper unit and the lower unit. The Conemaugh formation outcrops on the hillsides of the site at approximate elevations of 700 to 920 feet MSL.

Underlying the Conemaugh formation is the Breathitt formation, which consists of sandstone, siltstone, and shale with some limestone and coal beds identified as Princess Coals. The uppermost Breathitt formation consists of shale with a resistant sandstone unit near elevation 680 feet MSL (URS 2013a). The Princess No. 8 coal bed is not laterally persistent but is thick enough for commercial mining. The coal bed has an average thickness of 30 inches in northern Lawrence County, where it extends westward for about 8 miles from the Big Sandy River near the mouth of the Blaine Creek valley (Huddle et al. 1963). Exposure of the Princess No. 7 was reported in the Horseford Creek valley at an approximate elevation of 610 to 620 feet MSL prior to the creation of the BSFAP (URS 2013a). The 2016 drilling and monitoring well installation at the BSFAP indicated a coal seam at an approximate elevation of 600 feet MSL. During installation, one monitoring well (MW-1603) intersected the coal seam (Attachments C and D). However, the coal seam was not continuous in the Horseford Creek valley. In borings further upstream of the Main Dam (in MW-1608 and MW-1609), a carbon-rich shale was encountered at an approximate elevation of 600 feet MSL.

2.4.3 Regional and Local Hydrogeologic Setting

The near-surface hydrogeology of the region is generally categorized into two systems: an alluvial aquifer system of unconsolidated deposits and an aquifer system in the fractures of the bedrock (Lloyd and Lyke 1995). The alluvial aquifer system typically consists of sand and gravel and occurs in present-day stream valleys. The bedrock mostly consists of repeated beds of fractured sandstone and limestone deposited during the multiple sedimentary cycles.

Groundwater at the capped BSFAP site is unconfined and is encountered within the fractured bedrock (shale, sandstone, coal) and in the alluvial deposits. Based on previous potentiometric surface measurements in monitoring wells screened in the alluvium and others screened in the bedrock, these water-bearing units appear to be hydraulically interconnected. The water-bearing units are recharged by precipitation, and groundwater generally flows parallel to the topographic slope. The BSFAP is surrounded by ridges, which function as groundwater divides (Figure 1). Although there are fractures present throughout the bedrock, aquifer characteristics of the bedrock and well yields vary depending on the number of fractures and how well the fractures are interconnected.



2.4.4 Surface Water and Surface Water-Groundwater Interactions

The now-closed BSFAP receives stormwater runoff from the approximately 675-acre contributing drainage area of the Horseford Creek watershed upstream from the Main Dam. Following closure, surface water generated from stormwater runoff on the final cover system and from adjacent contributing areas is managed as outlined in Section 2.2.6. The closed condition of the BSFAP with its engineered low-permeability cap, surface water management system, lowered Main Dam (equipped with a spillway), and removed Saddle Dam, promotes runoff, prevents infiltration, and prevents impoundment of water. As such, there is minimal potential for surface water recharge of groundwater within the footprint of the BSFAP.

Based on the site hydrogeology (Section 2.4.3), any remaining porewater in the BSFAP and groundwater may hydraulically interact with each other. Groundwater elevations in the overburden/weathered bedrock or fractured bedrock on the hillsides surrounding the BSFAP are higher than the previous surface water elevation in the pond. Downstream of the Main Dam, groundwater from the Horseford Creek alluvium likely flows first into the Blaine Creek valley alluvium before discharging into the surface water of the creek.

2.4.5 Water Users

Location and description of groundwater withdrawal wells were obtained from the Kentucky Groundwater Data Repository's Water Well and Spring Location Map (Kentucky Geological Survey 2023). The location of these wells is provided in Figure 5. As shown, a total of 10 water wells were identified within an approximately 1-mile radius of the BSFAP. Additional information on these wells is provided in Table 2. As shown on Table 2, 7 of these wells are used for domestic use, 1 for industrial use, 1 for mining, and 1 for an unknown use.



3. MONITORING NETWORK EVALUATION

3.1 Hydrostatic Units

3.1.1 Horizontal and Vertical Position Relative to CCR Unit

Groundwater at the now-closed BSFAP is unconfined and is encountered within the fractured bedrock of the Conemaugh and Breathitt formations and in the alluvial deposits at the bottom of the Horseford Creek valley. These bedrock and alluvium water-bearing units appear to be hydraulically connected. Outcrops of sandstone, siltstone, and shale along the hillsides of the Horseford Creek valley surround the ash pond (URS 2013b). The ash was placed directly above the alluvium in the Horseford Creek valley. Underlying the alluvium is either the sandstone or the shale of the Breathitt formation. Geologic cross sections illustrating this connectivity of the water-bearing formations are provided in Attachment C.

3.1.2 Overall Flow Conditions

As discussed in Section 2.4.3 above, groundwater flow conditions at the BSFAP site are generally consistent with (i.e., mimic) site topography. The outcropping water-bearing units are recharged by precipitation and groundwater generally flows parallel to the topographic slopes from the hillsides surrounding the BSFAP, with potential for hydraulic interconnection between bedrock and alluvium units. North of the Main Dam, it appears that groundwater from the Horseford Creek alluvium flows into the Blaine Creek valley alluvium and eventually makes its way into the surface water of the creek. Inferred groundwater flow directions are shown in Figure 6.

Site topographic information indicates the presence of a natural saddle between peaks on a ridgeline on the southeastern side of the BSFAP prior to construction of the Saddle Dam on the southeastern side of the BSFAP. The closure activities removed free water, dewatered ash, and removed the Saddle Dam – preventing impoundment of CCR and/or water adjacent to the saddle and thus removing the potential for associated hydraulic gradients driving groundwater outward from the BSFAP at this location. Instead, conditions that more closely resemble predevelopment at the saddle have been restored. Accordingly, and based on the aforementioned groundwater flow regime, this saddle functions as a groundwater divide. Groundwater flow near the saddle (former Saddle Dam location) would be split, with groundwater on the BSFAP-side of the saddle flowing toward the west or northwest, into the Horseford Creek valley (i.e., toward the now-closed BSFAP), and groundwater on the opposite side of the saddle flowing toward the southeast (away from the closed BSFAP). The closed BSFAP and associated limits of its final-covered in place CCR are situated entirely on the BSFAP-side of the saddle, and groundwater on this side of the saddle would be expected to flow west-northwestward and potentially interconnect with the bedrock-alluvium groundwater flow regime at the BSFAP site. In contrast, groundwater on the opposite side of the saddle would not have originated from nor have the potential to hydraulically interconnect with the flow regime at the BSFAP site).

The *Monitoring Well Installation Report* (Geosyntec 2016a) indicated that the horizontal hydraulic conductivity (K) of the bedrock units depends on the dimension of fractures identified in the screen interval and on how well the fractures are interconnected. Wells screened in the sandstone unit with one open fracture (such as MW-1601 and MW-1602) have an average K on the order of 10⁻⁴ centimeters per second (cm/sec). Similarly, monitoring well MW-1611, screened in shale and coal



seam with multiple open fractures, also has a K of 10^{-4} cm/sec. In contrast, monitoring wells screened in the sandstone and shale with multiple but narrow fractures (such as in MW-1608) resulted in K values on the order of 10^{-5} and 10^{-6} cm/sec. Two borings (designated as MW-1609 and MW-1610) were abandoned because borehole geophysics and packer testing results indicated no measurable groundwater flow in the target screen intervals. Monitoring wells screened in the sand and gravel alluvium have K values on the order of 10^{-3} cm/sec to 10^{-4} cm/sec.

3.2 Uppermost Aquifer

3.2.1 CCR Rule Definition

The *uppermost aquifer* referred to in Section 257.91 of the groundwater monitoring systems rule for CCR units is, according to 40 CFR 257.53, "the geologic formation nearest the natural ground surface that is an aquifer, as well as lower aquifers that are hydraulically interconnected with this aquifer within the facility's property boundary. Upper limit is measured at a point nearest to the natural ground surface to which the aquifer rises during the wet season."

An *aquifer* is defined as "a geologic formation, group of formations, or portion of a formation capable of yielding usable quantities of groundwater to wells or springs." Per the preamble that accompanies the CCR Rule, this definition includes a shallow, deep, perched, confined, or unconfined aquifer, provided that it yields usable water. Usable water is not defined in the CCR Rule nor in Kentucky regulations.

3.2.2 Identified On-Site Hydrostratigraphic Units – Uppermost Aquifer

The hydrostratigraphy in the vicinity of the capped BSFAP is characterized by an interconnected water-bearing system comprising Pennsylvanian-age bedrocks of the Conemaugh and Breathitt formations and the Quaternary alluvium. The bedrocks include sandstones, siltstones, shale, and coal that may grade laterally and vertically into one another. The alluvial deposits include sandy lean clay to silty sand and gravel at the bottom of the Horseford Creek valley and the floodplain of the Blaine Creek.

The interconnected water-bearing system of the fractured bedrock and alluvium within the Horseford Creek valley is considered the uppermost aquifer at the closed BSFAP site. This is based on the presence of groundwater in numerous monitoring wells screened in the water-bearing units, the recovery of these wells during pumping and development, and a potentiometric surface generally consistent with site topography and previous surface water elevations. This conclusion is further supported by the presence of several nearby water withdrawal wells (discussed in Section 2.4.5) that appear to be screened in the same or a similar hydrogeologic setting/formation or materials.

3.3 Overview of Groundwater Monitoring System Regulatory Requirements

The preamble that accompanies the CCR Rule concisely summarizes the groundwater monitoring system regulatory requirements of Rule 40 CFR 257.91: "all groundwater monitoring systems must consist of a sufficient number of appropriately located wells (at least one upgradient and three downgradient wells) in order to yield groundwater samples from the uppermost aquifer that represent the quality of background groundwater and the quality of groundwater passing the CCR waste boundary." The upgradient background wells must be located beyond the upgradient extent



of potential contamination, whereas the downgradient wells will monitor any contaminants leaking into the groundwater and must be located at the downgradient perimeter of the CCR unit. Although the rule requires a minimum of one upgradient and three downgradient monitoring wells, the number, spacing, and depths of the monitoring wells must be determined based on the hydrogeology of the site, including aquifer thickness and groundwater flow rates and direction.

3.4 Review of Existing Monitoring Network

3.4.1 Previous Monitoring Network

The original groundwater monitoring network consisted of 10 groundwater monitoring wells (MW-1011, MW-1012, MW-1203, MW-1601, MW-1602, MW-1603, MW-1604, MW-1605, MW-1606, and MW-1607) located both upgradient and downgradient of the BSFAP to support groundwater monitoring of the uppermost aquifer (fractured bedrock and alluvium) (Figure 7; Geosyntec 2016b).

Monitoring wells MW-1011, MW-1012, MW-1203, MW-1604, and MW-1605 were used for background monitoring, whereas monitoring wells MW-1601, MW-1602, MW-1603, MW-1606, and MW-1607 were placed downgradient of the BSFAP and used for downgradient monitoring.

The monitoring wells (with the exception of MW-1011, MW-1012, and MW-1203) were installed in an 8-inch borehole and have 4-inch-diameter polyvinyl chloride (PVC) casings with 10-footlong, 0.01-inch-slot-size screens. Monitoring wells MW-1011, MW-1012, and MW-1203 were constructed with 2-inch-diameter PVC casings and 0.01-inch-slot-size screens with screen lengths ranging between 10 and 30 feet. Well construction details are summarized in Table 3, and boring logs and well construction diagrams are provided in Attachment D.

3.4.2 Revised Monitoring Network

The revised monitoring network will consist of 9 monitoring wells (Figure 8). Three of the monitoring wells (MW-1011, MW-1012, and MW-1203) are screened in bedrock and were installed on the hillside slopes upgradient of the closed BSFAP for background monitoring. Two monitoring wells (MW-1601 and MW-1602) installed in bedrock are located downgradient of the BSFAP for downgradient monitoring. Two monitoring wells (MW-1604 and MW-1605) screened in alluvium will be used for background monitoring. Two other monitoring wells (MW-1606 and MW-1607), screened in alluvium and located below the Main Dam downgradient of the Horseford Creek valley, will be used for downgradient monitoring. Monitoring well MW-1603 will be removed from the groundwater monitoring network for reasons described below and will be plugged and decommissioned.

Previous statistical evaluations completed to support assessment monitoring indicated that concentrations of beryllium, cobalt, combined radium, and lithium at MW-1603 were detected at concentrations above those detected at monitoring wells located both upgradient and downgradient of the monitoring well. ASD evaluations determined that MW-1603 was screened within a coal seam, and the highly organic material within the coal served as a natural source of the elevated concentrations of beryllium, cobalt, combined radium, and lithium in the groundwater (EHS Support, LLC 2019a; 2019b; 2020; 2021a; 2021b; 2021c; 2022a; 2022b; 2023). Moreover, based on the changed conditions at the former Saddle Dam near MW-1603 due to BSFAP closure activities as described in Section 3.1.2, it is evident that MW-1603 is located on the opposing side



of the groundwater divide at the restored natural saddle and groundwater at this location would not be hydraulically interconnected with the flow regime at the BSFAP site. Therefore, groundwater at MW-1603 is not downgradient of the BSFAP, nor representative of groundwater found at other locations both upgradient and downgradient of the BSFAP. For the foregoing reasons, this location (MW-1603) will be removed from the groundwater monitoring network.

3.4.3 Compliance Assessment

Based on the review of the groundwater monitoring well network in relation to the geologic and hydrogeologic conditions in the area of the capped BSFAP, there are enough wells installed at the appropriate locations and depths to yield groundwater samples from the uppermost aquifer that accurately represent the quality of background groundwater and groundwater passing the waste boundary of the closed BSFAP. The groundwater monitoring well network can also provide a system for detection of potential contamination in the uppermost aquifer nearest the waste boundary. In particular, based on their close proximity to the downgradient waste boundary of the closed BSFAP and the documented hydrogeology and groundwater flow directions at the site, the downgradient groundwater monitoring wells are appropriately positioned. Based on the above review, the groundwater monitoring network around the closed BSFAP meets the requirements of 40 CFR 257.91.



4. CERTIFICATION BY QUALIFIED PROFESSIONAL ENGINEER

I have reviewed the groundwater monitoring network and well construction details in the vicinity of the Fly Ash Pond at the Big Sandy Plant and based on the evaluation presented in Section 3 of this report, I certify that the groundwater monitoring system has been designed and constructed to meet the requirements of Section 40 CFR §257.91.

Scott M. Graves		
Printed Name of Licen	nsed Professional E	ngineer
GRAVES GRAVES	Sed Floressional E	10/30/202
Seal and Signature		Date
		• ,
21274	Kentucky	
License No.	State	




Table 1. Timeline of Big Sandy Power Plant and BSFAP History

Fly Ash Pond Groundwater Monitoring Network, AEP - Big Sandy Plant Louisa, Kentucky

Year	Event							
1963	Unit 1 began operation.							
1968	Construction of Horseford Creek Dam Phase 1 began in late 1968.							
1969	Rock fill berms were constructed on both sides (upstream and downstream) of the embankment in January 1969.							
1969	Unit 2 began operation.							
Piezometers were installed in late 1969 to monitor the pore water press embankment fill and foundation soils; the berms were enlarged in late								
1970	Construction of phase 1 was completed in mid-February 1970 when the dam crest reached 625 feet (ft), above mean sea level (MSL) (i.e., 85 feet tall)							
1976	Design for Horseford Creek Dam Phase 2 began in April 1976.							
1979	Phase 2 construction was completed in 1979 with the crest at 675 ft, MSL (i.e., 135 feet tall). The service spillway tower and discharge pipe were constructed as part of phase 2. The Saddle Dam and emergency spillway were also constructed in phase 2.							
1993	Phase 3 construction begins, which included raising the crest of the Main Dam, constructing a new Saddle Dam, filling the old emergency spillway, and constructing a new emergency spillway.							
2009	Construction of the raising of the Main Dam was completed, achieving the final crest elevation of 711 ft, MSL.							
2010	AEP installed the MW1000-series wells to monitor groundwater quality downgradient of the BSFAP.							
2012	Twenty (20) borings were advanced by URS to assess the local geology and hydrogeology as well as to evaluate the geotechnical characteristics of the soil. Seven (7) borings were converted to MW1200-series monitoring wells.							
2016	Eleven (11) borings were drilled under Geosyntec's oversight to supplement the site hydrogeologic information and eight (8) borings were converted to MW1600-series monitoring wells.							
2016	Construction to close the BSFAP began in August 2016.							
2016	Initial Closure Plan was developed by AEP and submitted to Kentucky Power - Big Sandy Plant.							
2017	Groundwater Monitoring Network Evaluation Report was designed to assess and detail the current monitoring network implemented at the Big Sandy Fly Ash Pond (BSFAP).							
2018	Phase I of the BSFAP was completed. Events completed during this phase included subgrade preparation, the installation of the geomembrane, geocomposite, geotextile, placement of the aggregate, and placement of the protective soil cover.							

Table 1. Timeline of Big Sandy Power Plant and BSFAP History

Fly Ash Pond Groundwater Monitoring Network, AEP - Big Sandy Plant Louisa, Kentucky

2019	EHS Support conducted an alternative source demonstration (ASD) for beryllium, cobalt, and lithium at monitoring well MW-1603. This ASD successfully described that the exceedances were caused by a source other than the BSFAP.
2020	EHS Support conducted an ASD for combined 226 and 228 radium, beryllium, cobalt, and lithium at MW-1603. The ASD indicated that a source other than the BSFAP was responsible for the groundwater protection standard (GWPS) exceedances.
2021	BSFAP closure activities were completed and the unit transitioned into the post closure activities listed in the approved Post Closure Plan.

Table 2. Nearby Groundwater Withdrawal Wells

AEP Big Sandy Plant - Fly Ash Pond Louisa, Kentucky

AKGWA Number	Northing	Easting	Construction Date	Status	Primary Use	Surface Elevation (ft)	Total Depth (ft bgs)	Static Water Level (ft bgs)	Owner Last Name	Owner First Name	Owner Business Name	
00002933	256210.61	2106257.57	3/4/1987	Active	Domestic - Single Household	640	100	50	Kirk	Robert		
00006915	256902.45	2099538.43	5/16/1988	Active	Domestic - Single Household	580	120	60	West	Larry		
00006916	256504.86	2099944.59	6/1/1988	Active	Domestic - Single Household	580	105	70	West	Freddie		
00006922	254764.36	2110275.71	8/11/1988	Active	Domestic - Single Household	810	380	250	Kinner	John		
00008075	254417.41	2096227.64	2/23/1990	Active	Domestic - Single Household	680	80	25	Holbrook	Edgar		
00011523	254851.01	2103726.21	5/24/1988	Active	Domestic - Single Household	580	67	50	Davis	Kenneth		
00051043	248143.95	2102006.86	5/27/1999	-	ŀ	580	140	25	Colonial	Syufuel		
00056935	248445.85	2101921.66	8/25/2001	Active	Mining	680	200	51	NA	NA	Kanawa River	
00060898	251232.14	2110945.96	7/19/2011	Active	Industrial - General	576.2	302	55	NA	NA	Coastal Corrosion Control Inc	
30002996	255015.34	2107397.44			Domestic - Single Household	0	65	0	NA	NA		

Notes

AKGWA: Assembled Kentucky Groundwater numbers assigned to all repository wells and springs

ft : feet

ft bgs : feet below ground surface

NA : Not applicable
"--" : Data not available

Table 3. Monitoring Network Well Construction Summary Fly Ash Pond Groundwater Monitoring Network, AEP - Big Sandy Plant Louisa, Kentucky

Monitoring Well ID	Northing	Easting	TOC Elevation (ft, MSL)	Ground Surface Elevation (ft, MSL)	Stickup Length* (ft)	Well Purpose & Location	Screen Zone Geology	Screen Top BTOC (ft)	Screen Bottom BTOC (ft)	Screen Top Elevation (ft, MSL)	Screen Bottom Elevation (ft, MSL)	Proposed Pump Intake BTOC (ft)
MW-1011	251056.62	2105873.28	718.78	716.15	2.63	Sampling (Upgradient)	Bedrock	37.63	77.63	681.1	641.1	57.6
MW-1012	249566.05	2103715.55	790.56	787.91	2.65	Sampling (Upgradient)	Bedrock	112.65	142.65	677.9	647.9	127.7
MW-1203	252206.28	2101406.51	731.03	728.30	2.73	Sampling (Upgradient)	Bedrock	39.73	49.73	691.3	681.3	44.7
MW-1601	254131.13	2104798.67	716.59	713.84	2.75	Sampling (Downgradient)	Bedrock	69.8	79.8	646.8	636.8	74.8
MW-1602	254183.19	2105862.78	714.53	711.60	2.94	Sampling (Downgradient)	Bedrock	82.4	92.4	632.1	622.1	87.4
MW-1603	251596.53	2107344.43	675.75	673.24	2.51	Not Monitored	Bedrock	24.5	34.5	651.2	641.2	32.5
MW-1604	254482.33	2108828.43	556.21	553.12	3.09	Sampling (Upgradient)	Alluvium	43.1	53.1	513.1	503.1	48.1
MW-1605	252760.21	2110694.01	557.46	554.40	3.06	Sampling (Upgradient)	Alluvium	18.6	28.6	538.9	528.9	26.6
MW-1606	254592.81	2105122.96	554.10	550.99	3.11	Sampling (Downgradient)	Alluvium	44.1	54.1	510.0	500.0	49.1
MW-1607	254664.49	2105634.33	545.23	542.21	3.02	Sampling (Downgradient)	Alluvium	26.5	36.5	518.7	508.7	31.5
MW-1608	251052.42	2105883.65	719.08	716.15	2.94	Water Level Measurement	Bedrock	112.9	122.9	606.1	596.1	NA
MW-1611	254192.11	2105868.49	714.25	711.64	2.61	Water Level Measurement	Bedrock	107.6	117.6	606.6	596.6	112.6

Notes:

- 1. Northing and Easting are in North American Datum of 1983 (NAD83) State Plane KY North. Elevations are based on North American Vertical Datum of 1988 (NAVD88).
- 2. The northing and easting measurements were taken at the top of TOC.
- 3. MW-1603 was included in the original groundwater monitoring network (Geosyntec 2016) and was removed as of October 2023.


BTOC: below top of casing


ft: feet


MSL: mean sea level NA: not applicable NM: not measured TOC: top of casing


* : casing length above ground surface
















1. Monitoring well coordinates and water level data (collected on October 10, 2022) provided by AEP.


Site features based on information available in Groundwater Monitoring Network Evaluation - Big Sandy Fly Ash Pond (Geosyntec 2016) provided by AEP.
 Groundwater elevation units are feet above mean sea level (ft ansl).

- 4. Fly Ash Pond cap liner construction completed in November 2020.
- ft: feet.
- amsl: above mean sea level.

Groundwater Elevation - Uppermost Aquifer
October 2022

AEP Big Sandy Plant - Fly Ash Pond
Louisa, Kentucky

Geosyntec[▶] Figure consultants 6 Columbus, Ohio 2023/07/28



Legend

Fly Ash Pond (Approximate)

Monitoring Well


Gauging Well

Notes
1. Monitoring well locations based on 2016 coordinates.
2. MW-1206 and MW-1207 were abandoned during construction to close the BSFAP: Big Sandy Fly Ash Pond

Previous Groundwater Monitoring Well Network of the Uppermost Aquifer AEP Big Sandy Plant - Fly Ash Pond Louisa, Kentucky

7

Geosyntec[▶] Figure consultants Columbus, Ohio 2023/10/04



Legend

Fly Ash Pond (Approximate)

Monitoring Well

Gauging Well

Notes
1. Monitoring well locations based on 2016 coordinates.
2. MW-1206 and MW-1207 were abandoned during construction to close the BSFAP: Big Sandy Fly Ash Pond

Revised Groundwater Monitoring Well Network of the Uppermost Aquifer AEP Big Sandy Plant - Fly Ash Pond Louisa, Kentucky

2023/10/04

Figure

8

Geosyntec[▶] consultants

Columbus, Ohio

ATTACHMENT A Record of Changes

Record of Changes								
Revision Number	Date	Revision Description						
0	December 2016	Initial Report						
		Revisions were made throughout the document to note that the BSFAP has been closed in place, including installation of a final cover system, and the BSFAP is now closed and in its minimum 30-year post-closure care period.						
		Sections 2.2.6 and 2.4.4: Revised to reflect changes in surface water handling following installation of the final cover system.						
1	October 2023	Section 2.3: Revised to include the preparation of multiple alternative source demonstrations for the BSFAP.						
		Section 3.1.2: Revised to reflect changes in groundwater flow direction in the vicinity of the former Saddle Dam following closure activities.						
		Section 3.4: Revised to include documentation of the original network and basis for the revised network, including the removal of downgradient monitoring well MW-1603.						

ATTACHMENT B References


- AECOM. 2018a. Fly Ash Pond Closure Phase I.
- AECOM. 2018b. Fly Ash Pond Closure Phase II and III.
- AECOM. 2019. Fly Ash Pond Closure Phase III and IV.
- AECOM. 2021. AEP Big Sandy Fly Ash Pond Phase IV 2020-2021 and Final Closure CQA Certification Report.
- AEP. 2015a. Big Sandy Plant: Post-Conversion and Decommissioning Water Balance Flow Diagram (Interim and Final). American Electric Power. May.
- AEP. 2015b. 2015 Inspection Report, Horseford Creek Dam ID#:0367, Saddle Dam, Bottom Ash Complex. September.
- AEP. 2017. Closure Plan, CFR 257.102(b), Fly Ash Pond, Big Sandy Plant, Louisa, Kentucky. American Electric Power. October.
- AEP. 2021. 2021 Annual Dam and Dike Inspection Report, Fly Ash Pond, Big Sandy Plant, Kentucky Power, Louisa, Kentucky. American Electric Power. September.
- CAEP. 2019b. Annual Groundwater Monitoring Report; Kentucky Power Company, Big Sandy Plant, Fly Ash Pond CCR Management Unit, Louisa, Kentucky. American Electric Power. January.
- AEP. 2020. Annual Groundwater Monitoring Report; Kentucky Power Company, Big Sandy Plant, Fly Ash Pond CCR Management Unit, Louisa, Kentucky. American Electric Power. January.
- AEP. 2021a. Annual Groundwater Monitoring Report Revision 1; Kentucky Power Company, Big Sandy Plant, Fly Ash Pond CCR Management Unit, Louisa, Kentucky. American Electric Power.
- AEP. 2021b. Annual Groundwater Monitoring Report; Kentucky Power Company, Big Sandy Plant, Fly Ash Pond CCR Management Unit, Louisa, Kentucky. American Electric Power. January.
- AEP. 2022. Annual Groundwater Monitoring Report; Kentucky Power Company, Big Sandy Plant, Fly Ash Pond CCR Management Unit, Louisa, Kentucky. American Electric Power. January.
- EHS Support, LLC. 2019a. Alternative Source Demonstration Report for Beryllium, Cobalt, and Lithium, Big Sandy Fly Ash Pond, Louisa, Kentucky. February.
- EHS Support, LLC. 2019b. Alternative Source Demonstration Addendum Report for Beryllium, Cobalt, and Lithium, Big Sandy Fly Ash Pond, Louisa, Kentucky. September.
- EHS Support, LLC. 2020. Alternative Source Demonstration Addendum Report for 2019 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky. January.
- EHS Support, LLC. 2021a. Alternative Source Demonstration Addendum Report for the March and June 2020 Monitoring Data, Big Sandy Fly Ash Pond, Louisa, Kentucky. January.


- EHS Support, LLC. 2021b. Alternative Source Demonstration Addendum Report for the October 2020 Monitoring Data. Big Sandy Fly Ash Pond, Louisa, Kentucky. April.
- EHS Support, LLC. 2021c. Alternative Source Demonstration Addendum Report for the March and June 2021 Monitoring Data. Big Sandy Fly Ash Pond, Louisa, Kentucky. November.
- EHS Support, LLC. 2022a. Alternative Source Demonstration Addendum Report for the October 2021 Monitoring Data. Big Sandy Fly Ash Pond, Louisa, Kentucky. March.
- EHS Support, LLC. 2022b. *Alternative Source Demonstration Addendum Report for the March and June 2022 Monitoring Data*. Closed Big Sandy Fly Ash Pond, Louisa, Kentucky. December.
- EHS Support, LLC. 2023. Alternative Source Demonstration Addendum Report for the October 2022 Monitoring Data. Closed Big Sandy Fly Ash Pond, Louisa, Kentucky. May.
- Geosyntec. 2015. Big Sandy Fly Ash Pond: Report on Hydrogeology and Groundwater Quality. Geosyntec Consultants, Inc. June.
- Geosyntec. 2016a. *Monitoring Well Installation Report: Fly Ash Pond*. AEP Big Sandy Plant. Geosyntec Consultants, Inc. October.
- Geosyntec. 2016b. *Groundwater Monitoring Network Evaluation: Big Sandy Fly Ash Pond.* AEP Big Sandy Plant. Geosyntec Consultants, Inc. December.
- Geosyntec. 2017. *Statistical Analysis Plan*. AEP Big Sandy Plant. Geosyntec Consultants, Inc. January.
- Geosyntec. 2018. *Statistical Analysis Summary, Fly Ash Pond.* Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. February.
- Geosyntec. 2019a. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. July.
- Geosyntec. 2019b. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. December.
- Geosyntec. 2020. *Statistical Analysis Summary, Fly Ash Pond.* Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. October.
- Geosyntec. 2021a. *Statistical Analysis Plan, Revision 1*. AEP Big Sandy Plant. Geosyntec Consultants, Inc. January.
- Geosyntec. 2021b. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. February.
- Geosyntec. 2021c. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. October.
- Geosyntec. 2022a. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. February.
- Geosyntec. 2022b. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. October.

- Geosyntec. 2023a. 2022 Annual Groundwater Monitoring Report; Big Sandy Plant Fly Ash Pond, Louisa, Kentucky. Geosyntec Consultants, Inc. January.
- Geosyntec. 2023b. *Statistical Analysis Summary, Fly Ash Pond*. Big Sandy Plant, Louisa Kentucky. Geosyntec Consultants, Inc. February.
- Huddle, J.W., E.J. Lyons, H.L. Smith, and J.C. Ferm. 1963. *Coal Reserves of Eastern Kentucky*. United States Geological Survey Bulletin 1120.
- Kentucky Geological Survey. "Water Well and Spring Location Map." Kentucky Groundwater Data Repository. Accessed September 20, 2023. http://kgs.uky.edu/kgsmap/KGSWater/viewer.asp.
- Lloyd, Jr., O.B., and W.L. Lyke. 1995. Ground Water Atlas of the United States, Segment 10: Illinois, Indiana, Kentucky, Ohio, Tennessee. Hydrologic Investigations Atlas 730-K. United States Geological Survey.
- National Oceanic and Atmospheric Administration. 2023.
- URS. 2012. Geotechnical Summary Report Proposed Pond Closure American Electric Power Big Sand Plant. November.
- URS. 2013a. Final Report Hydrogeologic Site Investigation, AEP Big Sandy, Horseford Creek. URS Corporation. June.
- URS. 2013b. Report Groundwater Monitoring Plan, AEP Big Sandy, Horseford Creek. URS Corporation. June.
- URS. 2013c. Kentucky Power Company, Big Sandy Power Plant Ash Pond Closure Drawings, 100% Submittal. URS Corporation. June.

ATTACHMENT C Geologic Cross Sections

C'







KEY MAP

- 1. SUBSURFACE LITHOLOGIC ELEVATIONS BETWEEN BORINGS ARE INTERPRETED BASED ON AVAILABLE INFORMATION AND SHOULD BE CONSIDERED APPROXIMATE.
- GROUNDWATER ELEVATIONS WERE MEASURED ON JULY 13, 2016. GROUNDWATER ELEVATIONS IN MW-1010, MW-1011 AND MW-1603 WERE MEASURED ON A DIFFERENT DATE.
- SOIL BORING PB-8 AND MONITORING WELLS MW-1010 AND MW-1011 DATA WERE OBTAINED FROM FINAL REPORT HYDROGEOLOGIC SITE INVESTIGATION (URS, JUNE 2013)
- CROSS SECTION REPRESENTS PRE-CLOSURE CONDITIONS.



OCTOBER 2016

ATTACHMENT D Boring Logs and Monitoring Well Construction Diagrams

2012 BORING LOGS AND WELL CONSTRUCTION DIAGRAMS

Project Location: Louisa, KY Project Number: 13815141.10000

Key to Log of Boring/Rock Core


Sheet 1 of 2

	SAMPLES					
Elevation, feet Depth, feet	Type Number Sampling Resist. Blows/6" OR CORE% RQD Recovery, % Pocket Pene- trometer, tsf	Graphic Log	MATERIAL DESCRIPTION		Well Graphic	REMARKS AND OTHER DETAILS
1 2	3 4 5 6 7	8	9	10	11	12
COLUM	N DESCRIPTIONS					


- **<u>Elevation:</u>** Elevation in feet referenced to mean sea level (MSL) or site datum.
- 2 **<u>Depth:</u>** Depth in feet below the ground surface.
- 3 Sample Type: Type of soil sample collected at depth interval shown; sampler symbols are explained below.
- 4 Sample Number: Sample identification number.
- <u>Sampling Resistance:</u> Number of blows required to advance driven sampler each 6-inch interval, or distance noted, using a 5 140-lb hammer with a 30-inch drop.
- 6 **Recovery:** Percentage of driven sample length actually recovered.
- 7 <u>Pocket Penetrometer:</u> Pocket penetrometer field consistency measurement in tons per square foot (tsf).

- **<u>Graphic Log:</u>** Graphic depiction of subsurface material encountered; typical symbols are explained below.
- Material Description: Description of material encountered; may include color, moisture, grain size, and density/consistency.
- 10 Water Content of soil sample measured in laboratory, expressed as percent of dry weight of sample.
- 11 Well Graphic: Diagram of well installation
- Remarks and Other Details: Comments and observations regarding drilling or sampling made by driller or field personnel. Also includes well details and laboratory testing results.

TYPICAL MATERIAL GRAPHIC SYMBOLS



SANDSTONE



TYPICAL WELL GRAPHIC SYMBOLS

Filter Sand	Natural fill
PVC Pipe in Bentonite	PVC Pipe in Bentonite Grout
Bentonite Plug	PVC Pipe in Filter Sand
Slotted PVC Pipe in Filter	

OTHER GRAPHIC SYMBOLS

LIMESTONE

SHALE

First water encountered at time of drilling and sampling (ATD)

Water level at time indicated on log


Minor change in material properties within a lithologic stratum

--- Inferred or gradational lithologic contact

ATD At Time of Drilling NR Not Recorded NA Not Applicable

Soil classifications are based on the Unified Soil Classification System. Descriptions and stratum lines are interpretive; field descriptions may have been modified to reflect lab test results. Descriptions on these logs apply only at the specific boring locations and at the time the borings were advanced; they are not warranted to be representative of subsurface conditions at other locations or times

TYPICAL SAMPLER GRAPHIC SYMBOLS



MINOR SOIL TYPE(s)

Sand

"trace" When the soil type's percentage is estimated, using visual/manual procedures, t be between 1 and 15 percent of the total sample.

When the soil type's percentage is estimated, using visual/manual procedures, t be greater than 15 percent and less than 30 percent of the total sample.

When the soil type's percentage is estimated, using visual/manual procedures, to be greater than 30 percent of the total sample.



Project Location: Louisa, KY
Project Number: 13815141.10000

Key to Log of Boring

Sheet 2 of 2

KEY TO DESCRIPTIVE TERMS USED ON CORE LOGS

DISCONTINUITY DESCRIPTORS

a Dip of discontinuity, measured relative to a plane normal to the core axis.

b <u>Discontinuity Type:</u>

F - Fault J - Joint Sh - Shear Fo - Foliation V - Vein B - Bedding

e Amount of Infilling:

Su - Surface Stain Sp - Spotty Pa - Partially Filled Fi - Filled No - None

Surface Shape of Joint:

- Planar

Wa - Wavy

St - Stepped

- Irregular

h Discontinuity Spacing (feet):

EW - Extremely Wide (>6) W - Wide (2-6) M - Moderate (0.7-2) C - Close (0.2-0.7) VC - Very Close (<0.2)

c Aperture (inches):

W - Wide (0.5-2.0) MW - Moderately Wide (0.1-0.5) N - Narrow (0.05-0.1) VN - Very Narrow (<0.05) T - Tight (0)

d Type of Infilling:

CI - Clay
Ca - Calcite
Ch - Chlorite
Fe - Iron Oxide
Gy - Gypsum
H - Healed

Mn - Manganese Oxide

No - None Py - Pyrite Qz - Quartz Sd - Sand

g Roughness of Surface:

Slk - Slickensided [surface has smooth, glassy finish with visual evidence of striations]

S - Smooth [surface appears smooth and feels so to the touch]

SR - Slightly Rough [asperities on the discontinuity surfaces are distinguishable and can be felt]

 R - Rough [some ridges and side-angle steps are evident; asperities are clearly visible, and discontinuity surface feels very abrasive]

VR - Very Rough [near-vertical steps and ridges occur on the discontinuity surface]

ROCK WEATHERING / ALTERATION

Description

Completely Weathered/Altered

Highly Weathered/Altered

Moderately Weathered/Altered

Description

Slightly Weathered/Altered Fresh/Unweathered

Recognition

Original minerals of rock have been entirely decomposed to secondary minerals, and original rock fabric is not apparent; material can be easily broken by hand

Original minerals of rock have been almost entirely decomposed to secondary minerals, although original fabric may be intact; material can be granulated by hand

More than half of the rock is decomposed; rock is weakened so that a minimum 2-inch-diameter sample can be broken readily by hand across rock fabric

Rock is discolored and noticeably weakened, but less than half is decomposed; a minimum 2-inch-diameter sample cannot be broken readily by hand across rock fabric

Rock is slightly discolored, but not noticeably lower in strength than fresh rock Rock shows no discoloration, loss of strength, or other effect of weathering/alteration

ROCK STRENGTH

Residual Soil

Extremely Weak Rock Very Weak Rock Weak Rock Medium Strong Rock Strong Rock Very Strong Rock Extremely Strong Rock

Recognition

Can be indented by thumbnail
Can be peeled by pocket knife
Can be peeled with difficulty by pocket knife
Can be indented 5 mm with sharp end of pic
Requires one hammer blow to fracture
Requires many hammer blows to fracture
Can only be chipped with hammer blows

Approximate Uniaxial Compressive Strength (psi)

35 - 150 150 - 700 700 - 3,500 3,500 - 7,200 7,200 - 14,500 14,500 - 35,000 > 35,000

Report: GEO_CORE_KEY_P2_; File: AEPBORINGS-DRAFT.GPJ; 5/25/2012 Key

Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-1 (MW-1201)

Sheet 1 of 3

Date(s) Drilled	4/10/12	Logged By	S. Becker	Checked By	J. Lach
Drilling Method	HSA, HQ Wireline Core	Drill Bit Size/Type	6 1/4" HSA/6" OD bit with HQ core	Total Depth of Borehole	49.5 ft
Drill Rig Type	CME 55	Drilling Contractor	Frontz Drilling	Surface Elevation	799.4 ft above msl
Borehole	Backfill Borehole finished as monitoring well MW-1201	Sampling Method(s)	Split-spoon, HQ Wireline	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 252,798.0 E 2,099,724.0	Groundwater Level(s)	Not encountered		


			SAMPL	ES				l		
Elevation, feet	Depth, Feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %		REMARKS AND OTHER DETAILS
F	U-		WOH		1.0		Stiff, moist, brown to reddish brown lean CLAY (CL), trace silt and sand			Grout
-	1- - 2-	SS-1	2 2 3	50	2.0 2.0 3.25		Stiff to very stiff, moist, brown to reddish brown, very fine sandy lean CLAY (CL) [RESIDUUM]	_		SCH 40 PVC 2" diameter riser
-	2- - 3-	SS-2	5 5 5	50	3.5 4.5 3.5		becomes very stiff to hard	17.7		PL=17 LL=35 PI=18 %F=67.9
	4-		7		4.5		_	-		
795 	5— -	SS-3	2 2 5 7	63	1.75 3.0 4.0 3.0		becomes mottled reddish brown and light gray	-		₫
-	6— 7—	SS-4	7 10 11	100	3.5 4.5 4.25		Medium dense, moist, dark reddish brown fine to medium clayey SAND (SC) with trace oxidized sandstone gravel, with tan and light gray mottling [RESIDUUM]	-	NAKANANANANANANANANANANANANANANANANANAN	
_ 	8 9	SS-5	3 6 7 9	92	3.5 >4.5 3.5 >4.5		Very stiff to hard, moist, light gray to light tan, fat CLAY (CH), trace sand [RESIDUUM] 1/4" dark red-brown, highly weathered shale seam			NININININININININININININININININININI
-	10- - 11-	SS-6	2 5 9	92	3.75 4.0 4.25 4.25		- 	-		
	12-	SS-7	50/5"	8	>4.5		becomes gray to light gray	1		
_ _ _785	13- - 14-	R1	24%	50			Quartz SANDSTONE, gray, slight to no weathering, very strong, slight to moderate HCL reaction (4.5"-6"), grading more flaggy and micaceous at 9" Fracture #1: 0, B, N, None ,None, Ir, SR, M			Auger/spoon refusal at 12.5 ft bgs
-	15— - 16—						- -			ININININININININININININININININININININ
-	17—	R2	30%	50			SHALE, gray, slight to moderately weathered, very weak Fracture #2: 0, B, 0, None, None, PI, SR, VC	-		MINININININININININININININININININININ
_ _780	18 - 19							-		NININININININININININININININININININI
	20-	R3	27%	77						
1										

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:02 AM

URS

Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring/Rock Core HB-1 (MW-1201)



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-1 (MW-1201)

Sheet 3 of 3




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-2/SB-1 (MW-1202)


Sheet 1 of 3

Date(s) Drilled 4/13/12	Logged By	S. Becker	Checked By	J. Lach/V. Gautam
Drilling Method HSA, HQ Wireline Core	Drill Bit Size/Type	6 1/4" HSA/6" OD bit with HQ core	Total Depth of Borehole	44.5 ft
Drill Rig Type CME 55	Drilling Contractor	Frontz Drilling	Surface Elevation	849.6 ft above msl
Borehole Backfill Finished as monitoring well MW-1202	Sampling Method(s)	Split-spoon, HQ Wireline	Hammer Data	140#/30" Drop Auto
Boring Location N 254,651.6 E 2,101,180.0	Groundwater Level(s)	Water level @ 28.85 ft bgs		



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-2/SB-1 (MW-1202)




Project Location: Louisa, KY **Project Number:**

13815141.10000

Log of Boring/Rock Core HB-2/SB-1 (MW-1202)

Sheet 3 of 3



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-7/SB-2 (MW-1203)

Sheet 1 of 3


Date(s) Drilled	4/16/12	Logged By	S. Becker	Checked By	J. Lach
Drilling Method	HSA, HQ Wireline Coring	Drill Bit Size/Type	6 1/4" HSA/6" OD bit with HQ core	Total Depth of Borehole	54.5 ft
Drill Rig Type	CME 55	Drilling Contractor	Frontz Drilling	Surface Elevation	728.7 ft above msl
Borehole	Backfill Finished as monitoring well MW-1203	Sampling Method(s)	Split-spoon/Wireline	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 252,205.1 E 2,101,406.0	Groundwater Level(s)	Not encountered		

ſ			SAMPL	ES				Π	
Elevation, feet	Depth, feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
_ _ _	1- 2-	SS-^	3 2 2 4	50	0.75 1.5		Loose, moist, brown clayey SAND (SC), trace sandstone gravel [FILL]	7	PL=18 LL=31 PI=13 %G=8.3 %S=44.5 %F=47.2 SCH 40 PVC 2" diameter
_ _725	3-	SS-2	4 4 5 6	71	3.5 3.0 3.0		Stiff to very stiff, moist, reddish brown, lean CLAY (CL) [FILL] 1" red-brown medium sand seam 2" medium reddish brown sand seam with sandstone fragments		riser
_	4 5	SS-3	3 4 7 7	83	3.5 4.5 4.5 3.5		becomes with sandstone fragments (gravel) with red-brown sand iron-staining	16.7	PL=17 LL=31 PI=15
_	6 7	SS-4	14 15 17 20	92	4.5 4.5 >4.5 >4.5		Dense, dry to moist, red to brown, clayey SAND (SC) with gravel [ALLUVIUM]	-	Iron staining on sand and gravel
-720 -	8- 9- -	SS-5	7 12 13 16	100	4.0 4.0 4.5 4.0		becomes mottled brown and orange	10.4	%G=19.3 %S=49.8 %F=30.9
- -	10- - 11-	SS-6	5 13 14 12	100			becomes increasing sand and gravel content -		
_ _715	12- - 13-	SS-7	11 17 27 17	92	3.5 3.25 3.5 >4.5		Very stiff to hard, moist red-brown fat CLAY (CH) trace sand and gravel [ALLUVIUM]	17.6	
_	14- - 15-	SS-8	3 6 10 8	100	1.0 2.0 3.0		Medium stiff to stiff, moist, red-brown silty, clayey SAND (SC-SM) with weathered sandstone gravel [ALLUVIUM]	1	
 - -	16— 17— - 18—	SS-9	23 15 13 12	83	1.0 3.0 2.5 3.5		- 2" sandstone fragment in spoon	7	PL=15 LL=20 PI=5 %G=16.6 %S=53.6 %F=29.8
_710 _	19— 19— 20—	SS-1	4 3 6 6	63			Loose, moist to wet, red-brown clayey SAND (SC), trace sandstone gravel [ALLUVIUM]	-	

Report: GEO_CR_WELL; File K;NPROJECTSVA/AEP/13815141_BSLF/DOCS/LOGS/AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:25 AM

Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring/Rock Core HB-7/SB-2 (MW-1203)



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-7/SB-2 (MW-1203)

Sheet 3 of 3




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-4/SB-5 (MW-1204)


Sheet 1 of 2

Date(s) Drilled	4/18/12	Logged By	J. Lach	Checked By	V. Gautam
Drilling Method	HSA, HQ Wireline Coring	Drill Bit Size/Type	6 1/4" HSA, 6" OD bit with HQ core	Total Depth of Borehole	35.0 ft
Drill Rig Type	CME 550 Truck	Drilling Contractor	Frontz Drilling	Surface Elevation	721.3 ft above msl
Borehole	Backfill Finished as monitoring well MW-1204	Sampling Method(s)	Split-spoon, HQ Wireline	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 252,025.3 E 2,102,075.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-4/SB-5 (MW-1204)




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-5 (MW-1205)


Sheet 1 of 3

Date(s) Drilled	4/19/12	Logged By	S. Becker	Checked By	J. Lach
Drilling Method	HSA, HQ Wireline Coring	Drill Bit Size/Type	6 1/4" HSA/6" OD bit with HQ core	Total Depth of Borehole	54.5 ft
Drill Rig Type	CME 55	Drilling Contractor	Frontz Drilling	Surface Elevation	714.3 ft above msl
Borehole	Backfill Finished as monitoring well MW-1205	Sampling Method(s)	Split-spoon, HQ Core	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 251,131.0 E 2,104,397.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring/Rock Core HB-5 (MW-1205)



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core HB-5 (MW-1205)

Sheet 3 of 3




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring HB-3 (MW-1206)

Sheet 1 of 6

Date(s) Drilled	4/23/12	Logged By	S. Becker	Checked By	J. Lach
Drilling Method	Rotosonic (No vibration), Wireline	Drill Bit Size/Type	8.0" ID steel casing, 4.0" ID core barrel	Total Depth of Borehole	124.5 ft
Drill Rig Type	Versa-Sonic	Drilling Contractor	Frontz Drilling	Surface Elevation	695.4 ft above msl
Borehole	Backfill Finished as monitoring well MW-1206	Sampling Method(s)	Rotosonic Core Barrel	Hammer Data	Not Applicable
Boring Lo	ocation N 251,617.9 E 2,104,243.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-3 (MW-1206)

	SAMPLES								Ιt		
Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content	9,	REMARKS AND OTHER DETAILS
-675	20-							-			
_	21-										– Bentonite chips
_	22-								$\frac{1}{1}$		
	23-							- -			_ SCH 40 PVC 2" diamete
_	24-							- 			riser
_	25-							- 			
-670	26-										
-	-							- -	-		
_	27-							-			
_	28 -							- -			
_	29-							<u> </u>			
-665	30-										
_	31-							_	-		
	32-							- - -			
_	33-							- 			
_	34-							- 			
_	35-										
-660	36-							-			
-	-							_			
-	37- -	1						- -	1		
_	38-							<u>-</u> -	1		
_	39-							<u></u>			
-655	40-								}		
_	41-								-		
	42-	1						- -			
_	43-	1						<u>-</u> -	1		
				. '		•					

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-3 (MW-1206)

Sheet 3 of 6

feet feet 1	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %			REMARKS AND
-					ان		Wate %			OTHER DETAILS
I5-						. -				
-						-				- Bentonite chips
16-						-	-			- Bentonite Chips
17-						-				– SCH 40 PVC 2" diamete
18-						-				riser
19-						-				
50-						-	-			
51-						-	-			
52-						· -	-			
53-						· -				
54-						- -				
55-						_ -				
56-						- -				
57-						- -				
58-						- -				
59-						· -				
60-						- -				
51-						· _				
52						- -				
33-						_ -				
64-						<u> </u>				
65 <u> </u>						_				
66-						<u>-</u>				
	18	18- 19- 19- 51- 52- 53- 54- 55- 56- 57- 58- 59- 51- 52- 53- 54- 52- 53- 54- 55- 55- 56- 57- 58- 59- 51- 52- 53- 54- 55- 56- 56- 56- 56- 56- 56- 56- 56- 56	18	18- 19- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 58- 58- 58- 58- 58- 58- 58	18- 19- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 58- 58- 58- 58- 58- 58- 58	18- 19- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 59- 50- 51- 52- 53- 54- 55- 56- 57- 58- 58- 58- 58- 58- 58- 58- 58	18	18	18- 19- 10- 11- 13- 13- 13- 13- 13- 13- 13	

Project Location: Louisa, KY
Project Number: 13815141.10000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:14 AM

Log of Boring HB-3 (MW-1206)

Sheet 4 of 6


SAMPLES SAMPLES									Sneet 4 01 6					
Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DE	SCRIPTION	Water Content %			REMARKS AND OTHER DETAILS	
_	67 <u> </u>								_				Bentonite chips	
_	68 -							_	_					
-	69- -								-				 SCH 40 PVC 2" diameter riser 	
625	70-								_					
	71-							_	-					
	72 -							-	_					
	73-								-					
	74 -							-	-					
620	75- -							-	_					
	76							-	_					
	77 –							-						
	78- -							-	-					
	79-							-	_					
615	80-							-						
	81— -								-					
-	82- -								_					
	83- -								-					
	84-								-					
610	85— -								-					
	86 <u> </u>							<u></u>	-					
-	87— -							 - -	 -					
	88-							<u></u>	-					
	89— -							<u></u>	-					
	90-	:		<u> </u>		1	1	1		:	Ø		1	

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-3 (MW-1206)


Sheet 5 of 6



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring HB-3 (MW-1206)

Sheet 6 of 6




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 1 of 8

Date(s) Drilled	4/24/12	Logged By	S. Becker	Checked By	J. Lach
Drilling Method	Rotosonic (No vibration), Wireline HQ	Drill Bit Size/Type	8" ID steel casing, 6" OD bit HQ Wireline	Total Depth of Borehole	166.0 ft
Drill Rig Type	Vibra-Sonic	Drilling Contractor	Frontz Drilling	Surface Elevation	695.0 ft above msl
Borehole	Backfill Finished as monitoring well MW-1207	Sampling Method(s)	HQ Wireline	Hammer Data	Not applicable
Boring Lo	ocation N 251,598.3 E 2,104,256.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

<u>ر</u>				SAMPL igi	<u> </u>		ρ		tent		
Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %		REMARKS AND OTHER DETAILS
-675	20-		_	0, 🖽 🔾					120	1	
-	21-							- 		INININININININININININININININININININ	SCH 40 PVC 2" diamet
_	22-							- 			Bentonite grout
_	23-							- -			
_	24-							- -	_		
-670	25-							- 	-		
_	26-							- 	-		
-	27-	1						- 	-	ninininininininininininininininininini	
_	28-							- -			
_	29-							- -			
-665	30-							- 			
_	31-							- 			
_	32-							-			
	33-							-	_		
	-							-			
_	34-							-			
-660	35-							- -			
_	36-							-			
_	37-	1						- -	-		
_	38-	1						 -	-		
-	39-							<u>-</u> -	-		
-655	40-	1						<u>-</u> -	-		
-	41-							<u>-</u> -	-		
-	42-	1						 -		KININGKININGKINGKINGKINGKINGKINGKINGKING	
_	43-								4		

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)


Number Sampling Re.	Sampling resist. Blows/6" OR CORE% RQD Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DES		Water Content %	AIRAKINININININININININININININININININININ	REMARKS AND OTHER DETAILS SCH 40 PVC 2" diameter riser Bentonite grout
			- - - - - - - - - - - - - - - - - - -		- - - - - - - - - - - - - - - - - - -		AIRAKIRININININININININININININININININININI	– SCH 40 PVC 2" diamete riser – Bentonite grout
			- - - - - - - - - - - - - - - - - - -		- - - - - - - - - - - - -		AIRININININININININININININININININININI	riser – Bentonite grout
			- - - - - - - - - - - - - - - - - - -		- - - - - - - - - -		NININININININININININININININININININI	– Bentonite grout
			- - - - - - - - - - - - - - - - - - -		- - - - - - - - -		NINDER NEUTRINGERINGERINGERINGERINGERINGERINGERINGE	• • • • • • • • • • • • • • • • • • •
			- - - - - - - - - - -		- - - - - - - -			
			- - - - - - - - -		- - - - - -			
			- - - - - - -		- - - - -			
			- - - - -		- - - -	NINININININININININININININININININININI		
			- - - -		-			
			-			ı (≅		
					-			
			-		-			
			-		-			
			-		-			
					-	N N N		
			-		-			
			-		-			
					-			
					-			
					-			
					-			
					-			
					-			
					-			

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 4 of 8



Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 5 of 8

ć.				SAMPL ig			စ္ခ		ent		
Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %		REMARKS AND OTHER DETAILS
_	91-							- 		KIRININININININININININININININININININI	COLL 40 DVC 211 diament
_	92-							- 			- SCH 40 PVC 2" diameter riser - SCH 40 PVC 2" diameter riser
_	93-							- 	-		_
_	94-							- 			- Bentonite grout
-600	95-							- 			
_	96-							- 	_		
_	97-							- 	-	MINININININININININININININININININININ	
_	98-							- 			
_	99-							- 	-		
-595	100-							- -	-		
_	101-							- -	-		
_	102-							- -	-		
_	103-								-		
_	104-							- -	-		
-590	105-							- 	-		
_	106-							- 	-		
-	107-							- -	-		
_	108-	-						- 	-	KKIKINIKIKIKIKIKIKIKIKIKIKIKIKIKIKIKIKI	
_	109-							- 	-		
-585	110-							- -	-		
_	111-							- -	-		
-	112-							- 	-		
_	113-							- 	-		

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 6 of 8

				SAMPL	ES					<u></u>		
Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION		Water Content %		REMARKS AND OTHER DETAILS
_	114-							_	-		MAKINININININININININININININININININININ	SCH 40 PVC 2" diameter
-580	115-							- -	_			riser Bentonite grout
-	116-							- - -				
_	117-							- -	-			
-	118-							- -	_			
-	119							- - -	-			
-575	120-							- - -	-			
-	121-							- -	-			
_	122							- -	-			
-	123-							- -	-			
-	124-							- -	-			
-570	125-							- -	-			
-	126-	 11						No recovery 126-131. Driller notes "softer material"	_			
-	127-							-	-			
-	128-		04	00/	0			- -	-			
-	129-		Q1	0%	0			- -	-			
-565	130-							- -	_			
-	131-	\parallel						No recovery 131-136. Shale cuttings	_			
-	132-							_ -	-			
-	133-	1.22	Q2	0%	0			_	-			
_	134-		. 4∠	U%	0			- - -	-			
-560	135-							- -	-			
-	136-	Н	Q3	18%	80			SHALE, light gray to gray, moderately weathered, very to extremely weak				


Report: GEO_CR_WELL; File K:\PROJECTS\AMEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:22 AM

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 7 of 8




Project Location: Louisa, KY

Report. GEO_CR_WELL; File K:\PROJECTS\AVEP\13815141_BSLF\DOCS\LOGS\AEPBOR\NGS-6-10-13.GPJ; 6/10/2013 11:23:23 AM

Project Number: 13815141.10000

Log of Boring HB-6 (MW-1207)

Sheet 8 of 8



Project Location: Louisa, KY
Project Number: 13815141.10000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:28 AM

Log of Boring PB-1

Sheet 1 of 3


Date(s) Drilled	4/18/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method	Rotary/Water	Drill Bit Size/Type	4"	Total Depth of Borehole	57.0 ft
Drill Rig Type	Acker	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	Top of water el. 695.1 ft above msl
Borehole	Backfill Cement Bentonite Grout	Sampling Method(s)	Piston tube/Split-spoon	Hammer Data	140#/30" Manual drop
Boring Lo	ocation 38°10'57.4" N 83°38'41.3" W	Groundwater Level(s)	0' bgs		

			SAMPL	ES								
Elevation, feet	Depth, feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log		MATERIAL	DESCRIPTION		2	REMARKS AND OTHER DETAILS
- 695	0						Water			<u> </u>		Barge drilling- water @ 695.1.
	1-						_			_		
	-						-			-		
-	2-						_					
	3-						_					
	-						_			-		
-	4-						_			-		
—690	5-						- 					
_090	-						_			-		
-	6-						_			-		
	7-						_					
Г	'						_			-		
-	8-						-			-		
	9-						_					
	9-						_					
-685	10-						_			_		
	44						-			-		
	11-						_			_		
L	12-						_			_		
							_			-		
 	13						_					
	14-						_			_		
	-						-			-		
-680	15-						_			7		
	16						_					
	-									-		
-	17-						_			-		
	18-						_					
	-						_			-		
-	19						_			-		
	20											
	20							TIR:				

Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-1

Sheet 2 of 3



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-1

Elevation, feet	Depth, feet	Type	Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DES	SCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
	-	F	Ż	\(\mathrea{\text{B}}\) \(\text{B}\) \(\text{C}\)	Δ.	2.0	0	Soft, moist, dark gray, lean CLAY (C	:L) [ALLUVIUM] -	\$%	
_	44-	N				2.0		Soft, moist, dark gray, lean CLAY (C becomes stiff, yellow, some sand,	trace gravel		
-650	45-			3			////	 becomes very stiff, yellow brown w staining, with sand, trace gravel 	ith orange iron —		
_	46-	. ا	SS-3	3 4	38	2.5		-	- 		
_	47-			5				-	_		
	48-							_	_		
_	-								-		
-	49-							-	-		
-645	50- -			6				becomes stiff to very stiff, sandy, t	race gravel –		
-	51-	1	SS-4	7 12	33	1.0 2.5		-	_		
_	52-			12				-	_		
_	53-							-	_		
_	54-							Shale, gray, dry, crushed			Drilling change encountered @ 53.5 ft bgs
-640	55-							-	-		290
-040	-	1	20.5	45	22				-		
_	56- -		SS-5	50/2"	33			-	-		
-	57 -						-	End of Boring at 57	bgs -		
_	58-							-	-		
_	59-							-	_		
-635	60-							-	_		
_	61-							-	- -		
_	62-						-	-	<u>-</u>		
	63-							_	_		
_	-								-		
_	64-							-	-		
-630	65- -							-	-		
-	66-							-	_		

Project Location: Louisa, KY
Project Number: 13815141.10000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:29 AM

Log of Boring PB-2

Sheet 1 of 4

Date(s) Drilled 4/17/12-4/18/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method Rotary/Water	Drill Bit Size/Ty		Total Depth of Borehole	77.0 ft
Drill Rig Type Acker	Drilling Contract	tor Pennsylvania Drillin	Surface Elevation	Top of water el. 695.1 ft above msl
Borehole Backfill Bentonite chips	Samplir Method	(š) Pistori/Spiit-spoori/s	Shelby-tube Hammer Data	140#/30" Manual drop
Boring Location 38°10'52.5" N 83°	Groundy Level(s)	water 0 ft bgs		

			SAMPL	ES						T., T	
Elevation, feet	Depth, feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log		MATERIAL DES	SCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
-695	0-						Water				Pond elevation - 695.1 ft
L	1-						_		-	_	
	-						-			-	
-	2-						_		-		
L	3-						_		-]	
	-						_			-	
F	4-						_		-	-	
000	5-						_		_]	
- 690	J _						- -			_	
-	6-						_		-	-	
	-						_			-	
r	7-						_		-]	
L	8-						_		-	-	
	-						_			-	
-	9-						_		-]	
-685	10-								-	_	
	-						-			-	
F	11-						_		-	1	
L	12-						_		-]	
							_			-	
F	13-						_		-	-	
	- 14-						_			-	
 	14						_]	
-680	15-						_		-	-	
	-						_			-	
F	16-								-]	
L	17-						_		-		
	-						_			-	
-	18-						_		-		
	19-						-		-]	
	-						_			-	
	20										
L											J

Project Location: Louisa, KY
Project Number: 13815141.1000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBOR\NGS-6-10-13.GPJ; 6/10/2013 11:23:29 AM

13815141.10000 Sheet 2 of 4


Log of Boring PB-2

SAMPLES Water Content % Sampling Resist. Blows/6" OR CORE% RQD Graphic Log Elevation, feet Pocket Pene-trometer (tsf) Recovery, **REMARKS AND** MATERIAL DESCRIPTION Depth, feet Number OTHER DETAILS Type 20 -675 21 22 23 Pond bottom @ 23' bgs Soft sediments 24 25 -670 Casing sank to 25' Very loose, wet, gray bottom ash as medium to fine SAND 2 (SP-SM) with some gravel and shale fragments, trace plant fragments [BOTTOM ASH] 26 SS-1 17 2 3 27 28 29 30 -665 Loose, wet, fly ash as silty SAND (SM), light and dark * ***** laminations [FLY ASH] 31 0 * ✡ 32 \$ 1 blow for 24 inches 1 ✡ 0 33 SS-2 0 0 ✡ ** 0 34 35 -660 36 * 37 ✡ ~ ф 38 ✡ P-2 91 ✡ ** 39 *** *** 40 -655 1 SS-3 27 1 41 2 ***** 42 ✡

Project Location: Louisa, KY
Project Number: 13815141.100

13815141.10000

Log of Boring PB-2




Project Location: Louisa, KY
Project Number: 13815141.10000

Report. GEO_CR_WELL; File K:\PROJECTS\AVEP\13815141_BSLF\DOCS\LOGS\AEPBOR\NGS-6-10-13.GPJ; 6/10/2013 11:23:30 AM

Log of Boring PB-2

Sheet 4 of 4




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-3

Sheet 1 of 5


Date(s) Drilled	4/9/12-4/10/12	Logged By	T. George	Checked By	V. Gautam
Drilling Method	HSA, Mud rotary with recirculated mud	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricore mud-rotary	Total Depth of Borehole	93.0 ft
Drill Rig Type	CME 55 Track Mounted and ATV-remote control	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	698.3 ft above msl
Borehole	set w/ grout	Sampling Method(s)	Split-spoon/Piston/Shelby-tube	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 251,582.4 E 2,102,704.0	Groundwater Level(s)	4' ATD		



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-3

Sheet 2 of 5



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-3



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-3

Sheet 4 of 5




Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring PB-3

Sheet 5 of 5




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-4

Sheet 1 of 5


Date(s) 4/11/12-4/13/12	Logged By	T. George	Checked By	V. Gautam
Drilling Method HSA, Mud rotary	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricone bit	Total Depth of Borehole	112.2 ft
Drill Rig CME 55 Rubber Track ATV, Remote control	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	700.0 ft above msl
Borehole Backfill 2" PVC riser pipe set with grout	Sampling Method(s)	Piston/Split-spoon/Shelby-tube	Hammer Data	140#/30" Drop Auto
Boring Location N 251,302.5 E 2,103,601.0	Groundwater Level(s)	Encountered at 7.6' bgs ATD		



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-4

Sheet 2 of 5



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-4



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-4


Sheet 4 of 5



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-4

Sheet 5 of 5




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-5

Sheet 1 of 3


Date(s) Drilled	4/13/12,4/16/12	Logged By	T. George	Checked By	V. Gautam
Drilling Method	HSA, Mud rotary	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricone bit	Total Depth of Borehole	57.1 ft
Drill Rig Type	CME 55 Rubber Track ATV, Remote control	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	700.9 ft above msl
Borehole	Backfill 2" SCH 40 PVC riser grouted in place	Sampling Method(s)	Piston/Split-spoon	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 251,174.1 E 2,103,663.0	Groundwater Level(s)	Encountered 8' bgs ATD, W.L. @ 10.5	bgs on 4/16	/12



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-5

Sheet 2 of 3



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-5


Elevation, feet Depth.	feet Type	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %		REMARKS AND OTHER DETAILS
	SS-7	5	54			to fine SAND (SP-SM), with completely weathered sandstone gravel [ALLUVIUM]	-		l ose mud return betwee
- 2	17 	3 4 5	75			Loose, moist, dark brown, clayey SAND (SC) to sandy lean CLAY (CL) with decayed plant matter [ALLUVIUM] Loose, moist, light brown, medium to fine SAND (SP-SM) with gravel as completely weathered sandstone [ALLUVIUM]	 		Lose mud return betwee 42-47' bgs
- (19 50 51	10				 - 	- - - -		
- (52 53 SS-9	22 38 46 50/2"	85			Very dense, moist, brown with gray mottling, oxidation staining, silty SAND (SM) as completely to highly weathered sandstone [RESIDUUM]	- - -		%G=4.0 %S=56.6 %F=39.4
- (54- 55- 56-	30/2				Sandstone, fine to medium, gray, slightly weathered to fresh, medium strong	-		
-	57 SS-10	0∫\ 50/1/4"∫	100			End of Boring at 57.1′ bgs	-		Set PVC casing at 57' bgs. Cement-bentonite grout placed using tren pipe
- (59- 60- 61-					 - - -	- - - -		
- (52- 53-					- - - -	- - - -		
- (64- 65- 66-					 - -	- - - -		

Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-6

Sheet 1 of 5


Date(s) Drilled	4/2/12	Logged By	T. George	Checked By	V. Gautam
Drilling Method	HSA, Mud rotary	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricone bit	Total Depth of Borehole	100.0 ft
Drill Rig Type	CME 55 Track Mounted Remote-control	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	698.6 ft above msl
Borehole Backfill 2" SCH 40 PVC riser grouted in place		Sampling Method(s)	Piston/Split-spoon/Shelby-tube	Hammer Data	140#/30" Drop Auto
Boring Location N 251,301.0 E 2,103,083.0 Groundwater Level(s) Not encountered					



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-6

Sheet 2 of 5



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-6



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-6


Sheet 4 of 5



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-6

Sheet 5 of 5




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-7

Sheet 1 of 6


Date(s) 4/17/12-4/19/12	Logged By	T. George	Checked By	V. Gautam
Drilling Method HSA, Mud rotary	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricore mud-rotary	Total Depth of Borehole	127.0 ft
Drill Rig Type CME 55 Tracked ATV	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	695.3 ft above msl
Borehole Backfill 2" SCH 40 PVC riser grouted in place	Sampling Method(s)	Piston/Split-spoon	Hammer Data	140#/30" Drop Auto
Boring Location N 251,635.0 E 2,104,228.0	Groundwater Level(s)	Encountered 8' ATD		



Project Location: Louisa, KY
Project Number: 13815141.10000


Log of Boring PB-7

Sheet 2 of 6



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-7




Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring PB-7


Sheet 4 of 6



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-7


Sheet 5 of 6



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-7

Sheet 6 of 6




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8

Sheet 1 of 7


Date(s) Drilled	4/20/12,4/23/12-4/25/12	Logged By	T. George	Checked By	
Drilling Method	HSA, Mud rotary	Drill Bit Size/Type	4 1/4" ID/8" OD HSA, 4" tricore mud-rotary	Total Depth of Borehole	153.0 ft
Drill Rig Type	CME 55 Rubber Track ATV, Remote control	Drilling Contractor	Pennsylvania Drilling	Surface Elevation	674.0 ft above msl
Borehole	Backfill 2" SCH 40 PVC riser grouted in place	Sampling Method(s)	Piston/Split-spoon	Hammer Data	140#/30" Drop Auto
Boring Lo	ocation N 253,100.3 E 2,105,679.0	Groundwater Level(s)	3.1 ft ATD		



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8


Sheet 2 of 7



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8


Sheet 3 of 7



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8


Sheet 4 of 7



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8


Sheet 5 of 7



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8


Sheet 6 of 7



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring PB-8

Sheet 7 of 7




Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core SB-3

Sheet 1 of 3


Date(s) Drilled 4/11/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method HSA/NX Core	Drill Bit Size/Type	3 1/4" HSA/2" Core	Total Depth of Borehole	54.0 ft
Drill Rig Type D-120	Drilling Contractor	AEP	Surface Elevation	845.7 ft above msl
Borehole Backfill Bentonite grout	Sampling Method(s)	Split-spoon/NX Core	Hammer Data	140#/30" Drop Auto
Boring Location N 253,542.1 E 2,102,379.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core SB-3

Sheet 2 of 3




Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-3

Sheet 3 of 3



Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core SB-4

Sheet 1 of 2

Date(s) Drilled 4/10/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method HSA	Drill Bit Size/Type	3 1/4" HSA/NX Core	Total Depth of Borehole	30.0 ft
Drill Rig Type D-120	Drilling Contractor	AEP	Surface Elevation	794.0 ft above msl
Borehole Backfill Bentonite grout	Sampling Method(s)	Split-spoon/NX Core	Hammer Data	140#/30" Drop Auto
Boring Location N 251,829.7 E 2,101,718.0	Groundwater Level(s)	Not encountered		


		SAMPL	ES				1	
Elevation, feet Depth, feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
- 1- - 2-	SS-1	3 4 5 9	21			Stiff, moist, light brown with gray mottling lean CLAY (CL) [RESIDUUM] -	23.8	
- 3 790 4 -	SS-2	4 6 10 22	67			becomes very stiff with no mottling	- - 20.2	PL=23 LL=45 PI=22 %F=96.5
- 5- - 6- - 7-	SS-3	5 15 26 50/1"	89			becomes with gray mottling becomes buff to tan, sandy Sandstone, light brown to tan, moderately weathered, strong, mica on split surfaces	12.6	
- 8 -	- - - R1	84.7%	100			Fracture #1: 0, B, VN, CL, Sn, Wa, S, C Shale, brown, extremely weak Fracture #2: 90, J, VN, Fe, Fi	- - - -	
- 6 7 8785 9 10 11 12 13780 14 15-	R2	50%	60			becomes orange-stained 1" sandstone, strong becomes with iron staining, orange to gray, extremely weak Sandstone, dark brown, strong, quartz crystal lined, iron stained Fracture #1 Fracture #3: 90, B, VN, Fe, Pa, Ir	- - - - - -	
- 15- - 16- - 17- - 18- - 775 19- - 20-	- R3	56.7%	61			becomes fine-grained, iron staining Fracture #1 Fracture #3 Fracture #3 Shale, gray to black, extremely weak		

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-4

Sheet 2 of 2



Project Location: Louisa, KY
Project Number: 13815141.10000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:52 AM

Log of Boring/Rock Core SB-6

Sheet 1 of 2

Date(s) 4/12/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method HSA/NX Core	Drill Bit Size/Type	3 1/4" HSA/2" Core	Total Depth of Borehole	39.3 ft
Drill Rig Type D-120	Drilling Contractor	AEP	Surface Elevation	768.8 ft above msl
Borehole Backfill Bentonite grout	Sampling Method(s)	Split-spoon/NX Core	Hammer Data	140#/30" Drop Auto
Boring Location N 251,202.5 E 2,102,399.0	Groundwater Level(s)	Not encountered		

			SAMPLI	ES				Ī	
Elevation, feet	Depth, feet	l ype Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
_	1-	SS-1	4 3 7 6	38	2.25		1" dark brown topsoil Stiff, moist, light brown with trace dark brown mottling, fat CLAY (CH) [RESIDUUM] 2" sandstone gravel		
_ 765	3-4-	SS-2	2 3 5 11	58	2.25 to 3.25		becomes stiff to very stiff, with brown mottles 2" cemented shale with red/orange iron stains	26.3	PL=23 LL=62 PI=37 %F=89.6
_	5 6- 7-	SS-3	3 5 9 22	83	>4.5		becomes hard - becomes black	29.5	PL=30 LL=59 PI=29
_ _760	8- 9-	SS-4	19 25 21 38	96	>4.5		9" coal seam - becomes with coal	- - - -	
-	11-	SS-5	12 21 27 50/3"	100	2.5		5 1/2" coal seam becomes stiff, black and gray 2 1/2" coal seam becomes with black coal	- - - -	
_ 755	13-	SS-6	30 50/5"	100			3" coal seam 3" shale, light gray, very weathered 3" coal seam Shale, gray with some black partings		
<u> </u>	15	SS-7	49 50/3"/	100			- - - -	_ - - -	
- - -750	18-	R1	70.7%	97			becomes light gray, moderately weathered, weak	- - -	Back of spoon wet Auger refusal @ 17.2' bgs
	19— 20	KI	70.7%	91			Fracture #1: 60, V, N, CI, Fi, Wa, R		

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-6

Sheet 2 of 2


<u>ر</u>			SAMPL	<u>ES</u>	Ι.			ent	
Elevation, feet		Type	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
	20-						Fracture #2: 90, V, N, Cl, Fi, Wa, R		
_	21-							-	
-	22-	R1	70.7%	97			becomes sandy shale	-	Interbedded sandy shal and shale interbeds with
_	23-						- -]	Interbedded sandy shal and shale interbeds with sand are 3" to 1/8" - sha beds are 1/8 to 1 1/2" thick
-745	24-						- 	-	
_	25-						- 	_	
_	26-						Fracture #3: 30 to 90, J, N, None, None, Ir, Vr Fracture #3	-	
_	27-						- 	_	
_	28-						- -	_	
-740	-						-	_	
_	29-	R2	61.6%	98			Sandstone, light gray, some lamination, some iron staining, slightly weathered, strong rock	_	
_	30-						-	-	
_	31 <u> </u>							-	
	32- -						- -	-	
_	33 <u> —</u>						 -	-	
-735	34-	╂—					 -	_	
_	35-						- Shale, gray, moderately weathered, weak rock	_	
_	36-						_	_	
-	37-	R3	100%				Sandy shale, light gray, slightly weathered, strong rock, interbeds of sandy shale and shale]	
-	38-						- -	-	
-730	39 <u> </u>						- 	-	
_	40-						End of Boring at 39.3′ bgs		
_	41-						- 	_	
_	42-						- -	_	
_	-						-	-	
	43-				<u> </u>			<u> </u>	

Project Location: Louisa, KY
Project Number: 13815141.10000

Log of Boring/Rock Core SB-7

Sheet 1 of 2

Date(s) d/10/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method HSA/Core	Drill Bit Size/Type	3 1/4" HSA/3" Core	Total Depth of Borehole	29.7 ft
Drill Rig Type D-120	Drilling Contractor	AEP	Surface Elevation	850.4 ft above msl
Borehole Backfill Bentonite grout	Sampling Method(s)	Split-spoon/NX Core	Hammer Data	140#/30" Drop Auto
Boring Location N 252,280.4 E 2,103,342.0	Groundwater Level(s)	Not encountered		



Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-7

Sheet 2 of 2

ion,			Sesist. OD QD	<u>ES</u> %	ne- lsf)	Log	MATERIAL DECORPTION	ontent	DEMARKO AND
Elevation, feet		Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	Water Content %	REMARKS AND OTHER DETAILS
-830	20 - 21-							-	
_	21-								Shale is mechanically broken no fractures observable
_	23-	R2	0%	18			_		
-	24-						_		
_	25—	_					becomes brown shale, moderately weathered, weak		25 27! has shale is
-825	26-						-	-	25-27' bgs: shale is softmechanically broke No fractures observable
_	- 27-	R3	20%	20			-	-	
_	_ 28-	Ro	20%	20			-	-	
_	- 29-						-	-	
-	30-	<u> </u>					End of Boring at 29.7' bgs	-	
-820	31						-	-	
_	32-						-	-	
_	33-						-		
_	34						-	-	
-815	35-						-		
-	36						-	-	
_	37-						-		
-	38-						-	_	
-	39-						-	-	
-810	40-						-	-	
_	41-						-	-	
_	42-						-	-	
	43-					-	-	<u> </u>	

Project Location: Louisa, KY
Project Number: 13815141.10000

Report: GEO_CR_WELL; File K:\PROJECTS\A\AEP\13815141_BSLF\DOCS\LOGS\AEPBORINGS-6-10-13.GPJ; 6/10/2013 11:23:54 AM

Log of Boring/Rock Core SB-8

Sheet 1 of 3

Date(s) 4/12/12	Logged By	J. Ristow	Checked By	V. Gautam
Drilling Method HSA	Drill Bit Size/Type	3 1/4" HSA/NX Core	Total Depth of Borehole	49.3 ft
Drill Rig Type D-120	Drilling Contractor	AEP	Surface Elevation	711.3 ft above msl
Borehole Backfill Bentonite grout	Sampling Method(s)	Split-spoon/NX Core	Hammer Data	140#/30" Drop Auto
Boring Location N 251,071.0 E 2,103,738.0	Groundwater Level(s)	Not encountered		


			SAMPL	ES				Τ.	.	
Elevation, feet	Depth, feet	Type Number	Sampling Resist. Blows/6" OR CORE% RQD	Recovery, %	Pocket Pene- trometer (tsf)	Graphic Log	MATERIAL DESCRIPTION	tactac CrotoN	water content	REMARKS AND OTHER DETAILS
_ _710	1- 2-	SS-1	4 3 5 15	58	3.25 to 3.5		3" Bottom ash (road fill) Very stiff, moist, light yellow/brown, lean CLAY (CL) [RESIDUUM] Shale, light yellow brown, with orange red iron oxidation staining, completely to moderately weathered	/ <u>_</u>		
_	3- 4-	SS-2	9 6 8 13	13			· - - -	-		
_ _705	5— 6— 7—	SS-3	9 19 31 34	96			- - - -	-		
- - -	8- 9-	SS-4	11 21 32 50	58			becomes light gray, without iron oxidation	-		
_ 	10- 11-	SS-5	10 18 47 50/3"	76			becomes with red mottle staining becomes red with gray mottles	-		
_	12- 13- 14-	SS-6	21 49 50/3"	80			2" crushed chert nodules becomes gray with red mottles to light gray	- - -		
_ 695	15— - 16—	SS-7	15 18 50/3"	80			becomes gray with some red mottles	-		
_	17- 18-	SS-8	12 50/5"	100			becomes with some orange mottles	-		
-	19- - 20-						TDC	_		

Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-8

Sheet 2 of 3




Project Location: Louisa, KY

Project Number: 13815141.10000

Log of Boring/Rock Core SB-8

Sheet 3 of 3






BORING AND WELL LOG LEGEND

engineers | scientists | innovator

LITHOLOGY
WATER LEVEL
WELL/BORING
COMPLETION
SAMPLE TYPE

DESCRIPTION



NOTES:

Lab Sample and ID



engineers | scientists | innovators

Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1601

Page: 1 of 5

Drilling Start Date: 04/25/2016
Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 84
Boring Diameter (in): 8

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

DTW After Drilling (ft): 46.0

Top of Casing Elev. (ft msl): 716.59

Location (X,Y): 2104798.67, 254131.13*

Well Depth (ft): 77


Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted

Seal Material(s): Bentonite Pellets
Filter Pack: Global Filter Pack #5





engineers | scientists | innovator

Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1601

77

0.010

Page: 2 of 5

Well Depth (ft):

Screen Slot (in):

Riser Material:

Well Diameter (in): 4

Drilling Start Date: 04/25/2016
Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 84
Boring Diameter (in): 8

Bonng Diameter (III). 6

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

DTW After Drilling (ft): 46.0

Top of Casing Elev. (ft msl): **716.59** Location (X,Y): **2104798.67**, **254131.13***

46.0 Screen Material:


Sea

Sch 40 PVC Slotted

Sch 40 PVC

Seal Material(s): Bentonite Pellets

Filter Pack: Global Filter Pack #5





Client: **American Electric Power**

Project: **Big Sandy Plant**

Boring Depth (ft):

Boring Diameter (in):

Sampling Method(s):

DTW During Drilling (ft):

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1601

Page: 3 of 5

Drilling Start Date: 04/25/2016 Drilling End Date: 04/25/2016

Drilling Company: Layne

Rock Coring/Air Hammer Drilling Method:

Drilling Equipment: CS1500

Logged By: Nardos Tilahun

Driller: Kimberly Keizer

DTW After Drilling (ft): Top of Casing Elev. (ft msl): 716.59

Location (X,Y): 2104798.67, 254131.13*

8

Core Barrel

Well Depth (ft): 77

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted Seal Material(s): **Bentonite Pellets**

Filter Pack: Global Filter Pack #5

					CC	LLE	СТ				
DEPTH (ft)	LITHOLOGY	WATER LEVEL	WELL	Sample Type	Date & Time	Blow Counts	Recovery (ft)	N Value RQD (%)	SOIL/ROCK VISUAL DESCRIPTION	REMARKS	ELEV. (ft msl)
40			<<<<<<								 - -
- - 45 —		•	<	СО	04/25		4.0	50		(44') Bedding Plane Separation: 44.0 to 49.0.	- 670 -
- - 50 —			(СО	04/25		4.0	20	(49') SED ROCK (COAL); laminated, moderately weathered, moderately soft, moderately fractured, black, moist, 7.5YR 2/0.	(49') Bedding Plane Separation: 49.0 to 54.0.	_ _ 665 _
- - 55 —			<	СО	04/25		10.0	100	(49.5') SED ROCK (SHALE); laminated, decomposed, soft, very intensely fractured, light gray, moist, 7.5YR 6/0. (54') SED ROCK (SANDSTONE); moderately bedded, intensely weathered, hard, slightly fractured, light brown, moist, 7.5YR 3/4.	(54.4') Bedding Plane Separation: 54.4, 54.7, 55.0, 55.4, 56.1, 60.2. (55.6') Random Fracture at 55.6, 59.2.	- - 660 -
- - 60 —			< < < < < < < < < < < < < < < < < < <							(59.2') Random Fracture at 55.6, 59.2.	_ _ 655 _



Client: American Electric Power

Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY

Sampling Method(s):

WELL LOG

Well No. MW-1601

77

Page: 4 of 5

Screen Slot (in):

Drilling Start Date: 04/25/2016 Drilling End Date: 04/25/2016

Drilling Company: Layne

Rock Coring/Air Hammer Drilling Method:

Drilling Equipment: CS1500

Driller: Kimberly Keizer Logged By: Nardos Tilahun

Well Depth (ft): Boring Depth (ft):

Core Barrel

Well Diameter (in): 4 Boring Diameter (in): 8

DTW During Drilling (ft): Riser Material:

DTW After Drilling (ft):


Top of Casing Elev. (ft msl): 716.59

Location (X,Y): 2104798.67, 254131.13*

Sch 40 PVC Screen Material: Sch 40 PVC Slotted

0.010

Seal Material(s): **Bentonite Pellets** Global Filter Pack #5 Filter Pack:





engineers | scientists | innovator

Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1601

Page: 5 of 5

Drilling Start Date: 04/25/2016
Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 84

Boring Diameter (in): 8

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

DTW After Drilling (ft): 46.0

Top of Casing Elev. (ft msl): 716.59

Location (X,Y): 2104798.67, 254131.13*

Well Depth (ft): 77


Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets

Filter Pack: Global Filter Pack #5





Client: American Electric Power Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY **WELL LOG**

Well No. MW-1602

90

0.010

Sch 40 PVC

Page: 1 of 5

Drilling Start Date: 04/28/2016 Drilling End Date: 04/28/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer Logged By: Nardos Tilahun

Boring Depth (ft): Boring Diameter (in): 8

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft):

DTW After Drilling (ft):

Top of Casing Elev. (ft msl): 714.53 Location (X,Y): 2105862.78, 254183.19*

Filter Pack:

Well Depth (ft):

Screen Slot (in):

Screen Material:

Riser Material:

Well Diameter (in): 4

Sch 40 PVC Slotted

Seal Material(s): **Bentonite Pellets** Global Filter Pack #5

COLLECT WATER LEVEL COMPLETION (ft msl) LITHOLOGY Sample Type DEPTH (ft) Date & Time **Blow Counts** WELL N Value RQD (%) Recovery SOIL/ROCK VISUAL DESCRIPTION **REMARKS** Ĕ. ᆸ 711.60 (0') Poorly graded GRAVEL with sand (GP); \boxtimes mostly fine-coarse grained gravel, some medium-coarse sand, trace silt, trace clay, - 710 loose, moist, light gray. (1.5') Lean CLAY (CL); trace silt, mostly clay, medium plasticity, stiff, moist, brown, 7.5YR 4/3. 5 705 (7.5') Gravelly SILT (ML); little fine-coarse gravel, some fine-medium sand, some silt, few clay, low plasticity, medium stiff, moist, brown, 7.5YR/4/3. 10 (10') SED ROCK (SHALE); laminated, decomposed, soft, very intensely fractured, light gray, dry, 7.5YR 6/0. 700 (12') No Recovery: Split Spoon ends, Rock Coring begins. (14') SED ROCK (SHALE); laminated, decomposed, soft, very intensely fractured, 15 light gray, moist, 7.5YR 6/0. 695 0-20' geology logged from MW-1611



Client: American Electric Power Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY **WELL LOG**

Well No. MW-1602 Page: 2 of 5

Drilling Start Date: 04/28/2016 Drilling End Date: 04/28/2016

Drilling Company: Lavne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer Logged By: Nardos Tilahun

Boring Depth (ft): Boring Diameter (in): 8

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft):

DTW After Drilling (ft):

Top of Casing Elev. (ft msl): 714.53

Location (X,Y): 2105862.78, 254183.19*

Well Depth (ft): 90

Well Diameter (in): 4

Filter Pack:

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted Seal Material(s): **Bentonite Pellets**

Global Filter Pack #5

COLLECT **WATER LEVEL** COMPLETION (lsm LITHOLOGY Sample Type **JEPTH** (ft) Date & Time **Blow Counts** WELL ≝ % % Recovery SOIL/ROCK VISUAL DESCRIPTION **REMARKS** N Valu RQD (Ε. 핍 20 3.1 l (20.1') Bedding Plane (20') SED ROCK (SHALE); thinly bedded, 14:42 Separation: 20.1, 22.0. fresh, moderately hard, unfractured, light gray, moist, 7.5YR 6/0, casing set at 20 ft 690 bgs. 04/27 10.0 100 (24.0') SED ROCK (SANDSTONE); thinly 14:17 bedded, fresh, moderately soft, very slightly 25 fractured, light gray, moist, 7.5YR 6/0. (26') SED ROCK (SANDSTONE); fine sand, 685 thickly bedded, intensely weathered, hard, (26.8') Random Fracture: slightly fractured, light brown, wet, 7.5YR Open; Surface (Slightly 3/4, Breathitt Formation. Rough, Planar, Intensely Circulation water was lost at about 27 ft bgs. Weathered, Mod Soft); Filling (Very Thin, Iron Oxide, Intensely Weathered, Mod Soft, Not Healed); Lost 30 circulation around 27 ft bgs. Circulation water was back at about 30 ft (27.8') Random Fracture at 27.8. 680 (24.3') Bedding Plane Separation: Slightly Open; Surface (Smooth, Planar, Slightly Weathered, Mod Soft); Filling (Very Thin, Sand, Slightly Weathered, 04/27 10.0 85 Mod Soft, Not Healed); 14:42 Bedding Plane Separation: 35 24.3, 24.6, 24.8, 25.0, 27.8, 28.3, 31.0. (34.4') Fracture at 34.4, 34.6 675 and 34.8. (35') Bedding Joint: Slightly Open; Surface (Smooth, Planar, Moderately Weathered, Soft); Filling (Thin, Clay, Moderately Weathered, Soft, Not Healed); Fracture at 35.2,



engineers | scientists | innovators

Client: American Electric Power
Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY

WELL LOG

Well No. MW-1602

Page: 3 of 5

Drilling Start Date: 04/28/2016
Drilling End Date: 04/28/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 94

Boring Diameter (in): 8

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

DTW After Drilling (ft): 65.3

Top of Casing Elev. (ft msl): 714.53

Location (X,Y): **2105862.78**, **254183.19***

Well Depth (ft): 90


Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets

Filter Pack: Global Filter Pack #5





engineers | scientists | innovators

Client: American Electric Power
Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY

WELL LOG

Well No. MW-1602

Page: 4 of 5

Drilling Start Date: 04/28/2016
Drilling End Date: 04/28/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Diameter (in): 8

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

Boring Depth (ft):

DTW After Drilling (ft): **65.3**

Top of Casing Elev. (ft msl): **714.53** Location (X,Y): **2105862.78**, **254183.19*** Well Depth (ft): 90
Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets
Filter Pack: Global Filter Pack #5

COLLECT **WATER LEVEL** COMPLETION (lsm LITHOLOGY Sample Type **JEPTH** (ft) Date & Time **Blow Counts** WELL Recovery (≝ % % SOIL/ROCK VISUAL DESCRIPTION **REMARKS** N Valu RQD (Ē. 핍 60 (55.5') Bedding Plane 3/4. Separation: 55.5, 56.8, 58.2, (58.5') SED ROCK (SANDSTONE); fine 59.8. 650 sand, thickly bedded, intensely weathered, hard, very slightly fractured, light brown, wet, 7.5YR 3/4, Breathitt Formation. 04/29 10.0 100 (64') SED ROCK (SANDSTONE); 08:51 moderately bedded, moderately weathered, 65 (65.1') Bedding Plane hard, very slightly fractured, wet, 7.5YR 3/4 and 7.5YR 6/0 alternating. Separation: Slightly Open; Surface (Slightly Rough, 645 Planar, Moderately Weathered, Mod Soft); Filling (Very Thin, Iron Oxide, Moderately Weathered, Mod Soft, Not Healed); Fracture at 65.1, 66.4, 68.6, 70.3. (Bottom 73). 70 (65.7') Fracture Zone: Moderately Open; Surface (Slightly Rough, Planar, Intensely Weathered, Soft); 640 Filling (Moderately Thin, Clay, Moderately Weathered, Mod Soft, Not Healed). 04/29 10.0 100 09:20 75 (76.3') Bedding Plane Separation: Moderately Open; Surface (Slightly 635 Rough, Planar, Intensely Weathered, Soft); Filling (Moderately Thin, Iron Oxide, Intensely Weathered, Soft, Not Healed); Bedding Plane Separation: 76.3, 80.0, 81.3, 82.0, 82.7, 83.5.



engineers | scientists | innovator

Client: American Electric Power
Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY

WELL LOG

Well No. MW-1602

90

0.010

Page: 5 of 5

Drilling Start Date: 04/28/2016
Drilling End Date: 04/28/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 94
Boring Diameter (in): 8

Sampling Method(s): Core Barrel

DTW During Drilling (ft):

DTW After Drilling (ft): 65.3

Top of Casing Elev. (ft msl): **714.53** Location (X,Y): **2105862.78**, **254183.19*** Riser Material: Sch 40 PVC

Well Diameter (in): 4

Well Depth (ft):

Screen Slot (in):

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets
Filter Pack: Global Filter Pack #5

COLLECT **WATER LEVEL** COMPLETION (lsm LITHOLOGY Sample Type **JEPTH** (ft) Date & Time **Blow Counts** WELL € % % Recovery SOIL/ROCK VISUAL DESCRIPTION **REMARKS** N Valu RQD (Ē. ᆸ 80 630 (83.5') Random Fracture: CO 04/29 Slightly Open; Surface 10.0 100 (84') SED ROCK (SANDSTONE); 09:57 (Slightly Rough, Planar, moderately bedded, intensely weathered, 85 Intensely Weathered, Mod hard, very slightly fractured, light brown, wet, Soft); Filling (Very Thin, Iron 7.5YR 3/4, 89-89.5: light grey fresh Oxide, Intensely Weathered, Sandstone, unfractured. Mod Soft, Not Healed). 625 (85.6') Bedding Joint at 85.6. Bedding Plane Separation: 85.6, 90.4, 93.0. (84.9') Random Fracture: Slightly Open; Surface (89.5') SED ROCK (SHALE); moderately 90 (Slightly Rough, Planar, bedded, fresh, moderately hard, unfractured, Intensely Weathered, Mod light gray, wet, 7.5YR 6/0. Soft); Filling (Very Thin, Iron Oxide, Moderately 620 Weathered, Mod Soft, Partly Healed). (93.7') Random Fracture: Moderately Open; Surface (Slightly Rough, Planar, (94') SED ROCK (SHALE); moderately Intensely Weathered, Soft); bedded, fresh, moderately hard, unfractured, 95 Filling (Moderately Thin, light gray, wet. End of Boring Clay, Moderately Weathered, Soft, Not Healed). 615 100



Client: American Electric Power

Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1603

Page: 1 of 2

Drilling Start Date: 04/25/2016 Drilling End Date: 06/01/2016

Drilling Company: Layne

Drilling Equipment: SCR-13

Drilling Method:

Driller: Keith Fehrman

Logged By: N. Tilahun/J. Ivanowski

HSA/Rock Coring

Boring Depth (ft):

Boring Diameter (in): 8

Sampling Method(s): SS & Core Barrel

DTW During Drilling (ft): 3.8

DTW After Drilling (ft): Top of Casing Elev. (ft msl): 675.75

Location (X,Y): 2107344.43, 251596.53*

Well Depth (ft): 32

Well Diameter (in): 4


Screen Slot (in):

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted Seal Material(s): **Bentonite Pellets**

0.010

Filter Pack: Global Filter Pack #5





engineers | scientists | innovators

Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1603

Page: 2 of 2

Drilling Start Date: 04/25/2016
Drilling End Date: 06/01/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring
Drilling Equipment: SCR-13

Driller: Keith Fehrman

Logged By: N. Tilahun/J. Ivanowski

Boring Depth (ft): 40 Well Depth (ft): 32

Boring Diameter (in): 8 Well Diameter (in): 4

Sampling Method(s): SS & Core Barrel Screen Slot (in): 0.010

DTW During Drilling (ft): 3.8 Riser Material: Sch 40 PVC

DTW After Drilling (ft): 21.8 Screen Material: Sch 40 PVC Slotted

Top of Casing Elev. (ft msl): 675.75 Seal Material(s): Bentonite Pellets
Location (X,Y): 2107344.43, 251596.53* Filter Pack: Global Filter Pack #5

COLLECT **WATER LEVEL** COMPLETION (lsm Sample Type **JEPTH** (ft) LITHOLOGY Date & Time **Blow Counts** WELL ≝ % % Recovery SOIL/ROCK VISUAL DESCRIPTION **REMARKS** N Valu RQD (Ε. ᆸ 20 5.0 (20') Well-graded SAND (SW); mostly fine 18:16 grained sand, loose, saturated, light yellowish-brown. (22') SED ROCK (SANDSTONE); fine sand, massive, slightly weathered, hard, 650 unfractured, light yellowish-brown, wet. (23') SED ROCK (SHALE); silt, laminated, decomposed, soft, intensely fractured, dark 25 gray, wet, iron oxide staining; organic 4.5 24 matter. (24') SED ROCK (SHALE); silt, laminated, decomposed, very soft, intensely fractured, black, wet, nearly all organic matter; slight coaly texture. 645 (25') SED ROCK (CLAYSTONE); clay, moderately bedded, intensely weathered, moderately soft, slightly fractured, pale 30 bluish-gray, wet. 70 46 (29') SED ROCK (SANDSTONE); very fine (31') Bedding Joint: 5°-10° sand, very thinly bedded, intensely Dip, Open; Surface (Slightly weathered, moderately hard, very intensely Rough, Planar); Filling (Clay). fractured, light reddish-brown, wet. (30') SED ROCK (SANDSTONE); very fine 640 sand, laminated, slightly weathered, very hard, moderately fractured, dark bluish-gray, wet, some micaceous minerals. 35 5.0 90 (32') SED ROCK (SANDSTONE); very fine sand, laminated, fresh, very hard, unfractured, dark bluish-gray, moist. (35.5') Fractured zone; slight iron-oxide staining on surface. 635 (39.5') As Above. End of Boring



engineers | scientists | innovato

Client: American Electric Power
Project: Big Sandy Fly Ash Pond
Address: Lawrence County, Louisa, KY

Boring Depth (ft):

Boring Diameter (in):

Sampling Method(s):

DTW During Drilling (ft): 19.0

WELL LOG Well No. MW-1604 Page: 1 of 3

Drilling Start Date: 06/06/2016
Drilling End Date: 06/06/2016
Drilling Company: Layne

Drilling Method: Hollow Stem Auger

Drilling Equipment: CME95

Driller: Tim Woods

Logged By: Nardos Tilahun

: CME95 DTW After Drilling (ft): 28.7
Tim Woods Top of Casing Elev. (ft msl): 556.21

Location (X,Y): 2108828.43, 254482.33*

50.5

Cuttings


8

Well Depth (ft): 50
Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Chips
Filter Pack: Global Filter Pack #5





06/06/2016

Tim Woods

Layne

Drilling Start Date: 06/06/2016

Drilling End Date:

Drilling Company:

Drilling Equipment: CME95

Drilling Method:

Driller:

Client: **American Electric Power** Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY **WELL LOG**

Well No. MW-1604 Page: 2 of 3

0.010

Boring Depth (ft): 50.5 Well Depth (ft): 50 Boring Diameter (in): 8 Well Diameter (in): 4

Sampling Method(s): **Cuttings** Screen Slot (in):

Hollow Stem Auger DTW During Drilling (ft): 19.0 Riser Material: Sch 40 PVC

> DTW After Drilling (ft): Screen Material: Sch 40 PVC Slotted Top of Casing Elev. (ft msl): 556.21 Seal Material(s): **Bentonite Chips** Location (X.Y): 2108828.43. 254482.33* Filter Pack: Global Filter Pack #5

Logged By: Nardos Tilahun								Location (X,Y): 2108828.43, 254482.33*	Filter Pack:	Glob	bbal Filter Pack #5			
DEPTH (ft)	LITHOLOGY	WATER LEVEL	WELL COMPLETION	COLLECT							MEAS			
				Sample Type	Date & Time	Blow Counts	Recovery (ft)	SOIL/ROCK VISUAL DESC	SOIL/ROCK VISUAL DESCRIPTION				ELEV. (ft msl)	
20			^^^^^^^^^					(19.5') Lean CLAY (CL); mostly clay, medium light brown. (23') Poorly graded SAND (SP); mostly fine-notery loose, wet, light brown. (25') Lean CLAY (CL); mostly silt, trace clay, medium stiff, wet, dark gray.	nedium grained san				- - - 530 - -	
30		•	^^^^^^					(30') Lean CLAY (CL); mostly clay, medium p wet, light brown.	olasticity, medium st	iff,			- 525 - - - - - 520	
35 — - - - 40 —								(38') Poorly graded SAND (SP); mostly fine-n trace silt, trace clay, loose, wet, light brown.	nedium grained san	nd,			- - - 515 -	



engineers | scientists | innova

Client: American Electric Power
Project: Big Sandy Fly Ash Pond

Address: Lawrence County, Louisa, KY

WELL LOG Well No. MW-1604

Page: 3 of 3

Drilling Start Date: 06/06/2016
Drilling End Date: 06/06/2016

Drilling Company: Layne

Drilling Method: Hollow Stem Auger

Drilling Equipment: **CME95**Driller: **Tim Woods**

Logged By: Nardos Tilahun

Boring Depth (ft): 50.5

Boring Diameter (in): 8

Sampling Method(s): Cuttings

DTW During Drilling (ft): 19.0

DTW After Drilling (ft): 28.7

Top of Casing Elev. (ft msl): 556.21

Location (X,Y): 2108828.43, 254482.33*

Well Depth (ft): 50

Well Diameter (in): 4
Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted

Seal Material(s): Bentonite Chips
Filter Pack: Global Filter Pack #5

COLLECT **MEASURE WATER LEVEL** -EV. (ft msl) COMPLETION LITHOLOGY Sample Type Lab Sample DEPTH (ft) Date & Time **Blow Counts** WELL PID (ppm) Recovery SOIL/ROCK VISUAL DESCRIPTION П 40 (40') Poorly graded SAND (SP); mostly fine-medium grained sand, trace fine-coarse gravel, trace silt, loose, saturated, light brown. 510 45 505 50 (50') Poorly graded SAND (SP); mostly fine-medium grained sand, trace fine-coarse gravel, trace silt, loose, saturated, light brown, End of Boring. 500 55



Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1605

Page: 1 of 2

Drilling Start Date: 04/27/2016

Drilling End Date: 04/27/2016

Boring Depth (ft): 32

Well Depth (ft): 26

Well Diameter (in): 4

Drilling Company: Layne

Sampling Method(s): Split Spoon


Screen Slot (in): 0.010

Drilling Method: Hollow Stem Auger DTW During Drilling (ft): 18.0 Riser Material: Sch 40 PVC

Drilling Equipment: CME95 DTW After Drilling (ft): 15.9 Screen Material: Sch 40 PVC Slotted

Driller: Tim Woods Top of Casing Elev. (ft msl): 557.46 Seal Material(s): Bentonite Pellets

Logged By: Nardos Tilahun Location (X,Y): 2110694.01, 252760.21* Filter Pack: Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1605

Page: 2 of 2

Drilling Start Date: 04/27/2016
Drilling End Date: 04/27/2016

Drilling Company: Layne

Drilling Method: Hollow Stem Auger

Drilling Equipment: **CME95**Driller: **Tim Woods**

Logged By: Nardos Tilahun

Boring Depth (ft): 32
Boring Diameter (in): 8

Sampling Method(s): Split Spoon

DTW During Drilling (ft): **18.0**DTW After Drilling (ft): **15.9**

Top of Casing Elev. (ft msl): 557.46


Location (X,Y): 2110694.01, 252760.21*

Well Depth (ft): 26
Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets
Filter Pack: Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1606

Page: 1 of 3

Well Depth (ft): Drilling Start Date: 04/26/2016 Boring Depth (ft): 52 51.3 Drilling End Date: 04/26/2016 Boring Diameter (in): 8 Well Diameter (in): 4 **Drilling Company:** Sampling Method(s): Screen Slot (in): 0.010 Split Spoon Layne

Drilling Method: Hollow Stem Auger DTW During Drilling (ft): 20.0 Riser Material: Sch 40 PVC

Drilling Equipment: CME95 DTW After Drilling (ft): 30.6 Screen Material: Sch 40 PVC Slotted

Driller: Tim Woods Top of Casing Elev. (ft msl): 554.10 Seal Material(s): Bentonite Chips
Logged By: Nardos Tilahun Location (X,Y): 2105122.96, 254592.81* Filter Pack: Global Filter Pack #5

COLLECT **MEASURE** WATER LEVEL COMPLETION ms) Sample LITHOLOGY Sample Type **JEPTH** (ft) Date & Time **Blow Counts** WELL (mdd) € Recovery SOIL/ROCK VISUAL DESCRIPTION Ē. 믑 ab_ ᆸ 550.99 0 04/26 4 (0') Lean CLAY (CL); some silt, mostly clay, medium plasticity, stiff, 80:80 4 moist, light yellowish-gray, roots, 7.5YR/7/2. 550 6 6 2 2.0 04/26 08:21 2 (2.5') Poorly graded SAND (SP); mostly fine grained sand, few silt, 4 few clay, medium dense, moist, light reddish-brown, 7.5YR/7/4. 4 04/26 2 2.0 (3') Fat CLAY with sand (CH); little fine sand, some silt, mostly clay, 08.58 2 high plasticity, medium stiff, moist, light yellowish-gray, 5 GLEY1/8/10Y. 3 545 (4') Lean CLAY with sand (CL); some fine sand, some silt, mostly 04/26 4 2.0 clay, medium plasticity, medium stiff, moist, light reddish-gray, 08:37 4 5YR/6/4. 5 6 (6.5') Fat CLAY (CH); trace fine sand, little silt, mostly clay, high 2 04/26 2.0 plasticity, stiff, moist, light gray, GLEY2/5/5PB. 08:43 2 3 3 10 2.0 04/26 4 08:48 3 540 (11.5') Poorly graded SAND with silt (SP-SM); mostly fine grained 04/26 3 2.0 sand, some silt, few clay, medium dense, moist, light gray, 08:54 4 GLFY2/5/10B. 3 (12') Fat CLAY (CH); trace fine sand, few silt, mostly clay, high 04/26 4 2.0 plasticity, stiff, moist, light gray, GLEY2/5/5PB. 09:00 3 15 4 5 535 2.0 04/26 4 09:05 8 6 04/26 2 2.0 09:09 4 4 20



Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1606

Page: 2 of 3

Drilling Start Date: 04/26/2016 Boring Depth (ft): 52 Well Depth (ft): 51.3


Drilling End Date: 04/26/2016 Boring Diameter (in): 8 Well Diameter (in): 4

Drilling Company: Layne Sampling Method(s): Split Spoon Screen Slot (in): 0.010

Drilling Method: Hollow Stem Auger DTW During Drilling (ft): 20.0 Riser Material: Sch 40 PVC

Drilling Equipment: CME95 DTW After Drilling (ft): 30.6 Screen Material: Sch 40 PVC Slotted
Driller: Tim Woods Top of Casing Elev. (ft msl): 554.10 Seal Material(s): Bentonite Chips

Logged By: Nardos Tilahun Location (X,Y): 2105122.96, 254592.81* Filter Pack: Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1606

51.3

0.010

Sch 40 PVC

Sch 40 PVC Slotted

Page: 3 of 3

Drilling Start Date: 04/26/2016 Boring Depth (ft): 52 Well Depth (ft): 5
Drilling End Date: 04/26/2016 Boring Diameter (in): 8 Well Diameter (in): 4
Drilling Company: Layne Sampling Method(s): Split Spoon Screen Slot (in): 0

Drilling Company: Layne Sampling Method(s): Split Spoon

Drilling Method: Hollow Stem Auger

DTW During Drilling (ft): 20.0

Drilling Equipment: CME95

Driller: Tim Woods

DTW After Drilling (ft): 30.6


Top of Casing Elev. (ft msl): 554.10

Logged By: Nardos Tilahun Location (X,Y): 2105122.96, 254592.81*

Seal Material(s): Bentonite Chips

Riser Material:

Screen Material:





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1607

Page: 1 of 2

Drilling Start Date: 04/26/2016

Drilling End Date: 04/26/2016

Drilling Company: Layne

Drilling Method: Hollow Stem Auger

Drilling Equipment: CME95

Driller: Tim Woods

Logged By: Nardos Tilahun

Boring Depth (ft): 34.5

Boring Diameter (in): 8

Sampling Method(s): Split Spoon


DTW During Drilling (ft): 23.0
DTW After Drilling (ft): 19.8

Top of Casing Elev. (ft msl): **545.23** Location (X,Y): **2105634.33**, **254664.49*** Well Depth (ft): 34
Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets
Filter Pack: Global Filter Pack #5





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1607


Page: 2 of 2

Well Depth (ft): Drilling Start Date: 04/26/2016 Boring Depth (ft): 34.5 34 Drilling End Date: Well Diameter (in): 4 04/26/2016 Boring Diameter (in): 8 **Drilling Company:** Sampling Method(s): Split Spoon Screen Slot (in): 0.010 Layne

Drilling Method: **Hollow Stem Auger** DTW During Drilling (ft): 23.0 Riser Material: Sch 40 PVC

Drilling Equipment: CME95 DTW After Drilling (ft): Screen Material: Sch 40 PVC Slotted Driller: **Tim Woods** Top of Casing Elev. (ft msl): 545.23 Seal Material(s): **Bentonite Pellets**

Logged By: Nardos Tilahun Location (X,Y): 2105634.33, 254664.49* Filter Pack: Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 1 of 7

Drilling Start Date: 04/25/2016 Boring Depth (ft): 121 Well Depth (ft): 120
Drilling End Date: 06/24/2016 Boring Diameter (in): 8 Well Diameter (in): 4


Drilling Company: Layne Sampling Method(s): SS, Core Barrel Screen Slot (in): 0.010

Drilling Method: HSA/Rock Coring/Air Hammer DTW During Drilling (ft): 29.0 Riser Material: Sch 40 PVC

Drilling Equipment: CS1500 DTW After Drilling (ft): 29.3 Screen Material: Sch 40 PVC Slotted

Driller: Kimberly Keizer Top of Casing Elev. (ft msl): 719.08 Seal Material(s): Bentonite Pellets

Logged By: D. Yifru & N. Tilahun Location (X,Y): 2105883.65, 251052.42* Filter Pack: Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 2 of 7

Drilling Start Date: 04/25/2016
Drilling End Date: 06/24/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121

Boring Diameter (in): 8

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*


Well Depth (ft): 120

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 3 of 7

Drilling Start Date: 04/25/2016
Drilling End Date: 06/24/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121
Boring Diameter (in): 8

Boring Diameter (in): 8
Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*

Well Depth (ft): 120

Well Diameter (in): 4

Seal Material(s):


Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted

Filter Pack: Global Filter Pack #5

Bentonite Pellets





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

Boring Diameter (in):

WELL LOG

Well No. MW-1608

Page: 4 of 7

Drilling Start Date: **04/25/2016**Drilling End Date: **06/24/2016**

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*

8


Well Depth (ft): 120

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 5 of 7

Drilling Start Date: 04/25/2016
Drilling End Date: 06/24/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121

Boring Diameter (in): 8

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*


Well Depth (ft): 120

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 6 of 7

Drilling Start Date: 04/25/2016
Drilling End Date: 06/24/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121
Boring Diameter (in): 8

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*


Well Depth (ft): 120

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1608

Page: 7 of 7

Drilling Start Date: 04/25/2016
Drilling End Date: 06/24/2016

Drilling Company: Layne

Drilling Method: HSA/Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer

Logged By: D. Yifru & N. Tilahun

Boring Depth (ft): 121

Boring Diameter (in): 8
Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 29.0

DTW After Drilling (ft): 29.3

Top of Casing Elev. (ft msl): 719.08

Location (X,Y): 2105883.65, 251052.42*


Well Depth (ft): 120

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Layne

Kimberly Keizer

engineers | scientists | innovator

Drilling Company:

Driller:

Drilling Equipment: CS1500

Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609 Page: 1 of 8


Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)

Drilling End Date: 04/20/2016 Boring Diameter (in):

Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

DTW After Drilling (ft): 26.9
Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609

Page: 2 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)


Drilling End Date: 04/20/2016 Boring Diameter (in):

Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609

Page: 3 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)


Drilling End Date: 04/20/2016 Boring Diameter (in):

Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609

Page: 4 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)


Drilling End Date: 04/20/2016 Boring Diameter (in):

Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1609 Page: 5 of 8

Boring Depth (ft): 154 (Abandoned)


Drilling Start Date: 04/19/2016

Drilling End Date: 04/20/2016 Boring Diameter (in):

Drilling Company: Sampling Method(s): Core Barrel Layne

DTW During Drilling (ft): Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9 Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609 Page: 6 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)


Drilling End Date: 04/20/2016 Boring Diameter (in): 8

Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609

Page: 7 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)

Drilling End Date: 04/20/2016 Boring Diameter (in):


Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28

Logged By: Nardos Tilahun Location (X,Y): 2101420.87, 252205.98*



NOTES: *Northing and easting are in NAD83 Kentucky North. Elevation is in ft MSL NAVD88. Monitoring well was not installed in this borehole.



Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1609 Page: 8 of 8

Drilling Start Date: 04/19/2016 Boring Depth (ft): 154 (Abandoned)


Drilling End Date: 04/20/2016 Boring Diameter (in):

Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft):

Drilling Equipment: CS1500 DTW After Drilling (ft): 26.9

Driller: Kimberly Keizer Ground Surface Elev. (ft): 728.28





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1610

Page: 1 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft): 136 (Abandoned)

Drilling End Date: 04/25/2016 Boring Diameter (in):


Drilling Company: Layne Sampling Method(s): Core Barrel

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft): 49.0

Drilling Equipment: CS1500 DTW After Drilling (ft): 49.0

Driller: Kimberly Keizer Ground Surface Elev. (ft): 715.76

Logged By: Nardos Tilahun Location (X,Y): 2104799.937, 254147.538*





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1610

Page: 2 of 7

Drilling Start Date: 04/21/2016

Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: **Rock Coring/Air Hammer**

Drilling Equipment: CS1500

Driller: Kimberly Keizer


Logged By: Nardos Tilahun Boring Depth (ft): 136 (Abandoned)

Boring Diameter (in):

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft): 49.0 DTW After Drilling (ft): 49.0

Ground Surface Elev. (ft): 715.76





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

BORING LOG

Boring No. MW-1610

Page: 3 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft): 136 (Abandoned)

Drilling End Date: 04/25/2016

Drilling Company: Layne Sampling Method(s): Core Barrel


Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft): 49.0

Drilling Equipment: CS1500 DTW After Drilling (ft): 49.0

Driller: Kimberly Keizer Ground Surface Elev. (ft): 715.76

Logged By: Nardos Tilahun Location (X,Y): 2104799.937, 254147.538*

Boring Diameter (in):





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1610

Page: 4 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft): 136 (Abandoned)

Drilling End Date: 04/25/2016

Drilling Company: Layne Drilling Method: **Rock Coring/Air Hammer**

Drilling Equipment: CS1500


Driller: Kimberly Keizer

Logged By: Nardos Tilahun

Boring Diameter (in):

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft): 49.0 DTW After Drilling (ft): 49.0 Ground Surface Elev. (ft): 715.76





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1610

Page: 5 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft): 136 (Abandoned)

Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer


Logged By: Nardos Tilahun

Boring Diameter (in):

Sampling Method(s): Core Barrel

DTW During Drilling (ft): 49.0

DTW After Drilling (ft): 49.0 Ground Surface Elev. (ft): 715.76





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1610

Page: 6 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft):

Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer


Logged By: Nardos Tilahun 136 (Abandoned)

Boring Diameter (in):

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft): 49.0 DTW After Drilling (ft): 49.0

Ground Surface Elev. (ft): 715.76





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **BORING LOG**

Boring No. MW-1610

Page: 7 of 7

Drilling Start Date: 04/21/2016 Boring Depth (ft):

Drilling End Date: 04/25/2016

Drilling Company: Layne

Drilling Method: **Rock Coring/Air Hammer**

Drilling Equipment: CS1500

Driller: Kimberly Keizer


Logged By: Nardos Tilahun 136 (Abandoned)

Boring Diameter (in): 8

Sampling Method(s): **Core Barrel**

DTW During Drilling (ft): 49.0 DTW After Drilling (ft): 49.0

Ground Surface Elev. (ft): 715.76





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1611

Page: 1 of 7

Drilling Start Date: 04/27/2016 Boring Depth (ft): 124 Drilling End Date: 04/28/2016 Boring Diameter (in): 8

Drilling Company: Sampling Method(s): SS, Core Barrel Lavne

DTW During Drilling (ft): 68.2 Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500 DTW After Drilling (ft):

Driller: Kimberly Keizer Top of Casing Elev. (ft msl): 714.25 Logged By: Nardos Tilahun

Location (X,Y): 2105868.49, 254192.11*


Well Depth (ft): 115.5

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted Seal Material(s): **Bentonite Pellets**





Lavne

Drilling Company:

Client: American Electric Power

Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1611

0.010

Page: 2 of 7

Screen Slot (in):

Well Depth (ft): Drilling Start Date: 04/27/2016 Boring Depth (ft): 124 115.5 Drilling End Date: Well Diameter (in): 4 04/28/2016 Boring Diameter (in): 8


Sampling Method(s):

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft): 68.2 Riser Material: Sch 40 PVC

Drilling Equipment: CS1500 DTW After Drilling (ft): Screen Material: Sch 40 PVC Slotted Driller: Top of Casing Elev. (ft msl): 714.25 Seal Material(s): **Bentonite Pellets** Kimberly Keizer

SS, Core Barrel

Location (X,Y): 2105868.49, 254192.11* Filter Pack: Logged By: Nardos Tilahun Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1611

Page: 3 of 7

Drilling Start Date: 04/27/2016 Boring Depth (ft): 124 Well Depth (ft): 115.5

Drilling End Date: 04/28/2016 Boring Diameter (in): 8 Well Diameter (in): 4


Drilling Company: Layne Sampling Method(s): SS, Core Barrel Screen Slot (in): 0.010

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft): 68.2 Riser Material: Sch 40 PVC

Drilling Equipment: CS1500 DTW After Drilling (ft): 75.8 Screen Material: Sch 40 PVC Slotted

Driller: Kimberly Keizer Top of Casing Elev. (ft msl): 714.25 Seal Material(s): Bentonite Pellets

Logged By: Nardos Tilahun Location (X,Y): 2105868.49, 254192.11* Filter Pack: Global Filter Pack #5





Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1611

Page: 4 of 7

Drilling Start Date: 04/27/2016 Drilling End Date: 04/28/2016

Drilling Company: Layne

Rock Coring/Air Hammer Drilling Method:

Drilling Equipment: CS1500

Driller: Kimberly Keizer Logged By: Nardos Tilahun

Boring Depth (ft): 124

Boring Diameter (in): 8

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 68.2 DTW After Drilling (ft):

Top of Casing Elev. (ft msl): 714.25

Location (X,Y): 2105868.49, 254192.11*

Well Depth (ft): 115.5

Well Diameter (in): 4

Filter Pack:

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted Seal Material(s): **Bentonite Pellets** Global Filter Pack #5

COLLECT **WATER LEVEL** COMPLETION EV. (ft msl) Sample Type LITHOLOGY DEPTH (ft) Date & Time **Blow Counts** WELL % % Recovery SOIL/ROCK VISUAL DESCRIPTION **REMARKS** N Valu RQD (핍 60 650 10.0 100 04/27 (64') SED ROCK (SANDSTONE); fine sand, 15:55 moderately bedded, moderately weathered, 65 hard, very slightly fractured, wet, 7.5YR 3/4 and 7.5YR 6/0 alternating, Breathitt (65.7') Moderately Open; Formation. Surface (Slightly Rough, Planar, Intensely Weathered, 645 Soft); Filling (Moderately Thin, Clay, Moderately Weathered, Mod Soft, Not Healed); Bedding Plane Separation: 65.7. 70 640 04/27 10.0 100 16:26 75 635 (77') Bedding Plane Separation: 77.0, 80.2, 83.6.



Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1611

Page: 5 of 7

Drilling Start Date: **04/27/2016**Drilling End Date: **04/28/2016**

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 124
Boring Diameter (in): 8

Sampling Method(s): SS, Core Barrel

DTW During Drilling (ft): 68.2

DTW After Drilling (ft): 75.8

Top of Casing Elev. (ft msl): 714.25

Location (X,Y): 2105868.49, 254192.11*


Well Depth (ft): 115.5

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets





Lavne

Drilling Company:

Client: American Electric Power

Project: **Big Sandy Plant**

Address: 23000 US-23, Louisa, KY **WELL LOG**

Well No. MW-1611

0.010

Page: 6 of 7

Screen Slot (in):

Well Depth (ft): Drilling Start Date: 04/27/2016 Boring Depth (ft): 124 115.5 Drilling End Date: Well Diameter (in): 4 04/28/2016 Boring Diameter (in): 8


Sampling Method(s):

Drilling Method: Rock Coring/Air Hammer DTW During Drilling (ft): 68.2 Riser Material: Sch 40 PVC

Drilling Equipment: CS1500 DTW After Drilling (ft): Screen Material: Sch 40 PVC Slotted Driller: Kimberly Keizer Top of Casing Elev. (ft msl): 714.25 Seal Material(s): **Bentonite Pellets**

SS, Core Barrel

Location (X,Y): 2105868.49, 254192.11* Filter Pack: Logged By: Nardos Tilahun Global Filter Pack #5





Client: American Electric Power

Project: Big Sandy Plant

Address: 23000 US-23, Louisa, KY

WELL LOG

Well No. MW-1611

Page: 7 of 7

Drilling Start Date: 04/27/2016
Drilling End Date: 04/28/2016

Drilling Company: Layne

Drilling Method: Rock Coring/Air Hammer

Drilling Equipment: CS1500

Driller: Kimberly Keizer
Logged By: Nardos Tilahun

Boring Depth (ft): 124

Boring Diameter (in): 8

 $Sampling \ Method(s): \qquad \textbf{SS, Core Barrel} \\$

DTW During Drilling (ft): 68.2

DTW After Drilling (ft): 75.8

Top of Casing Elev. (ft msl): 714.25

Location (X,Y): 2105868.49, 254192.11* Filter Paci


Well Depth (ft): 115.5

Well Diameter (in): 4

Screen Slot (in): 0.010

Riser Material: Sch 40 PVC

Screen Material: Sch 40 PVC Slotted
Seal Material(s): Bentonite Pellets



2010 INITIAL BORING LOGS AND WELL CONSTRUCTION DIAGRAMS



Soil Boring Log

Boring No: B-1007

	Date: Client:	11/19/2010 AEP				Proj.	No.:	E10028 Project: Big Sandy Location:
10	Drilling	Company:			Drilling	g, Inc.		Driller:
		By: <u>Larry</u> Elevation:		z 92'				Drilling Method: Air Rotary Top of Casing Elevation:
		epth: 90'	-	172		Dian	neter	
	Comme					-		
H		REC /				_	_	Description/Soil Classification
	epth feet)	RQD		Samp	le#	Litholo	ogy	(Color, Texture, Moisture, Structures)
	, , , ,	RQD	Т			1 100		(Sold) Addition that the state of the state
L	-			ı	_	The state of the s	_	
						1		
H	10.0 -				-	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		V-N
L	-1				_	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	_	Yellow brown Sandstone
				-		111111		
r	20.0			-	. $ extstyle ext$	100 miles (100 miles (
\vdash	-1			S	'	Link	-	
L	30.0			1	L	and the book of th		
	20.0			S	2	NAME OF THE PERSON OF THE PERS		
H	+		-			1011000 1011000 1011000 1011000		
L	40.0		and the same of	S.	3 -	100 mm to 100 mm	-	
				S	4	38966	3	
Γ]		١	V s	, [200000 200000 200000	NEGRAL.	Yellow brown fine to coarse sandstone, minor limonite (added water when groundwater encountered at approximatley 49' bgs
r	50.0			S		A. A. STANISH CO. A. A. STANISH CO. A. A. STANISH CO. A.		color to light gray
r				S		2000 to 1000 t	The state of	color to yellow brown
r	60.0			S		Barrier and American	TO THE PERSON	
r	- 1					district dis	-	color to light gray
H	70.0	l		S:	' -			
L				S	10	2,100		
				S	11	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	THE REAL PROPERTY.	
r	80.0							Gray Shale and Coal (black sheen in return water)
H			- 1	S	12 <u> </u>		-	
L	90.0				_		L	
1						H	-	
r	1					П	П	
-	0.001				\vdash	H	Н	
L						Ц	L	
1	- 1							
	10.0-					Н		
\vdash	-				-	Н	H	
L,	20.0-					Ц	Ц	
r	1					Н	H	
L	30.0-				_			
Γ	1							
<u>ا</u>	40.0				-	H	H	
F	-				_	Н	Н	
 	50.0-					П	П	
Ь			_					



Soil Boring Log

Boring No: B-1007
Page 2 of 2

Date: 11/23/2010	Proj. No.: E10028	Project: Big Sandy
Client: AEP		Location: Louiza, Ky
Dritting Company: Frontz	Drilling, Inc.	Driller:
Logged By: Larry Retz		Drilling Method: Sonic/HQ core
Surface Elevation:		Top of Casing Elevation:
Total Depth: 200'	Diameter: 6"-15"	Sampling Method:
Comments:		ALCOHOMO CONTRACTOR SERVICE AND CONTRACTOR SE

epth eet)	Sample #	Lithology	Description/Soil Classification
et)	171		(Color, Texture, Moisture, Structures)
		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	Medium gray medium to very coarse Sandstone
0.0-		1	
1		ПΓ	
0.0-		11 1	
S14505			
		+	
0.0-		H	
1		ПП	
0.0-		41 L	
-		+	
00.0		H	
1			
10.0		\bot	
4		+	
20.0-		H	
1		ПГ	
30.0		\sqcup	
4	111 +	$H \vdash$	
1		H	
1		TI [
1		$H \vdash$	
+	111 +	H	
1		TI F	
4	1	$H \vdash$	
1		H	
1		\sqcap	
		II L	
-		H	
-	111 -	$H \vdash$	
1	HIL	H	
7			



JOB NUMBER BS-CL-2133 MONITORII	NG WELL CO		
COMPANY Frontz Drilling, Inc.	WELL NO	KY6555	BORING No. MW-1007 INSTALLED 12-7-10
PROJECT Big Sandy Plant			
COORDINATES 38.18628 N -82.63430 W			
SYSTEM GPS			
	-		TOP RISER: FT 2
GROUND ELEVATION FT 692			
AEP supplied			NX//NX//NX//
Portorite Grout			
GROUTSEAL Bentonite Grout			
Bariod Quick-Grout			
BENTONITE SEAL: Bentonite Pellets			
3/8" Pel Plug TR 30/60			
3/8 Fel Flug In 30/00			
SCREEN: da., 2"x3-1/2" PrePack			TOP BENTONITE SEAL: FT 40
I— — ¬			
PVC .007 & .010 slot			
GRAVEL PACK: #7 in PrePack			
(S. 7. 3)			
#4 Borehole			
RISER PIPE: , dia , 2" Sch. 40 PVC			TOP GRAVEL PACK: FT 45
RISER PIPE: , dia , 2 SCIII 15 1			
			TOP SCREEN: FT. 47
SPACERS, DEPTH: PVC Centralizer			
SPACERS, DEPTH: 1 VC COLLEGE			
77 ft. and 40 ft.			
Notes:			
			*1
Bentonite 3/8" Holeplug			
Bottom 8 ft. of boring			
5			
<u> </u>			
B			BOTTOM SCREEN: FT 77
3			POTTOMINELL ST 22
CANIF			BOTTOM WELL: FT
8		- m	BOTTOM GRAVEL PACK: FT. 78
ਜ਼			
Ž-		/////s	BOTTOM BORING: FT 86
Bottom 8 ft. of boring			
ra .			



Soil Boring Log

Boring No: B-1008
Page 1 of 2

Drilling Logged Surface	11/17/2010 AEP Company: By: Larry R Elevation: epth: 120' nts:	Frontz Drillin teitz	Proj. No.: g, Inc.	Location: Driller; Drilling Method: Air Rotary Top of Casing Elevation:
Depth	REC /	Sample #	Lithology	Description/Soil Classification
(feet)	RQD	Jampie #		(Color, Texture, Moisture, Structures)
_ 10.0 -		S1 S2 s3		Yellow brown silty Clay color to yellow gray
- 20.0		S4 S5	Control (Control (Con	color to yellow brown Sandstone Groundwater encountered at approximately 25' bgs
- 30.0		S6	Colorest Col	Control of the contro
- 40.0 -		S7 S8 _	N 1 m 1 m 1 m 1 m 1 m 1 m 1 m 1 m 1 m 1	Medium gray Shale
_ 50.0 _		S10	Applications of the control of the c	
-		S11		Same as above with fine sand
- 60.0		S12 S13		Medium gray Sandstone
70.0		S14 S15	100 100 100 100 100 100 100 100 100 100	
- 80.0		\$16	Principles of the control of the con	
- 90.0		S17 S18	10000000000000000000000000000000000000	
		S19		color to light gray Sandstone
- 100.0-		S20 S21	200 mg mg	Medium gray Shale
- 110.0-		S22		Possible coal (black sheen in return water)
		S23		
- 120.0 - 				
- 130.0-				
- 140.0				
150.0				



Soil Boring Log

Boring No: B-1008

Date: 11/23/2010	Proj. No.: E10028	Project: Big Sandy
Client: AEP		Location: Louiza, Ky
Drilling Company: Front	z Drilling, Inc.	Driller:
Logged By: Larry Retz		Drilling Method: Sonic/HQ core
Surface Elevation:	C 1	Top of Casing Elevation:
Total Depth: 200'	Diameter: 6"-15"	Sampling Method:
Comments:		- 176 766 4 7

Depth (feet)	Sample #	Litholog	Description/Soil Classification (Color, Texture, Moisture, Structures)
(ieet)	111		Medium gray medium to very coarse Sandstone
160.0-		Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles Principles	Medium gray medium to very coatse Sandstone
100.0			
		H + 1	
170.0		H	1
. 1		Ш	
·			
180.0-		H	
- 1		H + I	
190.0-			
150.0			
		H + H	
200.0-			
J		Ш	
210.0-		H + 1	
1		H	
220.0-		Ш	
220.07			
		H + H	_
and the second			
230.0-		H	
		H	-
1		H	
		Ш	
		H +	
1			
-		\square	
	111		
1		ПП	
- 1		Ш	_
-		H	
1			
-		H	
-	HI		-
-			⊣



JOB NUMBER BS-CL-2133 MONITORING	WELL CONSTRUCTION
COMPANY Frontz Drilling, Inc.	WELL No KY6556 BORING No. MW-1008 INSTALLED 12-7-10
PROJECT Big Sandy Plant	
COORDINATES 38.18657 N -82.63066 W	
SYSTEM GPS	
	Participant

	—		TOP RISER: FT2
GROUND ELEVATION FT 725		1	
AEP supplied			
GROUTSEAL: Bentonite Grout			
Bariod Quick-Grout			
BENTONITE SEAL: Bentonite Pellets			
3/8" Pel Plug TR 30/60			
SCREEN: dia., 2"x3-1/2" PrePack			TOP BENTONITE SEAL: FT. 53
PVC .007 & .010 slot			-
GRAVEL PACK: #7 in PrePack			
#4 Borehole			
RISER PIPE: , dia , 2" Sch. 40 PVC		_	TOP GRAVEL PACK: FT58
			TOP SCREEN: FT. 60
DVC Centralizer			
SPACERS, DEPTH: PVC Centralizer			
100 ft. and 50 ft.			
Notes:			
Bentonite 3/8" Holeplug			
Bottom 11 ft. of Boring			
9			
			BOTTOM SCREEN: FT 100
			POTTOM MELL ST 100
TA CONTRACTOR OF THE CONTRACTO			BOTTOM WELL: FT. 100
8			BOTTOM GRAVEL PACK: FT. 102
			BOTTOM BORING: FT 113
BLANK JAONT_WELL_LOG CANL LAB.GPJ			
N N N N N N N N N N N N N N N N N N N			



Soil Boring Log

Boring No: B-1009
Page 1 of 2

Date: 11/18/2010	Proj. No.: E10028	Project: Big Sandy		
Client: AEP		Location:		
Driffing Company: Front	z Drilling, Inc.	Driller:	W	
Logged By: Larry Reitz		Drilling Method: Air Rotary		
Surface Elevation:		Top of Casing Elevation:		
Total Depth: 124'	Diameter:	Sampling Method:		
Comments:		9 350 - Attitude - Att		

Depth	REC /	· ·	1. 4		Lithology	Description/Soil Classification
(feet)	RQD	Sample #		Sample # Lith		(Color, Texture, Moisture, Structures)
				П	iidi	
L 4				Ц		
					Page 1	
- 10.0 -				Н	1000	
			SI	П	2000 E	Yellow brown Sandstone
F 1				П		
- 20.0			S2	Н		
			34	Н	14010	
F 1			S3	П		1
- 30.0 -				Н	- 100	
			S4	П	100	
- 1	- 1			\vdash		1
- 40.0 -			S5	Ц		
40.0			S6			Gray Shale
F 4	1		30	H	- 1	
50.0			S7			Yellow brown Sandstone
- 50.0 -				П		Gray Shale
			88	Н	-	- The state of the
			S9	П		
- 60.0 -		1 1 1		H	1 =	1
L 1			S10	Ц		
			S11			Water encountered at approximately 68' bgs; (added water, black sheen in return)
- 70.0 -			311	Н	-	The service of the se
			S12			Possible coal
F 1				П	100000000 1000000000000000000000000000	
- 80.0 -			S13	H		
100000			S14	П	1000	Light gray Sandstone
- 1	-			H		1 ^ ^ ^
- 90.0 -			S15	Ц		
2772			S16		B TREATMENT OF THE PARTY OF THE	Color grades to medium gray
+ 1	Ď I			\vdash		Davids and
- 100.0-	6		S17	Ц		Possible coal
100.0			S18			Medium gray Shale
			310	Н	-	Made (10) (40) (40) (40) (40) (40)
1 1			S19			
-110.0-			2005	H		
] [S20			
			020	H		
			S21			
-120.0-			S21	Н	┪	
			344			
				H		
1 1				П		
- 130.0-				\vdash		
F 4				H		
- 140.0 -				\sqcup		
10-58						
				Ц	4 L	
_ 150.0_						
130.0				Π		
				Щ		L



Soil Boring Log

Boring No: B-1009
Page 2 of 2

Date: 11/23/2010 Proj. No.: E10028	Project: Big Sandy
Client: AEP	Location: Louiza, Ky
Driffing Company: Frontz Drilling, Inc.	Driller:
Logged By: Larry Retz	Drilling Method: Sonic/HQ core
Surface Elevation:	Top of Casing Elevation:
Total Depth: 200' Diameter: 6"-15"	Sampling Method:
Commonter	

epth eet)	Sample #	Lithology	Description/Soil Classification (Color, Texture, Moisture, Structures)
,	TTTT		Medium gray medium to very coarse Sandstone
_			intending gray intending to very coarse samustone
0.0		$H \vdash$	
		+	-
1			
4		$H \vdash$	
ı			
1		+	
		\bot	
-	111 +	+	1
1		ПГ	
4		+	
1		+	
1		\bot	
+		$H \vdash$	
1		ПГ	
-		+	
1		H	1
1		\bot	
-		$H \vdash$	
-		+	1
1		\top	1
		$H \vdash$	-
1		H	1
1		\bot	
+		+	1
1		\sqcap	
-		$H \vdash$	
1	\vdash	+ -	1
]		\bot	
- 1			



JOB NUMBER BS-CL-2133 MONITORING
COMPANY Frontz Drilling, Inc.
PROJECT Big Sandy Plant
COORDINATES 38.17955 N -82.62633 W
SYSTEM GPS

BLANK_MONT_WELL_LOG CAYL LAB.GPJ AEP.GDT 112408

WELL No KY6557BORING No. MW-1009INSTALLED 12-7-10

	Ţ]		TOP RISER: FT 2
GROUND ELEVATION FT 733				and the same of th
			W/W	
AEP supplied			Y////	
GROUTSEAL: Bentonite Grout				
Bariod Quick-Grout				
BENTONITE SEAL: Bentonite Pellets				
3/8" Pel Plug TR 30/60				
3/8" Per Prug 1R 30/80				
SCREEN: da., 2"x3-1/2" PrePack				TOP BENTONITE SEAL: FT 58
PVC .007 & .010 slot				
GRAVEL PACK: #7 in PrePack				
#4 Borehole				
RISER PIPE: , dla , 2" Sch . 40 PVC				TOP GRAVEL PACK: FT. 63
				TOP SCREEN: FT. 65
SPACERS, DEPTH: PVC Centralizer				
^				
Notes:	/ / / / / / / / / / / / / / / / / / /			
Bentonite 3/8" Holeplug				
Delicolitic 570 Hoteping				
Bottom 37 ft, of Boring				
BOLLOM ST IC, OF BOILING				
				BOTTOM SCREEN: FT. 85
		1		
				BOTTOM WELL: FT. 85
				BOTTOM GRAVEL PACK: FT 87
				BOTTOM BORING: FT 124
				*



Soil Boring Log

Boring No: B-1010
Page 1 of 2

Date:	Proj. No.: E10028	Project: Big Sandy
Client: AEP		Location:
Drilling Company: Front	Drilling, Inc.	Driller:
Logged By: Larry Reitz		Drilling Method: Air Rotary
Surface Elevation:	Charles and Charle	Top of Casing Elevation:
Total Depth: 200'	Diameter:	Sampling Method:
Comments:		

Depth	REC /	Sample #	Lithology	Description/Soil Classification
(feet)	RQD	Oampic #		(Color, Texture, Moisture, Structures)
1				
10.0			# 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
		S1 S2	1915	Red gray Sandstone
1		S2	T	
- 20.0	. 1	S3 -	$H \blacksquare H$	
. 4		S4 -	4 = -	
20.0				
- 30.0 -		85		Medium gray Shale
				Coal
- 40.0 -		S6 _	_	
		S7		Medium gray Shale
		S8		
- 50.0 -			+	
		S9 -	4 = -	
- 60.0 -		S10		
0.00		811		
- 1				
- 70.0 -		S12	₩₽	
		S13	╜≣╚	
		S14		
- 80.0				Coal with carbonaceous Shale
- 4		S15		
90.0		S16		Medium gray Shale
		\$17		
. 1		S18		
- 100.0-				Same as above with some sand
		S19	₩	Same as above with some same
		\$20		
- 110.0-				
		S21		
- 120.0-		S22 S23	4=-	
		323		
. 1			+	
		S24		
- 130.0-				
. 4		S25	+ = +	
		S26		
140.0-		320		
		S27		Medium gray Shale
-				
150.0-		S28		
150.02				



Soil Boring Log

Boring No: B-1010 Page 2 of 2

Date:	Proj. No.: E10028	Project: Big Sandy	
Client: AEP		Location: Louiza, Ky	
Drilling Company: Front	z Drilling, Inc.	Dritter:	
Logged By: Larry Retz		Drilling Method: Air Rotary	
Surface Elevation:		Top of Casing Elevation:	
Total Depth: 200°	Diameter:	Sampling Method:	
Comments:			

	lenth			Description/Soil Classification
S29 S30 S31 S32 Gray Sandstone Gray Shale S35 S36 S37 S38 Same as above with some sand	epth feet)	Sample #	Lithology	(Color, Texture, Moisture, Structures)
S30	(eet)	S29		(Color, restart, mostart, structure)
S31 S32 Gray Sandstone Gray Shale S35 S36 S36 S37 S38 S38 S38 S38 S38 S38 S38 S39 Same as above with some sand Same as ab		S30		
S31 S32 Gray Sandstone Gray Shale S35 S36 S36 S37 S38 S38 S38 S38 S38 S38 S38 S39 Same as above with some sand Same as	60.0-			7
Gray Sandstone Gray Shale S35 S36 S37 S38 Same as above with some sand	1	S31		
S33 S34 Gray Shale S35 S36 S36 S37 S38 Same as above with some sand	1	S32		
S33 S34 Gray Shale S35 S36 S36 S37 S38 Same as above with some sand			14040	Gray Sandstone
\$33 \$34 \$35 \$36 \$37 \$38 \$38 \$38 \$38 \$38 \$38 \$38	70.0			
S35 S36 S37 S38 Same as above with some sand		S33		Gray Shale
80.0- 90.0- S37 S38 Same as above with some sand 90.0-		\$34	TIE	
S35 S36 S37 S38 Same as above with some sand				
S36 S37 S38 Same as above with some sand	80.0-			1
S36 S37 S38 Same as above with some sand	5	S35		
Same as above with some sand Same as above with some sand	1	S36		1
Same as above with some sand Same as above with some sand			1000000	1
	90.0	S37		C
		\$38		Same as above with some sand
	1			
	000			
	00.0			1
	- 1			
	1		T1 F	1
	10.0			1
	1		1	1
	- 1			
	1		+	1
	į.	$I \cup I$		
	-1		+	
		\perp		
	- 1		+	1
	- 1			
	-1		+	-
	- 1			
	1		+	1
	-1		+	1
	- 1			
	1		+	1
	1		+	
	1		+	
	1	1	+ +	1
	1		+	
	1		+	
	-		+	
	-		+	1
	-		+	
	4		+	
	-	HI	+	-
4 1 1 1 1 1 1				
	-	HIL	4 -	



JOB NUMBER BS-CL-2133 MONITO	ORING WELL CONSTRUCTION
COMPANY Frontz Drilling, Inc.	WELL NoKY6558 BORING No. MW-1010 INSTA
PROJECT Big Sandy Plant	
COORDINATES 38.17721 N -82.63093	W
SYSTEM GPS	-

		TOP RISER: FT2
GROUND ELEVATION FT. 849		
AEP supplied		
GROUTSEAL: Bentonite Grout		
Bariod Quick-Grout		
BENTONITE SEAL: Bentonite Pellets		
3/8" Pel Plug TR 30/60		
SCREEN: dia., 2"x3-1/2" PrePack		TOP BENTONITE SEAL: FT. 163
PVC .007 & .010 slot		
GRAVEL PACK #7 in PrePack		
#4 Borehole		
RISER PIPE: , dia., 2" Sch. 40 PVC		TOP GRAVEL PACK: FT 168
	_	TOP SCREEN: FT. 170
SPACERS, DEPTH: PVC Centralizer		
100 ft, 160 ft, 200 ft		
Notes:		
Bentonite 3/8" Holeplug		
The state of the s		
b Boccom 44 Ic. of 2011mg		
Bottom 44 ft. of boring		BOTTOM SCREEN: FT. 200
מאו		BOTTOM WELL: FT. 200
2		BOTTOM GRAVEL PACK: FT 201
		BOTTOM BORING: FT. 245
BLANK, MONT_WELL_LOG GWIL LAB.		
2		



Soil Boring Log

Boring No: 1011
Page 1 of 2

Client: Drilling Logged Surface	Company: By: Larry Elevation: cpth: 80'	Frontz Drilling	Proj. No.:	Location: Ash pond (south) Driller: Drilling Method: Sonic/HQ core Top of Casing Elevation:
				Description/Soil Classification Sample Number
Depth (feet)	REC / RQD	Well Construction	Lithology	(Color, Texture, Moisture, Structures)
(ict)	KQD	III	T Hill	Fill
_ 5.0 _				Mottled very light gray and red Clay mottled medium red brown and light gray weathered Shale Light gray Clay with limonite stains and yellow brown very fine sand, silty
- 10.0				Gray brown very fine Sand, some yellow brown clay
				Light yellow brown silty Clay; medium gray shale with limonite beds
- 15.0 - -	0%			Dark gray green Shale pieces
- 20.0 -				
	- 1			Dark gray green wethered Shale
- 25.0 -	8' 50%		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	
			H	
- 30.0 -			-	
				Grades to medium gray medium to coarse Sandstone
- 35.0 -	8.8' 51%		8120 State	•
- 40.0 -			100 100 100 100 100 100 100 100 100 100	
-			2000 000 1000 000 1000 1000 000 1000 00	Same as above with limonite staining
- 45.0 -	8.4' 78%		100 100 100 100 100 100 100 100 100 100	
- 1				
→ 50.0 -				
1	10'			Medium gray fine to coarse Sandstone; fine interbedded medium gray shale and medium to coarse sandstone
- 55.0 -	71%		THE REPORT OF THE PARTY OF THE	
1			Official and a second and a sec	
- 60.0 -	- 1		Ended Sector	Meduim gray coarse to very coarse Sandstone
				Carbonaceous lens at 62.6 to 63.1
	9.9' /			
- 65.0 -	53%			Medium gray medium to coarse Sandstone, grades to very coarse Sandstone
				To an about the Transaction of the person of the County Transaction and the Advantage County of the
- 70.0 -				
- 1			1	
750				

Dark gray Shale lens



Soil Boring Log

Boring No: 1011 Page 2 of 2

Date: 11/23/2010 Proj. No.: E10028	Project: Big Sandy
Client: AEP	Location: Louiza, Ky
Drilling Company: Frontz Drilling, Inc.	Driller:
Logged By: Larry Retz	Drilling Method: Sonic/HQ core
Surface Elevation:	Top of Casing Elevation:
Total Depth: 200' Diameter: 6"-15"	Sampling Method:
Comments:	

epth feet)	T	Well onstruction	Litholog	Description/Soil Classification	Sample Number
feet)		onstruction	1 Helst	(Color, Texture, Moisture, Structures)	
9.7	/		Ded Colored Ded Colored	Medium gray medium to very coarse Sandstone	
17	47%	1 1	200	7	
80.0					
- 1	1		\mathbf{H}		
		1 1	+		
				ł c	
1			11	1	
1			\perp		
+			+	-	
l li					
1			11 1	1	
			Ш		
			H	_	
-		1 1	+	7	
1			П		
1			4 !		
4		1	+	-	
1			T1	7	
			ш		
			H	-	
-			+	-	
1			\Box		
-1			\mathcal{H}	_	
-			+	1	
1					
_			$H \mid$		
-		-	+	-	
1			11		
			4		
-			+		
+			+		
1			\Box		
]			Ш		



JOB NUMBER BS-CL-2133 MONITOR						ALE
COMPANY Frontz Drilling, Inc.						12 0 10
PROJECT Big Sandy Plant		WEL	L No.	.033	BORING No. MWIUII	INSTALLED 12-8-10
COORDINATES 38.17819 N -82.63071 V	7					
SYSTEM GPS						
			7		ACTION OF THE COLOR	
		Т	T		TOP RISER: FT2	
GROUND ELEVATION FT. 685	SMILL	d	mm	VIII	777897778977	
AEP supplied						
					///////////////////////////////////////	
GROUTSEAL: Bentonite Grout						
Remind Out the Count						
Bariod Quick-Grout						
- <u> </u>						
BENTONITE SEAL: Bentonite Pellets				ķ		
3/8" Pel Plug TR 30/60						
SCREEN: da., 2"x3-1/2" PrePack					TOP BENTONITE SEAL: F	т. 28
PVC .007 & .010 slot						
GRAVEL PACK: #7 in PrePack						
#4 Borehole						
RISER PIPE: , dia., 2" Sch. 40 PVC	VIIII		VIIII A		TOP GRAVEL PACK: FT.	33
		==			TOP SCREEN: FT. 35	
SPACERS, DEPTH: PVC Centralizer						
			1			
Notes:		量量				
			71			
-	1					
	1					
					POTTOM POPERAL PE	75
					BOTTOM SCREEN: FT	75
	1	إ			BOTTOM WELL: FT. 7	5
<u> </u>						
	//YYYYY	77777		_	MITTOM CONTEL BACK, F	T 01

BOTTOM BORING; FT. 81

BLANK JACHT_WELL_LOG CAYL LABGRU AEP.GDT 112409

2010 REVISED BORING LOGS AND WELL CONSTRUCTION DIAGRAMS



JOE	NUN	MBER _					-				i bortiivo					
																OF
PRO	JEC	⊤ BIG	SANE	PΥ						ВС	RING START _	12/7/10) BO	ORING FINISH	12	2/7/10
CO	ORDI	NATES								PII	ZOMETER TYP	E		_ WELL TYPE		
GRO	DUNE	D ELEVA	TION_	692.0	SY	'STEM				НС	T. RISER ABOV	E GROUN	ND	DIA	5.	78
WA	TER	LEVEL	$\overline{\mathbb{V}}$		<u></u>		$ar{ar{\Lambda}}$			DE	PTH TO TOP OF	WELL S	CREEN_4	7 BOTTOM	_77	7
TIM										W	ELL DEVELOPMI	ENT_Ye	s	BACKFILL	G	rout
DA	 ΓΕ									FIE	ELD PARTY Fr	ontz Dri	illing	RIG		
								ı			T					
SAMPLE	SAMPLE	DE	MPLE PTH EEET	STAN PENET RESIS	DARD RATION TANCE	TOTAL ENGTH COVERY	RQD %	DEPTH IN FEET	RAPHIC LOG	nscs		SOIL / F			WELL	DRILLER'S NOTES
0, 2	. 0)	FROM	ТО	BLOV		, <u>¬</u> #		FEET	ß							
								-	-		BROWN SANI	DSTONE				
								-								
									-							
								5 -]:::::							
								-	<u> </u>							
								-	-							
								10 -								
								-	-							
								-								
								-	-							
		30														
								20 -	-							
								-]:::::							
								-								
								25 -								
								_								
								-	-							
								30 -								
								-	-							
								-								
								35 -								
								35 -	::::							
								-	1::::							
								40	-							
								40 -								
								-								
									-							
	45 -															
2/11/15								-	1::::							
		TVDI		ASINC.	HIGED				<u> </u>		Can	atinuad N	Next Boo			
AEP.GDT	TYPE OF CASING USED NQ-2 ROCK CORE PIEZOMET									Continued Next Page						
Z W	6" x 3.25 HSA SLOT									IETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE OTTED SCREEN, G = GEONOR, P = PNEUMATIC					ZEN IUBE	
P.G		9" x 6.2	5 HSA	DVANCE	:P	4"	-									OF ON ACA!
BS FAP.GPJ		NW CA	SING	PAMINOE	.13	3"	\Rightarrow	WELL T	TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON							
۵.	SW CASING 6" X AIR HAMMER 8"								RECORDER							



JOB	NUM	BER				_		LO	J U	F BURING
		Y							ВС	DRING NOMW-1007 DATE 2/11/15 SHEET 2 OF 2
		BIG S								DRING START 12/7/10 BORING FINISH 12/7/10
SAMPLE	SAMPLE	SAMPL DEPTI IN FEE FROM	E H ET TO	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	nscs	SOIL / ROCK IDENTIFICATION □ DRILLER'S NOTES
		TROM		BLOWOTO			-			
							55 -			
							60 -			
							65 -			GRAY SANDSTONE
							70 -			
							75 -			
							80 - - - - 85 -			GRAY SHALE & COAL
9.GDT 2/11/15										
AEP BS FAP.GPJ AEP.GDT 2/11/15										
4 T T										



JOB	NUM	IBER _							LO	30	F BORING						
COM	MPANYOJECT _ BIG SANDY																
PRO	JEC ⁻	т_ ВІС	SAND	Υ						ВС	RING START	12/7/	10	BORING FINISH	_12	2/7/10	
COC	RDI	NATES _								PIE	ZOMETER TY	PE		WELL TYPE			
GRO	UND	ELEVA	TION_	725.0	SY	STEM _				HG	T. RISER ABC	VE GRO	UND	DIA	5.	78	
WA	ΓFRΙ	LEVEL	$\overline{\nabla}$		lacksquare		1			DE	PTH TO TOP (OF WELL	SCREEN	60 BOTTOM	10	00	
TIMI			-		-		+							BACKFILL			
DAT										FIE							
DAT													•				
SAMPLE	SAMPLE	SAM DEF IN F FROM	EET	PENET RESIS	IDARD RATION TANCE VS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	nscs	BROWN SIL	IDENTI	/ ROCK FICATION		WELL	DRILLER'S NOTES	
								5									
								10 - - - -			BROWN SAI	NDSTON	E				
								15 — - - -									
								20 -									
								25 - - - -									
								30 -									
								35 — - -			GRAY SHAL	E					
								40 -									
2/11/15								45 - - - -									
		TYPE	OF C	ΣΔSING	USED		\top		Continued Nevt Page								
BS FAP.GPJ AEP.GDT	TYPE OF CASING USED NQ-2 ROCK CORE PIEZOME									Continued Next Page							
2 	6" x 3.25 HSA PIEZOME									METER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE OTTED SCREEN, G = GEONOR, P = PNEUMATIC							
P	9" x 6.25 HSA HW CASING ADVANCER 4" WELL TVE																
SS FA		NW CAS	SING	DVANCE	:K	4" 3"		WELL T	TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON								
	SW CASING 6"										RECORDER	₹					
₩ <u>X</u>	AIR HAMMER 8"																



JOB	NUM	IBER _				_		LO	30	DF BORING
		Y							ВС	ORING NO.MW-1008 DATE 2/11/15 SHEET 2 OF 2
		T BIG							ВС	ORING START
SAMPLE	SAMPLE	DEI	MPLE PTH EEET	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	nscs	SOIL / ROCK IDENTIFICATION DRILLER'S NOTES
		FROIVI	10	BLOWS / 6						GRAY SANDSTONE & SHALE
							55 —			
							60 -			BROWN SANDSTONE
							65 -			
							70 -			
	75						75 -			
							80 -			
							85 -			
										GRAY STANDSTONE
AEP BO FAR. GPJ AEP. GDJ Z/11/13										GRAY SHALE
P BS FAP.GP.										



JOB NUMBER	LOG OF BORING
COMPANY	BORING NO.MW-1009 DATE 2/11/15 SHEET 1 OF 3
PROJECT BIG SANDY	10/2/10
COORDINATES	
GROUND ELEVATION 733.0 SYSTEM	
	DEPTH TO TOP OF WELL SCREEN 65 BOTTOM 85
	WELL DEVELOPMENT Yes BACKFILL Grout
TIME	
DATE	FIELD PARTY Frontz Drilling RIG
SAMPLE STANDARD PENETRATION RESISTANCE FROM TO BLOWS / 6" ROW	IN 불이 Ö SOIL / ROCK 및 및 DRILLER'S
	BROWN SANDSTONE
	5 — 10 — 15 — 20 — 25 — 30 — 30 — 30 — 30 — 30 — 30 — 30 — 3
	35 —
	40
	GRAY SHALE
2/11/15	BROWN SANDSTONE
TYPE OF CASING USED	Continued Next Page
TYPE OF CASING USED NQ-2 ROCK CORE 6" x 3.25 HSA 9" x 6.25 HSA HW CASING ADVANCER 4" NW CASING 3"	PIEZOMETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE SLOTTED SCREEN, G = GEONOR, P = PNEUMATIC
HW CASING ADVANCER 4"	WELL TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON
SW CASING 6	RECORDER

8"

AIR HAMMER



JOB	NUM	BER _				_		LO	G O	BORING		
		Y							ВС	RING NO.MW-1009 DATE_2	2/11/15 SHEE	T_2_OF_3
			SAND	Υ						RING START		
											_	
ııı œ	111		1PLE	STANDARD	-≿	RQD	DEPTH	U				
1PLF 1BEI	1PL		PTH	PENETRATION	ZEE		IN	문원	SCS	SOIL / ROCK	WELL	DRILLER'S
SAMPLE	SAN		EET	STANDARD PENETRATION RESISTANCE BLOWS / 6"	드필입	%	DEPTH IN FEET	3RA L(s n	IDENTIFICATION	>	NOTES
		FROM	TO	BLOWS / 6"	22		1	_		ODAY OLIALE		
										GRAY SHALE		
							55 -					
							60 -					
							65 -					
							70 -					
							10					
							75 -					
							80 -					
							-					
							85 -					
							00			GRAY SANDSTONE		
								-				
							90 -			GRAY SHALE		
							95 -					
							100 -					
							105					
ဂ							105					
2/11/2												
 -												
파 -							110 -					
2												
AP. D.												
BS FAP. GPJ AEP. GDI 2/11/15												
] i										Continued Next Pa	age	



JOB NUM	IBER				_		LO	G O	F BORING				
COMPAN	Y							ВС	RING NO.MW-1	1009	DATE 2/11/15	_ SHEET_	3 OF 3
PROJEC ⁻	T_BIG	SAND	Υ					ВС	RING START	12/7/10	BORING F	INISH _12	/7/10
SAMPLE NUMBER SAMPLE	SAM DEF IN F	PLE PTH EET TO	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	nscs		SOIL / F		WELL	DRILLER'S NOTES
	FROM	TO	BLOWS / 6"	T T T T T T T T T T T T T T T T T T T	70	120 -							
							1	1	I				



JOB NUMBER	LOG OF BORING						
COMPANY	BORING NO. MW-1010 DATE 2/11/15 SHEET 1 OF 4						
PROJECT BIG SANDY							
COORDINATES							
GROUND ELEVATION 849.0 SYSTEM							
WATER LEVEL \(\subseteq \)	DEPTH TO TOP OF WELL SCREEN 170 BOTTOM 200						
	WELL DEVELOPMENT Yes BACKFILL Grout						
TIME	FIELD PARTY Frontz Drilling RIG						
DATE							
SAMPLE STANDARD PENETRATION FEET RESISTANCE STANDARD PENETRATION FEET RESISTANCE STANDARD PENETRATION FEET RESISTANCE STANDARD PENETRATION FEET RESISTANCE STANDARD FEET ROD FEET RESISTANCE STANDARD FEET ROD FEE	SOIL / ROCK DRILLER'S DRILLER'S NOTES						
FEET OF FROM TO BLOWS / 6" FEET							
	GRAY SANDSTONE						
5							
	-						
10 -							
15 -	I::::						
	- ::::						
20 -							
-	4888						
25 -	 ::::						
30 -	GRAY SHALE W/COAL						
	OTAT STINLE WIGGAL						
35							
-							
40							
- - - - - - - - -							
-							
45	GRAY SHALE						
2/11/18							
TYPE OF CASING USED	Continued Next Page						
TYPE OF CASING USED	METER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE						
6" x 3.25 HSA SLC	OTTED SCREEN, G = GEONOR, P = PNEUMATIC						
HW CASING ADVANCER 4" WELL T	YPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON						
	RECORDER						
SVV CASING 0	NECONDEN						

8"

AIR HAMMER



JOB	NUM	IBER _				_		LO	GΟ	FBORING		
		Y								RING NO MW-1010 DATE 2/11/15 S		
PRO	JECT	BIG	SAND)Y					ВС	RING START <u>12/6/10</u> BORING FINIS	н <u>1</u> 2	2/6/10
SAMPLE	SAMPLE	DEI	MPLE PTH EEET TO	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	nscs	SOIL / ROCK IDENTIFICATION	WELL	DRILLER'S NOTES
							-					
							55 -					
							60 -					
							65 -					
							-					
							70 -					
							-					
							75 -					
							-					
							80 -	4		BLACK COAL		
							85 -			GRAY SHALE		
							90 -					
							95 -					
							100					
							100 -					
							105					
01/1							105 -			GRAY SHALE & SANDSTONE		
, ed. 2							110 -					
AE AE							110					
P BS FAP.GPJ AEP.GDI Z/11/13												
ם ה										Continued Next Page		



JOB	NUM	BER _				_		LOC	<i>5</i> U	F BORING					
		Y							ВС	RING NO.MW-1	1010	DATE_2	2/11/15	SHEET_	3 OF 4
		BIG		Υ					ВС	RING START					
SAMPLE NUMBER	SAMPLE	SAM DEF IN F	PTH EET	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH ECOVERY	RQD %	DEPTH IN FEET	GRAPHIC LOG	USCS			/ ROCK FICATION		WELL	DRILLER'S NOTES
		FROM	10	BLOWS / 6"	<u>~</u>										
							-								
							-								
							120 -								
							-								
							-								
							125 -								
							-								
							130 -								
							-								
							135 -			GRAY SHALE	E				
							140 -								
							140								
							-								
							145 -								
							-								
							150 -								
							-								
							155 -								
							-								
							160 -								
							-								
							105								
							165 -			GRAY SAND	STONE				
							-								
							170 -								
							170			GRAY SHALE	E				
i															
B							175 -								
							-								
							-								
<u> </u>										_					
										Co	ntınued	Next Pa	ge		



		=K			_				F BORING			
COMPA								ВС	RING NO.MW-1010	DATE 2/11/15	SHEET_	4 OF 4
		BIG SAND	Υ					ВС	RING START12/6			
SAMPLE NUMBER SAMPLE	SAMPLE	SAMPLE DEPTH IN FEET ROM TO	STANDARD PENETRATION RESISTANCE BLOWS / 6"	TOTAL LENGTH RECOVERY	RQD	DEPTH IN FEET	GRAPHIC LOG	nscs		. / ROCK IFICATION	WELL	DRILLER'S NOTES
SAMP STATISTICS AFFICILITIES SAMP SAMP SAMP SAMP SAMP SAMP SAMP	FI FI	IN FEET	RESISTANCE BLOWS / 6"	TOTA TOTA LENG' LENG' RECOV	%	185 - 190 - 200 - 215 - 220 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 - 235 -	GRAPH	080		IFICATION	MEL	



JOB	NUM	IBER _					_				DOMINO				
		Y									RING NO. <u>MW-1011</u>				
		T _ BIG									RING START 12/6				
				1,056.6			04-4	. Di		PIE	ZOMETER TYPE		WELL TYPE	≣	
GRC	UND	ELEVA	TION _	716.2	SY	'STEM	NAI	te Plane usi D83/88	ng	HG	T. RISER ABOVE GROU	JND <u>2.63</u>	3 DIA	△ <u>5</u> .	.78
Wat	er Le	vel, ft	$\overline{\mathbb{Z}}$		<u> </u>		Ā			DE	PTH TO TOP OF WELL	SCREEN _	35 BOTTON	/ <u>7</u>	5
TIMI	E									WI	LL DEVELOPMENT	Yes	BACKFILI	L <u>G</u>	rout
DAT	E									FIE	LD PARTY Frontz	Drilling	RIC	3 <u> </u>	
SAMPLE	SAMPLE	DE	MPLE EPTH EEET TO		DARD RATION TANCE VS / 6"	TOTAL LENGTH RECOVERY	RQD %	IN FEET	GRAPHI	SOSO	IDENT	L / ROCK TIFICATION		WELL	DRILLER'S NOTES
								5	1		RED CLAY	CHALE			
								10	=		GRAY AND BROWN S	SHALE			
								15	=						
								20	+		GRAY SHALE				
									#						
								25							
								30	= : : : :		GRAY SANDSTONE V	N/SHALF			
								35	3::::		0.01. 0.1.20.01.2				
								40	∃						
									#::::						
								45] :::::						
								50	ქ::::						
								55	3::::						
								60	4::::						
									4::::						
								65	3						
								70	==:::::						
								75	3::::						
								00			GRAY SANDSTONE				
								80							
9/15															
<u>-</u>															
BS FAP.GPJ AEP.GDT 11/19/15		TYP	E OF C	ASING	USED										
AEP			OCK CC	RE							: PT = OPEN TU				EN TUBE
GPJ	+	6" x 3.2 9" x 6.2					\dashv	SL	OTTE	ED S	CREEN, G = GEOI	NOR, P =	PNEUMATIC		
FAP		HW CA	SING AE	OVANCER	₹	4"		WELL 7	TYPE:	O	V = OPEN TUBE S	LOTTED	SCREEN, GN	Л = G	EOMON
BS		NW CA SW CA				3" 6"					RECORDER				
₩ X		AIR HA				8"					תבטטאטבא				



JOB	NUM	IBER _							LO		r boring					
COMPANY							BORING NO. <u>MW-1012</u> DATE <u>11/19/15</u> SHEET <u>1</u> OF <u>2</u>					1 OF2				
PROJECT BIG SANDY								ВС	RING START	_1	2/8/10	BORING FINISH	_12	2/8/10		
COORDINATES N 249,566.1 E 2,103,715.6								PIE	EZOMETER T	YPE _		WELL TYPE				
GROUND ELEVATION 787.9 SYSTEM NA					Stat NAD	State Plane using IAD83/88 H			ST. RISER AB	OVE G	ROUND	55 DIA	<u>5.</u>	78		
			Ā			DE	EPTH TO TOP OF WELL SCREEN110_ BO			110 _ BOTTOM	_14	10				
	TIME							W			ELL DEVELOF	PMENT	Yes	BACKFILL	G	rout
DAT	DATE							FI			ELD PARTY _	Fron	tz Drilling	RIG		
				T			I				1					
SAMPLE	SAMPLE NUMBER SAMPLE		AMPLE STANDARD DEPTH PENETRATION N FEET RESISTANCE OM TO BLOWS / 6"			LENGTH RECOVERY	RQD %	INI	GRAPHIC LOG	USCS		SOIL / ROCK IDENTIFICATION			WELL	DRILLER'S NOTES
				=			SOIL									
								5 - 10 -			BROWN SH	HALE				
									15 20							
						25										
								30								
						35			GRAY SHA	LE						
								40 -								
								45 -								
						\dashv		50 -								
								55								
						60 -										
							65 - 70 - 75 - 75 - 75 - 75 - 75 - 75 - 7									
								_								
								80 -								
		85														
								90 -								
								95 -								
								=								
								100 -								
								105								
								110			CDAV SAN	DSTO*	TONE & SHALE			
								115 -			GIVAT SAIN	יוטוטו	NL & SI IALE			
ا							=									
11/19/1							1	120 -								
BS FAP.GPJ AEP.GDT 11/19/15	TYPE OF CASING USED							Continued Next Page								
NQ-2 ROCK CORE 6" x 3.25 HSA						PIEZOMETER TYPE: PT = OPEN TUBE POROUS TIP, SS = OPEN TUBE SLOTTED SCREEN, G = GEONOR, P = PNEUMATIC										
9" x 6.25 HSA HW CASING ADVANCER 4"						WELL TYPE: OW = OPEN TUBE SLOTTED SCREEN, GM = GEOMON						FOMON				
											LOIVIOIN					
SW CASING 6" X AIR HAMMER 8"						RECORDER										



			DODING NO. MW 1012 DATE 11/19/15 SHEET 2 OF 2					
COMPANY PROJECT _ BIG SAN I	ny		BORING NO. <u>MW-1012</u> DATE <u>11/19/15</u> SHEET <u>2</u> OF <u>2</u> BORING START <u>12/8/10</u> BORING FINISH <u>12/8/10</u>					
ROJECT BIO GAIN	<u> </u>		BORING START TEIGHT BORING FINISH TEIGHT					
SAMPLE DEPTH IN FEET FROM TO	STANDARD PENETRATION RESISTANCE BLOWS / 6" RQD DEI RQD W RQD FE	ZAPH LOG	SOIL / ROCK DIDENTIFICATION SOIL / ROCK NOTES					
FROM TO	13 13 14 14 15 16 16 17 17 18 18 19 20 20		GRAY SHALE & SANDSTONE					



JOB NUMBER	ELE GONOTINGOTION						
COMPANY	WELL No. MW-1010 BORING No. MW-1010 INSTALLED 12/8/10						
PROJECT BIG SANDY							
COORDINATES N 250,692.0 E 2,105,790.1							
SYSTEM State Plane using NAD83/88							
	— TOP RISER: 849.04 FT.						
GROUND ELEVATION 846.42 FT.							
SASSAS ZZZVANSKY SASZZVA							
GROUT SEAL: Bentonite							
XIIIIIV							
BENTONITE SEAL: Grout	TOP BENTONITE SEAL: 683.42 FT.						
E E E CODEEN OU II DIVO CAO COI							
SCREEN: 2" dia., PVC .010, 30'							
GRAVEL PACK:	— TOP GRAVEL PACK: 678.42 FT.						
	10F GRAVEL FACK: 0/0.4211.						
RISER PIPE: , dia., PVC	— TOP SCREEN: 676.42 FT.						
The latest the latest terms of the latest term							
	<u>서를 크</u> 셨다						
SPACERS, DEPTH:							
1							
Notes: KY Well #6558 Temporary 7.25" borehole to depth of 13' w/6" casing to depth of 14'	성 <u>트림</u> (첫성)						
depth of 14*	<u> </u>						
	()						
<u>.</u>	BOTTOM SCREEN: 646.42 FT.						
	BOTTOWIOCILLIN. 040.42 FT.						
	— BOTTOM WELL: 646.42 FT.						
	20.10						
	BOTTOM GRAVEL PACK: 645.42 FT.						
S FAP. GFU 11/1/16							
n	//////////////////////////////////////						



JOB NUMBER	,					
COMPANY	WELL N	No. <u>MW</u> -	-1011	BORING No. MW-1011	INSTALLED 12/6/10	
PROJECT BIG SANDY						
COORDINATES N 251,056.6 E 2,105,873.3						
SYSTEM State Plane using NAD83/88						
		٦				
		_		TOP RISER: 718.78 FT.		
GROUND ELEVATION 716.15 FT.						
CHOONS ELEVATION 710.1311.						
			Y//\\\\//			
GROUT SEAL: Bentonite						
BENTONITE SEAL: Grout	>>>			TOP BENTONITE SEAL:	688.15 FT.	
SCREEN: 2" dia., PVC .010, 30'						
GRAVEL PACK:						
	<u> </u>	(/////		TOP GRAVEL PACK: 683	3.15 FT.	
				TOD 00000000 000 00 00	_	
RISER PIPE: , dia., PVC				TOP SCREEN: 681.15 FT	•	
SPACERS, DEPTH:						
사람들은 사람들이 가장 하는 것이 없었다.						
	=					
Notes: KY Well #6559 Temporary 7.25" borehole to depth of 13' w/6" casing to depth of 14'						
depth of 14'						
	·: ·: /=====					
ه ا						
				BOTTOM SCREEN: 641.	15 FT.	
F						
10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00 10.00				BOTTOM WELL: 641.15 I	FT.	
S FAP. GPJ AEP. GDJ 11/19/15	<i>,,,,,,,</i>	,,,,,,,		BOTTOM GRAVEL PACK	(: 635.15 FT.	
				DOTTOM DODING: COE 4	is st	



JOB NUMBER	ITORING WELL CONSTR	RUCTION	
COMPANY	WELL No. MW-10	12 BORING No. MW-1012	INSTALLED 12/8/10
PROJECT BIG SANDY			
COORDINATES N 249,566.1 E 2,103,715.6			
SYSTEM State Plane using NAD83/88			
		— TOP RISER: 790.56 FT.	
GROUND ELEVATION 787.91 FT.		///////////////////////////////////////	
////~///~		//~///~///~///	
GROUT SEAL: Bentonite			
		TOD DELITOR WITE OF 11	
BENTONITE SEAL: Grout		TOP BENTONITE SEAL:	684.91 FT.
SCREEN: 2" dia., PVC .010, 30'			
GRAVEL PACK:			
GRAVEL PACK.		TOP GRAVEL PACK: 679	9.91 FT.
RISER PIPE: , dia., PVC		— TOP SCREEN: 677.91 F	Γ.
SPACERS, DEPTH:			
Notes: KY Well #6561			
Temporary 7.25" borehole to depth of 15' w/6" casing depth of 16'	g to		
dopar or to			
		BOTTOM SCREEN: 647.	91 FT.
		BOTTOM WELL: 647.91	FT.
		BOTTOM GRAVEL PACK	ር: 644.91 FT.
		— BOTTOM BORING: 577.9	91 FT.