

CLOSURE CERTIFICATION BY QUALIFIED PROFESSIONAL ENGINEER

I certify that the AEP Mitchell Bottom Ash Pond has been closed in accordance with the most recent written closure plan specified by 40 CFR 257.102(b) and the requirements of 40 CFR 257.102.

David Anthony Miller

Printed Name of Licensed Professional Engineer

David Anthony Miller

Signature



22663

License Number

West Virginia

Licensing State

01.15.2025

Date

Closure Completion Notification for Closure by Removal

January 15, 2025

Closure Completion Notification

Mitchell Plant

Bottom Ash Pond

On December 24, 2024, the Mitchell Plant Bottom Ash Pond was transitioned to closure status in accordance with 40 CFR 257.102. This notice of completion of closure is being placed in the operating record in accordance with 40 CFR 257.102(h).

Effective with the Closure Completion Notification, the former ash storage site is no longer a CCR unit. The following operating record documents are no longer required going forward:

- Hazard Potential Classification
- Emergency Action Plan (EAP)
- Face to Face Meeting Documentation for EAP
- History of Construction and Revisions for Surface Impoundments
- Structural Stability Assessments
- Safety Factor Assessments
- Fugitive Dust Plan
- Inflow Design Flood System Control Plan

VERDANTAS CERTIFICATION


Based on the construction observations performed by Verdantas representatives, I hereby certify that the Bottom Ash Pond West Basin at the Mitchell Plant in Moundsville, West Virginia, as shown on the record drawing located in Appendix C, has achieved removal of all CCR material and soil with constituent concentrations above relevant background standards (i.e., closed by removal) in substantial compliance with the Construction Quality Assurance (CQA) Plan for Pond Closure and Repurposing, the Construction Drawings for the CCR/ELG closure by removal project, Bottom Ash Pond Closure and Repurposing Contract as provided by Worley (December 3, 2021) and as per 40 CFR 257.102, and as clarified herein. The groundwater monitoring and compliance aspect of CCR Unit closure by removal criteria, as found at 40 CFR 257.102(c), will be certified under a separate report. The Contractor (R.B. Jergens) obtained the survey data used to develop the record drawing. R.B. Jergens verified that the elevations met the closure requirements, and Verdantas also reviewed the survey data.



Chris Goddard
Quality Assurance Officer/CQA Manager



Allen J. Smith Jr., PE
Certifying Engineer
WV PE# 020463



VERDANTAS CERTIFICATION

Based on the construction observations with associated photographic records, testing performed by Verdantas representatives in the field and documented in this report, I hereby certify to the best of my knowledge and to the extent of available information that the East Wastewater Pond at the Mitchell Plant in Moundsville, West Virginia, as shown on the record drawing located in Appendix B, has achieved removal of all CCR material and one foot (minimum) of underlying native soil in substantial compliance with the Construction Quality Assurance (CQA) Plan for Pond Closure and Repurposing, the Construction Drawings for the CCR/ELG Project, the Bottom Ash Pond Closure and Repurposing Contract as provided by Worley (December 3, 2021), per 40 CFR 257.102 and as clarified herein. The groundwater monitoring and compliance aspect of CCR Unit closure by removal criteria, as found at 40 CFR 257.102(c), will be certified under a separate report. This certification is strictly limited to CQA observations and associated field testing and does not include an engineering analysis of previously approved and permitted engineering designs or subsequent approved design/field changes. The Contractor (R.B. Jergens) obtained the survey data used to develop the attached record drawing. R.B. Jergens verified that the elevations met the construction requirements, and Verdantas also reviewed the survey data.



Chris Goddard
Quality Assurance Officer/CQA Manager



Allen J. Smith Jr., PE
Certifying Engineer
WV PE# 020463



4/4/2024

HISTORY OF CONSTRUCTION

CFR 257.73(c)(1)

Bottom Ash Complex

Mitchell Power Plant
Marshall County, West Virginia

October, 2016

Prepared for: Wheeling Power Company & Kentucky Power Company

Prepared by: American Electric Power Service Corporation

1 Riverside Plaza

Columbus, OH 43215



GERs-16-085

Table of CONTENTS

1.0 OBJECTIVE	3
2.0 DESCRIPTION OF CCR THE IMPOUNDMENT	3
3.0 SUMMARY OF OWNERSHIP 257.73(c)(1)(i)	3
4.0 LOCATION OF THE CCR UNIT 257.73 (c)(1)(ii)	3
5.0 STATEMENT OF PURPOSE 257.73 (c)(1)(iii)	4
6.0 NAME AND SIZE OF WATERSHED THE CCR UNIT IS LOCATED 257.73 (c)(1)(iv)	4
7.0 DESCRIPTION OF THE FOUNDATION AND ABUTMENT MATERIALS 257.73(c)(1)(v)	4
8.0 DESCRIPTION OF EACH CONSTRUCTED ZONE OR STAGE OF THE CCR UNIT 257.73 (c)(1)(vi)	4
9.0 ENGINEERING STRUCTURES AND APPURTENANCES, 257.73 (c)(1)(vii)	5
10.0 SUMMARY OF POOL SURFACE ELEVATIONS, AND MAXIMUM DEPTH OF CCR, 257.73 (c)(1)(vii)	5
11.0 FEATURES THAT COULD ADVERSELY AFFECT OPERATION DUE TO MALFUNCTION OR MIS-OPERATION 257.73 (c)(1)(vii)	6
12.0 DESCRIPTION OF THE TYPE, PURPOSE AND LOCATION OF EXISTING INSTRUMENTATION 257.73 (c)(1)(viii)	6
13.0 AREA - CAPACITY CURVES FOR THE CCR UNIT 257.73 (c)(1)(ix)	7
14.0 DESCRIPTION OF EACH SPILLWAY AND DIVERSION 257.73 (c)(1)(x)	7
15.0 SUMMARY CONSTRUCTION SPECIFICATIONS AND PROVISIONS FOR SURVEILLANCE, MAINTENANCE AND REPAIR 257.73 (c)(1)(xi)	8
16.0 RECORD OR KNOWLEDGE OF STRUCTURAL INSTABILITY 257.73 (c)(1)(xii)	8

Attachments

- Attachment A – Location Map
- Attachment B – Subsurface Investigation
- Attachment C – Design Drawings
- Attachment D – Instrumentation Location Map
- Attachment E – Hydrology and Hydraulic Report

1.0 OBJECTIVE

This report was prepared by AEP- Geotechnical Engineering Services (GES) section to fulfill requirements of the CCR rule section 257.73(c)(1).

2.0 DESCRIPTION OF CCR THE IMPOUNDMENT

The Mitchell Bottom Ash Pond Complex is located at the Mitchell Power Plant in Marshall County, West Virginia. The impoundment was constructed in 1977 and is comprised of a Bottom Ash Pond and a Clear Water Pond. The purpose of the pond is for the disposal of Bottom Ash produced at the Mitchell Power Plant.

The complex is surrounded by the Mitchell Power Plant on its north side, West Virginia State Route 2 on its east side, the adjacent wallboard facility and ancillary structures on its south side, and the metal cleaning tank, railroad tracks, and the Ohio River on its west side. The Bottom Ash Pond Complex is approximately 17 acres in size and consists of two impounding facilities, the Bottom Ash Pond which is approximately 10 acres, and the Clear Water Pond which is approximately 7 acres. The Bottom Ash Pond comprises the north portion of the complex and the Clear Water Pond comprises the southern portion. The Mitchell Bottom Ash Complex is regulated by the West Virginia Division of Water and Waste Management (WVDWWM) as a Hazard Class "2" Structure.

The Bottom Ash Pond is separated into ponding areas in its western and northeastern portions. In general, the bottom ash is sluiced into the northeastern portion of the pond; where after, the sluice water is routed through an interior splitter dike to the western portion of the pond. Flow through the western portion of the pond is routed around three interior flow diversion dikes. The southeastern portion of the Bottom Ash Pond is above the normal operating pool (pond) level and is used as an excavation and loadout area for bottom ash.

The Bottom Ash Pond and Clear Water Pond were constructed partially as incised ponds and partially using raised dike construction. Specifically, the pool level on the east side of the pond complex is generally below the bottom elevation of the east dike. The inside slopes of the Bottom Ash Pond and Clear Water Pond are lined with a composite soil and PVC liner.

3.0 SUMMARY OF OWNERSHIP 257.73(c)(1)(i)

[The name and address of the person(s) owning or operating the CCR unit: the name associated with the CCR unit: and the identification number of the CCR unit if one has been assigned by the state.]

The Mitchell Power Plant is located at 8999 Energy Road, Gate 3, Moundsville, WV 26041. The Mitchell Bottom Ash Pond Complex is equally owned by Wheeling Power Company and Kentucky Power Company (KPC) and it is operated by KPC. The WVDWWM ID number is 05108.

4.0 LOCATION OF THE CCR UNIT 257.73 (c)(1)(ii)

[The location of the CCR unit identified on the most recent U.S. Geological Survey (USGS) 7 ½ minute or 15 minute topographic quadrangle map, or a topographic map of equivalent scale if a USGS map is not available.]

A location map is included in Attachment A.

5.0 STATEMENT OF PURPOSE 257.73 (c)(1)(iii)

[A statement of the purpose for which the CCR unit is being used.]

The Bottom Ash Pond is a surface impoundment for the purpose of disposal and storage of bottom ash. Bottom Ash is settled and stored until it is removed and landfilled. The pond also receives other plant miscellaneous waste streams.

6.0 NAME AND SIZE OF WATERSHED THE CCR UNIT IS LOCATED

257.73 (c)(1)(iv)

[The name and size in acres of the watershed within which the CCR unit is located.]

The Bottom Ash Pond Complex is located with the Upper Ohio Wheeling watershed (HUC: 05030106) which has a listed acreage of approximately 962,298 acres. The Bottom Ash Pond Complex is a diked impoundment where the only inflows are from plant process water. There is no stormwater run-on from an offsite watershed.

7.0 DESCRIPTION OF THE FOUNDATION AND ABUTMENT MATERIALS

257.73(c)(1)(v)

[A description of the physical and engineering properties of the foundation and abutment materials on which the CCR unit is located.]

The foundation materials of the Bottom Ash Pond complex consist primarily of loose to very dense sands and gravels with N-values ranging from 3 to 50. Foundation and abutment soil properties were determined from a subsurface investigation. The following properties of the foundation materials were determined from laboratory testing:

Moist Unit Weight: 120 pcf

Saturated Unit Weight: 130 pcf

Coehsion: 0 psf

Friction Angle: 34 degrees

8.0 DESCRIPTION OF EACH CONSTRUCTED ZONE OR STAGE OF THE CCR UNIT

257.73 (c)(1)(vi)

[A statement of the type, size, range, and physical and engineering properties of the materials used in constructing each zone or stage of the CCR unit; and the approximate dates of construction of each successive stage of construction of the CCR unit.]

The Bottom Ash Pond complex was originally constructed in 1977. The original design drawings show the embankment being constructed of earthen fill with the lower portion of the impoundment excavated into the existing ground (incised). The embankment has an approximate top width of 20 feet. The crest of the Bottom Ash Pond is at elevation 690 feet-msl and the Clear Water Pond is approximately 675 feet-msl. The tallest section of embankment is approximately 19 feet at north and west embankments of the Bottom Ash Pond. The inboard and outboard slopes were constructed with a 3 horizontal to 1 vertical slopes. On top of the dike there is a gravel access road used for maintaining and operating the impoundment. There have been no successive raisings of the impoundment. A

subsurface investigation describing the engineering properties of the embankment soils is included in Attachment B and design drawings are included in Attachment C.

9.0 ENGINEERING STRUCTURES AND APPURTENANCES, 257.73 (c)(1)(vii)

[At a scale that details engineering structures and appurtenances relevant to the design, construction, operation, and maintenance of the CCR unit, detailed dimensional drawings of the CCR unit, including a plan view and cross sections of the length and width of the CCR unit, showing all zones, foundation improvements, drainage provisions, spillways, diversion ditches, outlets, instrument locations, and slope protection...]

Bottom ash is sluiced into the Bottom Ash Pond via sluice lines which are supported by a wooden truss structure at the northeast portion of the pond. Overflow from the western portion of the Bottom Ash Pond is conveyed to the Clear Water Pond via a concrete overflow shaft and a 30-inch diameter reinforced concrete pipe to a 30-inch diameter perforated distribution pipe in the Clear Water Pond. The Clear Water Pond was constructed using both incised pond and diked pond construction methods. In general, the pool levels along the southern and eastern sides of the Clear Water Pond are primarily incised. The inside slopes of the Bottom Ash Pond and Clear Water Pond are lined with a PVC liner overlaid by soil as recommended to prevent seepage. Overflow from the Clear Water Pond is conveyed through an overflow tower into a 36-inch diameter reinforced concrete pipe through the embankment and then a series of 36-inch diameter corrugated metal pipes which discharge into a riprap-lined channel leading to the Ohio River. Other plant process water is sent to the bottom ash pond through piping and valve structures located on the embankment. Detailed dimensional drawings are included in Attachment C.

Primarily the inboard slopes are protected by grass, aggregate or a layer of bottom ash. The outboard slopes primarily consist of grass vegetation.

There are four piezometers located within the dike. A map with instrumentation locations is provided in Attachment D.

10.0 SUMMARY OF POOL SURFACE ELEVATIONS, AND MAXIMUM DEPTH OF CCR, 257.73 (c)(1)(vii)

[...in addition to the normal operating pool surface elevation and the maximum pool elevation following peak discharge from the inflow design flood, the expected maximum depth of CCR within the CCR surface impoundment.]

The Bottom Ash Complex has been determined to be a Significant Hazard potential CCR impoundment. Based on this hazard classification the design flood is determined by section 257.82(a)(3) to be the 1000-year storm which corresponds to 7.10 inches in 24 hours for this site taken from NOAA Atlas 14. An analysis was performed which demonstrates the Bottom Ash Complex can safely pass the 1/2 PMP (Probable Maximum Precipitation), which is equivalent to 13.45 inches in 6 hours and therefore exceeds the requirements of section 257.82(a)(3). The complete analysis is included in Attachment E.

	Bottom Ash Pond	Clear Water Pond
Normal Pool Elevation	676.0	664.0
Maximum Pool Elevation following peak discharge from design flood (1/2 PMP)	683.51	666.5
Expected Maximum depth of CCR within impoundment	30 ft	Trace amount

11.0 FEATURES THAT COULD ADVERSELY AFFECT OPERATION DUE TO MALFUNCTION OR MIS-OPERATION 257.73 (c)(1)(vii)

[...and any identifiable natural or manmade features that could adversely affect operations of the CCR unit due to malfunction or mis-operation]

In the event of malfunction or mis-operation of any of the pond's appurtenances the ponds operations could be adversely affected. These structures include the outlet spillway structures located in the Bottom Ash Pond and Clear Water Pond and influent sluicing piping and structures. See design drawings in Attachment C for location and details of all appurtenances.

12.0 DESCRIPTION OF THE TYPE, PURPOSE AND LOCATION OF EXISTING INSTRUMENTATION 257.73 (c)(1)(viii)

[A description of the type, purpose, and location of existing instrumentation.]


The Bottom Ash Pond complex has 4 piezometers located within the dam. These piezometers are read a minimum of every 30 days for the purpose of determining the phreatic water level within the dike. A location map is provided in Attachment D.

13.0 AREA – CAPACITY CURVES FOR THE CCR UNIT 257.73 (c)(1)(ix)


[Area-capacity curves for the CCR unit.]

The area capacity curves for the Bottom Ash Pond Complex are shown below:

Bottom Ash Pond



Clear Water Pond



14.0 DESCRIPTION OF EACH SPILLWAY AND DIVERSION 257.73 (c)(1)(x)

[A description of each spillway and diversion design features and capacities and calculations used in their determination.]

Overflow from the western portion of the Bottom Ash Pond is conveyed to the Clear Water Pond via a concrete overflow shaft and a 30-inch diameter reinforced concrete pipe to a 30-inch diameter perforated distribution pipe in the Clear Water Pond. Overflow from the Clear Water Pond is conveyed through an overflow tower into a 36-inch diameter reinforced concrete pipe through the embankment

and then a series of 36-inch diameter corrugated metal pipes which discharge into a riprap-lined channel leading to the Ohio River. Detailed dimensional drawings are included in Attachment C. Capacities and Calculations are included in Attachment E. Drainage is diverted around the Bottom Ash Pond Complex by natural drainage channels and grass lined ditches.

15.0 SUMMARY CONSTRUCTION SPECIFICATIONS AND PROVISIONS FOR SURVEILLANCE, MAINTENANCE AND REPAIR 257.73 (c)(1)(xi)

[The construction specifications and provisions for surveillance, maintenance, and repair of the CCR unit.]

Construction of the Bottom Ash Pond Complex was completed around 1977. Original construction specifications are unavailable. Original design drawings are included in Attachment C. A subsurface investigation detailing the constructed soil material of the embankment is included in Attachment B.

As required by the CCR rules the Bottom Ash Pond is inspected at least every 7 days by a qualified person. Also as a requirement of the CCR rules the impoundment is also inspected annual by a professional engineer. Maintenance items are addressed as they are discovered as part of those inspections.




16.0 RECORD OR KNOWLEDGE OF STRUCTURAL INSTABILITY 257.73 (c)(1)(xii)

[Any record or knowledge of the structural instability of the CCR unit.]

To date there has been no known record or knowledge of structural instability of the CCR unit.

ATTACHMENT A

LOCATION MAP



THIS DRAWING IS CLASSIFIED AS:

AEP PUBLIC

OHIO POWER COMPANY

MITCHELL PLANT

REFERENCE AEP'S CORPORATE INFORMATION SECURITY POLICY

CRESAP

WEST VIRGINIA

"THIS DRAWING IS THE PROPERTY OF THE **AMERICAN ELECTRIC POWER SERVICE CORP.** AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE **AEP SERVICE CORP.** ,OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST"

BOTTOM ASH POND
USGS TOPO MAP
 7.5-MINUTE SERIES

UNIT:
34

DRAWING NUMBER:
LOCATION MAP

REV:
1

SCALE: 1"=2000'

CIVIL ENGINEERING

DR:

CH:

SUP:

ENG:

DATE: 9/13/16



AEP SERVICE CORP.
 1 RIVERSIDE PLAZA
 COLUMBUS, OH 43215

ATTACHMENT B

SUBSURFACE INVESTIGATION

Laboratory Testing Data

SUMMARY OF LABORATORY TEST RESULTS

							ATTERBERG LIMITS					Project: Mitchell Bottom Ash Pond Project Number: 09-379 Date: March 18, 2009
Boring	Sample No.	Sample Type*	Depth (ft)	Natural Moisture	Dry Density	Specific Gravity	Liquid Limit	Plasticity Index	USCS	Other Test	Soil Description	
B-1	S-3	SS	7.0-8.5	11.0	--	2.68	19	7	SC-SM	S	Sand, clayey, silty, brown, black, gray w/rock	
B-1	S-11	SS	35.0-36.5	15.2	--	2.74	12	np	SW-SM	S	Sand, silty, black w/rock	
B-2	S-5	SS	12.0-13.5	5.7	--	2.67	15	5	SP-SC	S	Sand, clayey, silty, brown, dark brown w/rock	
B-2	S-10	SS	29.0-30.5	5.4	--	2.71	--	np	SP-SM	S	Sand, brown	
B-2	ST-2	ST	34.5-36.5	8.7	105.5	2.70	--	np	SM	K,S,T	Sand, brown, light brown (Sand Foundation)	
B-3	S-6	SS	17.0-18.5	9.2	--	2.71	17	5	SC-SM	S	Sand, clayey, silty, dark brown, brown w/rock	
B-3	S-11	SS	29.5-31.0	13.0	--	2.65	17	5	SC-SM	S	Sand, clayey, silty, black, brown, w/rock &	
B-3	ST-2	ST	34.5-35.5	18.5	112.1	2.62	26	9	CL	K,S,U	Clay, silty, sandy, brown w/rock	
B-4	S-4	SS	12.0-13.5	7.9	--	2.69	--	np	SM	S	Sand, silty, brown, dark brown w/rock	
B-4	S-12	SS	39.5-41.0	5.2	--	2.71	--	np	SP	S	Sand, brown	
B-1,B-3,B-4	ST-1	ST	9.5-10.0	9.3	114.5	2.68	16	4	SC-SM	K,S,T	Sand, clayey, silty, brown w/rock	
B-5	S-3	SS	7.0-8.5	7.9	--	2.70	12	np	SM	S	Sand, silty, dark brown w/rock	
B-5	S-8	SS	24.5-26.0	7.8	--	2.66	16	4	SP-SC	S	Sand, clayey, silty, brown w/rock	
na	B	B	na	3.6	--	2.26	--	np	SP	S	Bottom Ash	

*ST-SHELBY TUBE SAMPLE, SS-SPLIT SPOON SAMPLE, B-BAG SAMPLE, J-JAR SAMPLE

**TEST RESULTS REPORTED ON OTHER SHEETS:


T-TRIAxIAL
S-SIEVE OR GRAIN SIZE ANALYSIS
U-UNCONFINED COMPRESSION

P-PROCTOR TEST
K-PERMEABILITY
C-CONSOLIDATION

**Geo/Environmental
Associates**

DATA CHECKED BY _____

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	7.2	26.0	12.1	15.8	11.3	27.6	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-1 S-3	7.0'-8.5'		SC-SM	Sand, clayey, silty, brown, black, gray w/rock	11.0	19	12

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	19.0	20.9	35.6	15.1	9.4	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-1 S-11	35.0'-36.5'		SW-SM	Sand, silty, black w/rock	15.2	12	np

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	14.2	21.9	17.7	22.2	12.2	11.8	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-2 S-5	12.0'-13.5'		SP-SC	Sand, clayey, silty, brown, dark brown w/rock	5.7	15	10

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	7.3	4.5	34.9	45.7	7.6	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-2 S-10	29.0'-30.5'		SP-SM	Sand, brown	5.4	nv	np

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	



Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	1.8	1.3	43.0	38.0	15.9	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-2 ST-2	34.5'-36.5'		SM	Sand, brown, light brown	8.7	nv	np

Client American Electric Power Project Mitchell Bottom Ash Pond Project No. 09-379	Geo/Environmental Associates, Inc. Knoxville, Tennessee	○ Sand Foundation Material
Figure		



Client: American Electric Power

Project: Mitchell Bottom Ash Pond

Depth: 34.5'-36.5'


Sample Number: B-2 ST-2

Project No.: 09-379

Figure 2

Geo/Environmental Associates, Inc.

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	22.8	19.1	22.6	13.3	22.2	


Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-3 S-6	17.0'-18.5'		SC-SM	Sand, clayey, silty, dark brown, brown w/rock	9.2	17	12

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

Particle Size Distribution Report



Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	9.8	12.8	7.2	11.7	58.5	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-3 ST-2	34.5'-35.5'		CL	Clay, silty, sandy, brown w/rock	18.5	26	17

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

UNCONFINED COMPRESSION TEST



Sample No.	1			
Unconfined strength, ksf	1.85			
Undrained shear strength, ksf	0.92			
Failure strain, %	4.5			
Strain rate, in./min.	0.01			
Water content, %	12.6			
Wet density, pcf	131.2			
Dry density, pcf	116.5			
Saturation, %	82.0			
Void ratio	0.4041			
Specimen diameter, in.	2.84			
Specimen height, in.	5.61			
Height/diameter ratio	1.98			

Description: Clay, silty, sandy, brown w/rock

LL = 26 PL = 17 PI = 9 GS = 2.62 Type: Shelby Tube

Project No.: 09-379

Date Sampled:

Remarks:

Client: American Electric Power

Project: Mitchell Bottom Ash Pond


Sample Number: B-3 ST-2 **Depth:** 34.5'-35.5'

UNCONFINED COMPRESSION TEST

Geo/Environmental Associates, Inc.

Figure _____

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	4.8	25.1	14.2	21.8	19.1	15.0	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-4 S-4	12.0'-13.5'		SM	Sand, silty, brown, dark brown w/rock	7.9	nv	np

Client American Electric Power	Geo/Environmental Associates, Inc. Knoxville, Tennessee
Project Mitchell Bottom Ash Pond	
Project No. 09-379	

Particle Size Distribution Report




% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	0.0	0.1	53.4	43.2	3.3	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-4 S-12	39.5'-41.0'		SP	Sand, brown	5.2	nv	np

Client American Electric Power	Geo/Environmental Associates, Inc. Knoxville, Tennessee
Project Mitchell Bottom Ash Pond	
Project No. 09-379	
Figure	

Particle Size Distribution Report





% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	3.3	23.1	12.0	29.5	16.9	15.2	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-1,B-3,B-4 ST-1	9.5'-10.0'		SC-SM	Sand, clayey, silty, brown w/rock	9.3	16	12

Client American Electric Power
 Project Mitchell Bottom Ash Pond
 Project No. 09-379

**Geo/Environmental
 Associates, Inc.
 Knoxville, Tennessee**

○ Sand Dike Material



Sample No.	1	2	3	
Initial	Water Content, %	9.2	9.3	9.3
	Dry Density, pcf	114.3	114.5	113.2
	Saturation, %	53.1	53.8	52.0
	Void Ratio	0.4632	0.4617	0.4774
	Diameter, in.	2.80	2.80	2.80
	Height, in.	5.60	5.60	5.60
At Test	Water Content, %	16.8	16.2	16.9
	Dry Density, pcf	115.5	116.6	115.1
	Saturation, %	100.0	100.0	100.0
	Void Ratio	0.4491	0.4344	0.4538
	Diameter, in.	2.79	2.78	2.78
	Height, in.	5.58	5.56	5.57
Strain rate, in./min.	0.00	0.00	0.00	
Back Pressure, psi	0.00	0.00	0.00	
Cell Pressure, psi	5.00	10.00	20.00	
Fail. Stress, ksf	2.55	3.83	6.72	
Ult. Stress, ksf				
σ_1 Failure, ksf	3.27	5.27	9.60	
σ_3 Failure, ksf	0.72	1.44	2.88	

Type of Test:

Consolidated Drained

Sample Type: Shelby Tubes

Description: Sand, clayey, silty, brown w/rock

LL= 16 PL= 12 PI= 4

Specific Gravity= 2.68

Remarks: Remolded specimens from B-1 ST-1, B-3 ST-1 & B-4 ST-1

Client: American Electric Power

Project: Mitchell Bottom Ash Pond

Sample Number: B-1,B-3,B-4 ST-1

Depth: 9.5'-10.0'






Proj. No.: 09-379

Date Sampled:

TRIAxIAL SHEAR TEST REPORT

Geo/Environmental Associates, Inc.

Figure 1



Client: American Electric Power
 Project: Mitchell Bottom Ash Pond
 Depth: 9.5'-10.0' Sample Number: B-1,B-3,B-4 ST-1
 Project No.: 09-379

Figure 2

**CONSTANT HEAD PERMEABILITY TESTING
ASTM D5084-90/SW846 Method 9100 Section 2.8**

PROJECT NAME : Mitchell Bottom Ash Pond

PROJECT NUMBER : 09-379

CLIENT : American Electric Power

DATE : March 16, 2009

SAMPLE LOCATION AND CONDITIONS

Sample Id. : B-1, B-3 & B-4; ST-1 **Depth of Tested Sample** : 9.5'-10.0'

Specimen : 5 psi Triaxial Specimen **Remolded** : Yes

Sample Description : Sand, clayey, silty, brown w/rock (Sand Dike)

INITIAL SPECIMEN PROPERTIES

Length (in.): 5.6 **Volume (ft³):** 0.0200 **Wet Density (PCF):** 124.8

Diameter (in.): 2.8 **Weight (lbs):** 2.49 **Dry Density (PCF):** 114.3

Area (ft²): 0.0428 **Moisture (%):** 9.2

Chamber Pressure (psi): 5 **Change in Pore Pressure (psi):** 2.0

Influent Pressure (psi): 3 **Change in Chamber Pressure (psi):** 2.0

Back Pressure (psi): 0 **"B" Factor:** 1.0

PERMEABILITY CALCULATIONS

k = Hydraulic Conductivity, (cm/sec)

$$k = \frac{QL}{Ath} = \text{cm/sec}$$

L = Length of Sample, along path of flow, (cm)

$$k = \frac{(700.0)(14.22)}{(39.73)(2352)(211.01)}$$

Q = Quantity of flow, taken as the average of inflow and outflow, (cm³)

A = Cross-sectional area of specimen, (cm²)

$$= \frac{9,954.00}{19,717,821.01}$$

t = Interval of time, over which the flow Q occurs, (sec)

h = Difference in hydraulic head across specimen, (cm)

$$= \underline{5.05 \times 10^{-4} \text{ cm/sec}}$$

CONSTANT HEAD PERMEABILITY TESTING

ASTM D5084-90/SW846 Method 9100 Section 2.8

PROJECT NAME : Mitchell Bottom Ash Pond

PROJECT NUMBER : 09-379

CLIENT : American Electric Power

DATE : March 16, 2009

SAMPLE LOCATION AND CONDITIONS

Sample Id. : B-1, B-3 & B-4; ST-1 **Depth of Tested Sample** : 9.5'-10.0'

Specimen : 10 psi Triaxial Specimen **Remolded** : Yes

Sample Description : Sand, clayey, silty, brown w/rock (Sand Dike)

INITIAL SPECIMEN PROPERTIES

Length (in.): 5.6 **Volume (ft³):** 0.0200 **Wet Density (PCF):** 125.1

Diameter (in.): 2.8 **Weight (lbs):** 2.50 **Dry Density (PCF):** 114.5

Area (ft²): 0.0428 **Moisture (%):** 9.3

Chamber Pressure (psi): 7 **Change in Pore Pressure (psi):** 2.0

Influent Pressure (psi): 5 **Change in Chamber Pressure (psi):** 2.0

Back Pressure (psi): 2 **"B" Factor:** 1.0

PERMEABILITY CALCULATIONS

k = Hydraulic Conductivity, (cm/sec)

$$k = \frac{QL}{Ath} = \text{cm/sec}$$

L = Length of Sample, along path of flow, (cm)

Q = Quantity of flow, taken as the average of inflow and outflow, (cm³)

$$k = \frac{(700.0)(14.22)}{(39.73)(2662)(211.01)}$$

A = Cross-sectional area of specimen, (cm²)

$$= \frac{9,954.00}{22,316,683.47}$$

t = Interval of time, over which the flow Q occurs, (sec)

h = Difference in hydraulic head across specimen, (cm)

$$= \underline{4.46 \times 10^{-4} \text{ cm/sec}}$$

CONSTANT HEAD PERMEABILITY TESTING

ASTM D5084-90/SW846 Method 9100 Section 2.8

PROJECT NAME : Mitchell Bottom Ash Pond

PROJECT NUMBER : 09-379

CLIENT : American Electric Power

DATE : March 16, 2009

SAMPLE LOCATION AND CONDITIONS

Sample Id. : B-1, B-3 & B-4; ST-1 **Depth of Tested Sample** : 9.5'-10.0'

Specimen : 20 psi Triaxial Specimen **Remolded** : Yes

Sample Description : Sand, clayey, silty, brown w/rock (Sand Dike)

INITIAL SPECIMEN PROPERTIES

Length (in.): 5.6 **Volume (ft³):** 0.0200 **Wet Density (PCF):** 123.7

Diameter (in.): 2.8 **Weight (lbs):** 2.47 **Dry Density (PCF):** 113.2

Area (ft²): 0.0428 **Moisture (%):** 9.3

Chamber Pressure (psi): 10 **Change in Pore Pressure (psi):** 2.0

Influent Pressure (psi): 8 **Change in Chamber Pressure (psi):** 2.0

Back Pressure (psi): 5 **"B" Factor:** 1.0

PERMEABILITY CALCULATIONS

k = Hydraulic Conductivity, (cm/sec)

$$k = \frac{QL}{Ath} = \text{cm/sec}$$

L = Length of Sample, along path of flow, (cm)

Q = Quantity of flow, taken as the average of inflow and outflow, (cm³)

$$k = \frac{(700.0)(14.22)}{(39.73)(1424)(211.01)}$$

A = Cross-sectional area of specimen, (cm²)


$$= \frac{9,954.00}{11,938,000.48}$$

t = Interval of time, over which the flow Q occurs, (sec)

h = Difference in hydraulic head across specimen, (cm)

$$= \underline{8.34 \times 10^{-4} \text{ cm/sec}}$$

Particle Size Distribution Report



% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	6.6	17.4	22.0	30.2	13.6	10.2	


Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	B-5 S-8	24.5'-26.0'		SP-SC	Sand, clayey, silty, brown w/rock	7.9	16	12

Client American Electric Power
 Project Mitchell Bottom Ash Pond
 Project No. 09-379

**Geo/Environmental
 Associates, Inc.
 Knoxville, Tennessee**

Figure

Particle Size Distribution Report



GRAIN SIZE - mm.

% +3"	% Gravel		% Sand			% Fines	
	Coarse	Fine	Coarse	Medium	Fine	Silt	Clay
0.0	0.0	16.8	34.4	41.2	3.6	4.0	

Source	Sample #	Depth/Elev.	Date Sampled	USCS	Material Description	NM %	LL	PL
	Bucket			SP	Bottom Ash	3.6	nv	np

Client American Electric Power	<h2 style="margin: 0;">Geo/Environmental Associates, Inc.</h2> <h3 style="margin: 0;">Knoxville, Tennessee</h3>
Project Mitchell Bottom Ash Pond	
Project No. 09-379	

Borehole Data

Geo/Environmental Associates, Inc.

Boring No. B-1

Page 1 Of 2

PROJECT: AEP Mitchell BAP	PROJECT NO: 09-379
Start Date: 3-4-09	Drilling Contractor: Horn and Associates
Finish Date: 3-4-09	Driller: Tom Leininger
Logged By: Seth Frank	Helper: Jared and Bradley
Location: N 485362.82 E 1599372.71NAD83	Drill Type: Dietrick D50
Ground Elevation: 692.42' NAVD88	
Notes:	Thickness of Soil:
	Depth Drilled In Rock:
	Total Depth of Boring: 51.0'

DEPTH (FEET)		SAMPLE NOS., & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
2.0	3.5	S-1 / 1.2'	SAND, brown w/green & yellow, gravel, dense, damp	15-22-19
4.5	6.0	S-2 / 1.3'	SAND, brown w/grey & yellow, gravel, very dense, damp	17-32-24
7.0	8.5	S-3 / 1.3'	SAND, clayey, silty, brown, gravel, medium dense, moist	10-11-15
9.5	9.9	ST-1 / 0.4'	SAND, clayey, silty, brown, gravel, moist	
12.0	13.5	S-4 / 1.4'	0-0.2': SAND, brown, gravel; 0.2-0.6': SAND, black (possible bottom of preexisting fill); 0.6-1.0': SAND, grey/white; 1.0-1.4': SAND- silty, brown, dense, damp	10-20-19
14.5	16.0	S-5 / 1.2'	SILT, sandy, clayey, gravel, medium dense to very stiff (qu>5tsf), damp	8-12-13
17.0	18.5	S-6 / 1.5'	SAND, brown, gravel, medium dense, damp	9-9-10
19.5	20.5	S-7 / 1.1'	SAND, gravelly, brown, medium dense, damp	6-7-5
22.0	23.5	S-8 / 1.3'	SAND, brown, gravel, medium dense, damp	5-5-6

GeoEnvironmental Associates, Inc.

Boring No. B-2

Page 1 Of 2

PROJECT: AEP Mitchell BAP	PROJECT NO: 09-379
Start Date: 3-4-09	Drilling Contractor: Horn and Associates
Finish Date: 3-5-09	Driller: Tom Leininger
Logged By: Seth Frank	Helper: Jared and Bradley
Location: N 485698.27 E 1598947.58 NAD83	Drill Type: Dietrick D50
Ground Elevation: 690.72' NAVD88	
Notes: Set piezometer to tip depth of 31.0'	Thickness of Soil:
Well dry at 31' on 3-5-09.	Depth Drilled In Rock:
Piezometer Elevation: 690.59' NAVD88	Total Depth of Boring: 51.0'
Casing Elevation: 691.78' NAVD88	

DEPTH (FEET)		SAMPLE NOS., & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
2.0	3.5	S-1 / 1.3'	SAND, brown, gravel, medium dense, moist	6-6-6
4.5	6.0	S-2 / 1.4'	SAND, brown, gravel, medium dense, moist	5-8-9
7.0	8.5	S-3 / 1.4'	SAND, silty, brown, gravel, very dense, damp	15-22-32
9.5	11.0	S-4 / 1.4'	SAND, silty, brown, gravel, very dense, moist	15-26-31
12.0	13.5	S-5 / 1.2'	SAND, clayey, silty, brown, gravel, medium dense, damp-moist	12-15-15
14.5	14.7	ST-1 / 0.2'	SAND, clayey, silty, brown, gravel, moist	
17.0	18.5	S-6 / 1.3'	CLAY, sandy, silty, brown mottled black, gravel, medium dense - very stiff (qu = 2.5tsf), moist	6-5-10
19.5	19.5	S-7 / 0.0'		NO RECOVERY
22.0	23.5	S-8 / 1.0'	SAND, brown, gravel, medium dense, damp (estimated original ground)	4-5-6
24.5	26.0	2-9 / 1.1'	SAND, brown, gravel, loose, damp - distinct 0.2' black, sandy layer at top of sample	4-5-4
29.0	30.5	S-10 / 1.2'	SAND, brown, clean, loose, damp	1-4-3
34.5	36.5	ST-2 / 1.7'	SAND, brown, light brown, damp	

GeoEnvironmental Associates, Inc.

Project Name/ Job Number: 09-379

Boring/Well Log No.: B-2

Page 2 of 2

DEPTH (FEET)		SAMPLE NO., SAMPLE INTERVAL & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
44.5	46.0	S-12 / 1.4'	SAND, brown, clean, loose, damp	3-3-4
49.5	51.0	S-13 / 1.5'	SAND, brown, clean, loose, moist – transition at 0.7' to clay, sandy, brown, firm (qu=1.0tsf), wet	3-2-2

TRANSITION FROM DIKE TO ORIGINAL AT
APPROXIMATELY 24.5
SET PIPE AT 31.0'

51.0 to 35.0	SAND CUTTINGS
35.0 to 32.0	BENTONITE
32.0 to 31.0	SAND
31.0 to 20.8	SCREEN
20.8 to 0.3	RISER
32.0 to 14.5	SAND
19.5 to 16.5	BENTONITE
16.5 to 3.0	GROUT
3.0 to 0.0	CONCRETE WITH MAN HOLE

W/L DRY @ 50.0'

GeoEnvironmental Associates, Inc.

Boring No. B-3

Page 1 Of 2

PROJECT: AEP Mitchell BAP

PROJECT NO: 09-379

Start Date: 3-3-09

Drilling Contractor: Horn and Associates

Finish Date: 3-5-09

Driller: Tom Leininger

Logged By: Seth Frank

Helper: Jared and Bradley

Location: N 485238.72 E1598811.08 NAD83

Drill Type: Dietrick D50

Ground Elevation: 691.80' NAVD88

Notes: Set piezometer to tip depth of 31.0'

Thickness of Soil:

W/L at 23.3' below top of pipe on 3-5-09

Depth Drilled In Rock:

Casing Elevation: 691.85' NAVD88

Total Depth of Boring: 51.0'

Piezometer Elevation: 691.54' NAVD88

DEPTH (FEET)		SAMPLE NOS., & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
2.0	3.5	S-1 / 1.2'	SAND, brown, gravel, very dense, damp	12-27-39
4.5	6.0	S-2 / 1.3'	SAND, brown, gravel, very dense, damp	14-29-30
7.0	8.5	S-3 / 1.4'	SAND, brown, gravel, dense, moist	18-23-26
9.5	9.9	ST-1 / 0.4'	SAND, brown, gravel, moist	
12.0	13.5	S-4 / 1.0'	SAND, dark brown, gravel, very dense, moist	17-29-38
14.5	16.0	S-5 / 1.1'	SAND, brown mottled grey, gravel, dense, moist	8-14-23
17.0	18.5	S-6 / 1.5'	SAND, clayey, silty, brown mottled black and grey, gravel, medium dense, moist	9-9-10
19.5	21.0	S-7 / 1.4'	SAND - gravelly, brown mottled grey, medium dense, damp-moist	21-21-23
22.0	23.5	S-8 / 1.4'	SAND, brown & black, gravel, dense, moist	15-21-20
24.5	26.0	S-9 / 1.3'	SAND brown mottled black, very dense, wet	15-24-23
27.0	28.5	S-10 / 1.3'	SAND, brown, gravel, dense, very wet	8-13-23

GeoEnvironmental Associates, Inc.

Project Name/ Job Number: 09-379

Boring/Well Log No.: B-3

Page 2 of 2

DEPTH (FEET)		SAMPLE NO., SAMPLE INTERVAL & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
29.5	31.0	S-11 / 1.1'	SAND, silty, clayey, brown, medium dense - very stiff (qu = 3.25tsf), moist	12-15-35
32.0	33.5	S-12 / 0.2'	SAND, silty, clayey, brown, very dense, wet <i>*split spoon blocked by rock</i>	19-29-29
34.5	35.5	ST-2 / 1.0'	CLAY, silty, sandy, brown, gravel, wet	
39.5	41.0	S-13 / 1.1'	SAND, brown, gravel, medium dense, wet	4-6-7
45.0	46.5	S-14 / 1.2'	SAND, brown, gravel, medium dense, wet	3-4-7
49.5	51.0	S-15 / 1.0'	SAND, brown, medium dense, wet	3-6-8

			TRANSITION FROM DIKE TO ORIGINAL AT APPROXIMATELY 29.5 - 30' SET PIPE AT 31'
51.0 to	35.0		SAND CUTTINGS
35.0 to	32.0		BENTONITE
32.0 to	31.0		SAND
31.0 to	20.8		SCREEN
20.8 to	0.2		RISER
32.0 to	19.5		SAND
19.5 to	16.5		BENTONITE
16.5 to	3.0		GROUT
3.0 to	0.0		CONCRETE WITH MAN HOLE

Geo/Environmental Associates, Inc.

Boring No. B-4

Page 1 Of 2

PROJECT: AEP Mitchell BAP

PROJECT NO: 09-379

Start Date: 3-2-09

Drilling Contractor: Horn and Associates

Finish Date: 3-3-09

Driller: Tom Leininger

Logged By: Seth Frank & Robby Reynolds

Helper: Jared and Bradley

Location: N 484958.8 E 1599000.96 NAD83

Drill Type: Dietrick D50

Ground Elevation: 692.17' NAVD88

Notes: Set piezometer to tip depth of 30.0'

Thickness of Soil:

W/L at 24.6' below top of pipe on 3/5/09

Depth Drilled In Rock:

Piezometer Elevation: 691.91' NAVD88

Total Depth of Boring: 51.0'

Casing Elevation: 692.20' NAVD88

DEPTH (FEET)		SAMPLE NOS., & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
2.0	3.5	S-1	SAND, brown, gravel, very dense, damp	25-41-26
4.5	6.0	S-2	SAND, brown, gravel, dense, damp	12-17-23
7.0	8.5	S-3	SAND, brown, gravel, very dense, damp	19-28-30
9.5	10.0	ST-1 / 0.5'	SAND, clayey, silty, brown, gravel, damp	
12.0	13.5	S-4	SAND, silty, black / brown, gravel, dense, damp	12-17-23
14.5	16.0	S-5	SAND, black / brown, gravel, dense, damp	12-20-21
17.0	18.5	S-6	SAND, clayey, silty, brown / black, gravel, dense, damp	11-12-19
19.5	21.0	S-7	SAND, gravelly, brown mottled grey, medium dense, damp-moist	8-13-13
22.0	23.5	S-8	SAND, silty, clayey, dark brown / black, dense, moist	8-13-20
24.5	26.0	S-9	SAND, gravelly, brown, medium dense, moist - wet	19-17-13
27.0	28.5	S-10	SAND, brown, gravel, dense, very wet	17-24-20

Geo/Environmental Associates, Inc.

Project Name/ Job Number: 09-379

Boring/Well Log No.: B-4

Page 2 of 2

DEPTH (FEET)		SAMPLE NO., SAMPLE INTERVAL & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
29.5	31.0	S-11	SAND, silty, clayey, black / dark brown, organic matter, medium dense, moist (qu = 3.25tsf)	8-11-14
34.5	36.5	ST-2 / 1.7'	SAND, brown, wet	
39.5	41.0	S-12	SAND, brown, loose, wet	2-3-4
45.0	46.5	S-13	SAND, brown, medium, wet	3-4-6
49.5	51.0	S-14	SAND, brown, medium, wet	3-6-7

TRANSITION FROM DIKE TO ORIGINAL AT
APPROXIMATELY 24.5'
SET PIPE AT 30.0'

51.0 to	34.0	SAND CUTTINGS
34.0 to	31.0	BENTONITE
31.0 to	30.0	SAND
30.0 to	19.8	SCREEN
19.8 to	0.2	RISER
31.0 to	18.0	SAND
18.0 to	15.0	BENTONITE
15.0 to	3.0	GROUT
3.0 to	0.0	CONCRETE WITH MAN HOLE

Geo/Environmental Associates, Inc.

Boring No. B-5
 Page 1 Of 2

PROJECT: AEP Mitchell BAP	PROJECT NO: 09-379
Start Date: 3-2-09	Drilling Contractor: Horn and Associates
Finish Date: 3-3-09	Driller: Tom Leininger
Logged By: Seth Frank & Robby Reynolds	Helper: Jared and Bradley
Location: N 484664.32 E 1598966.05 NAD83	Drill Type: Dietrick D50
Ground Elevation: 674.82' NAVD88	
Notes: Set piezometer to tip depth of 17.0'	Thickness of Soil:
Well dry at 17.0' on 3-5-09	Depth Drilled In Rock:
Piezometer Elevation: 674.43' NAVD88	Total Depth of Boring: 36.0'
Casing Elevation: 674.86' NAVD88	

DEPTH (FEET)		SAMPLE NOS., & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
2.0	3.5	S-1	SAND, silty, brown, slightly gravelly, medium, dense, damp	7-10-9
4.5	6.0	S-2	SAND, silty, grey to brown, slightly gravelly medium dense, damp	3-5-7
7.0	8.5	S-3	SAND, silty, brown, slightly gravelly, loose, damp	4-4-3
9.5	11.0	S-4	SAND, silty, brown, dark brown, gravel, loose damp	1-2-2
12.0	13.5	S-5	Transition: SAND, black, slightly gravelly, damp To SAND clayey silty, dark brown, gravel, dense, damp	12-26-3
14.5	16.0	S-6	SAND, clayey, silty, brown, river rock, dense, damp	12-15-22
17.0	18.5	S-7	SILT, clayey, brown, very stiff, damp (qu=5tsf)	7-12-13
19.5	20.5	ST-1 / 0.8'	SAND, clayey, silty, brown, gravel, damp	
24.5	26.0	S-8	SAND, clayey, silty, dark brown, gravel, loose, damp	3-4-5

Geo/Environmental Associates, Inc.

Project Name/ Job Number: 09-379

Boring/Well Log No.: B-5

Page 2 of 2


DEPTH (FEET)		SAMPLE NO., SAMPLE INTERVAL & SPLIT SPOON RECOVERY	SOIL/BEDROCK DESCRIPTION	BLOW COUNTS AND COMMENTS
FROM	TO			
29.5	31.0	S-9	SAND, dark brown, gravel, medium dense, damp	4-5-7
34.5	36.0	S-10	SAND, gravely, light brown, medium dense, damp	6-9-9

TRANSITION FROM DIKE TO ORIGINAL AT
APPROXIMATELY 12.0'
SET PIPE AT 17.0'

36.0 to	21.0	SAND CUTTINGS
21.0 to	18.0	BENTONITE
18.0 to	17.0	SAND
17.0 to	7.0	SCREEN
7.0 to	0.6	RISER
18.0 to	5.0	SAND
5.0 to	2.5	BENTONITE
2.5 to	0.0	CONCRETE WITH MAN HOLE

W/L DRY @ 36.0'

ATTACHMENT C
DESIGN DRAWINGS



GENERAL NOTES

FOR TIMBER NOTES SEE DWG. 12-3424A.
FOR STRUCTURAL STEEL NOTES SEE DWG. 12-3424C.

MATERIAL

FOR TIMBER AND BOLT SCHEDULES SEE DWG. 12-3424C.

REFERENCE DRAWINGS

FOR LIST OF REFERENCE DRAWINGS SEE DWG. 12-3424A.

DATE	NO.	DESCRIPTION	BY	APP'D.
	1	REVISED SECT		

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE A.E.P. SERVICE CORP. OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."





OHIO POWER COMPANY
MITCHELL PLANT
CRESAP, WEST VIRGINIA
BOTTOM ASH STORAGE AREA
CLEARWATER POND
OVERFLOW DISCHARGE SYSTEM
COLLECTION TROUGH SUPPORTS
AND SKIMMER BARRIER

DR. NO. 12-3424 D - 1


























ARCH.	ELEC.	MECH.	STR.	W.E.

KELLERMANN & DRAGNETT INC.
CONSULTING ENGINEERS
LITTLE FALLS, NEW JERSEY
JOB NO: 77 - 18





MANHOLE DETAILS
3/8"=1'-0"



GENERAL NOTES
FOR STRUCTURAL STEEL NOTES SEE DWG. 12-3424-C.

CONCRETE NOTES
ALL CONCRETE MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE REQUIREMENTS OF THE SPECIFICATIONS FOR CONCRETE. ALL CONCRETE SHALL BE CAPABLE OF DEVELOPING A MINIMUM COMPRESSIVE STRENGTH OF 3000 PSI AT 28 DAYS. REINFORCING BARS SHALL BE ASTM A615, GRADE 60, DEFORMED TYPE. GRATING NOTES: GRATING SHALL BE RECTANGULAR TYPE WITH 3/16" BEARING BARS @ 1 3/16" CENTERS AND CROSS BARS @ 4" CENTERS. GRATING SHALL BE GALVANIZED. GRATING SHALL BE SECURED BY FIELD WELDING TO SUPPORTING MEMBERS EVERY TENTH BEARING BAR & SHALL SPAN IN DIRECTION SHOWN OR PLAIN TUBS (---).

MATERIAL
CONCRETE: 14.0 CU. YDS.
REINFORCING: 0.8 TON

REFERENCE DRAWINGS
FOR LIST OF REFERENCE DRAWINGS SEE DWG. 12-3424-A.

DATE	NO.	DESCRIPTION	APP.
REVISIONS			

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

OHIO POWER COMPANY
MITCHELL PLANT
CRESAP, WEST VIRGINIA
BOTTOM ASH STORAGE AREA
CLEARWATER POND
OVERFLOW DISCHARGE SYSTEM
COLLECTION TROUGH SUPPORTS
AND SKIMMER BARRIER

DR. NO. 12-3424 E

ARCH.	ELEC.	MECH.	STR.	W.D.


SCALE: AS NOTED
DR. E.E.M.
CH. J.E.B.
ED. LANGRISH
DATE: 11/12/78

ENGINEERING DIV.
DESIGN DIV.



KELLERMANN & DRAGNETT INC.
CONSULTING ENGINEERS
LITTLE FALLS, NEW JERSEY

AMERICAN ELECTRIC POWER SERVICE CORP.

BAR LIST: 12-RS-303
JOB NO. 77-18



DR. NO. 12-3433-5



COMPILED BY PHOTOGRAMMETRIC METHODS FROM AERIAL PHOTOGRAPHS TAKEN 8-23-73, 9-7-73 & 9-9-73. GRID SHOWN IS WEST VIRGINIA STATE PLANE COORDINATE, NORTH ZONE. GRID TICKS ARE EXTENDED FROM MITCHELL AXIS.

AERIAL SURVEYS, INC.
CLEVELAND, OHIO
AS 1 674-B

SCALE: 1" = 100'

CONTOUR INTERVAL 1.2 & 3'

SEE CON. PAGES WITH M.H. L TO E FOR REVISIONS TO WELL - M.H. L TO E.

DATE	DESCRIPTION	APPROVED
3/14/75	REVISED CLEAR WATER POND	[Signature]
1/14/75	[Blank]	[Blank]


"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE A.E.P. SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."

OHIO POWER COMPANY
MITCHELL PLANT
CRESAP, WEST VIRGINIA


BOTTOM ASH STORAGE
AREA
DIKES

DR. NO. 12-3433-5			
ARCH.	ELEC.	MECH.	STR.
SCALE: 1" = 100'		ENGINEERING DIV.	
DR. C. JOHNSON		[Signature]	
CH.		OPERATION DIV.	
NO. LDR. M.E.		[Signature]	
DATE: 1/14/75		[Signature]	
AMERICAN ELECTRIC POWER SERVICE CORP. 2 BROADWAY NEW YORK			


SHEET 1




SECTION 3 - E
SCALE N.T.S.




PLAN 3-J
SCALE 1/4"=1'-0"




SECTION 3 - K
SCALE 3/8"=1'-0"



SECTION 6 - E
SCALE N.T.S.



SECTION 6-M (AS SHOWN & NOTED)
SECTION 6-N (AS SHOWN & NOTED)
SCALE 3/4"=1'-0"



SECTION 9 - G
SCALE N.T.S.

DATE	NO.	DESCRIPTION	APPR.
1/15/54	1	ADDED TOP OF DIKE DIM & EL. SECT. 5-E REVISION: SECT. 5-E & 9-G	W.S.
1/15/54	2	SECTIONS FOR CONSTRUCTION OF CLEAR WATER POND RELEASED	W.S.
1/15/54	3	GENERAL REVISION	W.S.
1/15/54	4	SECT. 3 & 3-K & 3-M ADDED 2.5' W.S.	W.S.
1/15/54	5	RELEASED FOR CONSTRUCTION	W.S.

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE AEP SERVICE CORP., OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.


OHIO POWER COMPANY
MITCHELL PLANT
CRESAP, WEST VIRGINIA

BOTTOM ASH STORAGE
AREA - DIKS
SECTIONS

DR. NO. 12-3434-4

ARCH.	ELEC.	MECH.	STR.
SCALE: CIVIL	ENGINEERING DIV.	DESIGN DIV.	
DR. C. JOHNSON	J. R. [Signature]	[Signature]	
CH.	DATE: 1/15/54	[Signature]	

AMERICAN ELECTRIC POWER SERVICE CORP.



GENERAL NOTES

- DO NOT SCALE THIS DWG
- PIPE SPEC'S**
- FROM CLEAR WATER OVERFLOW STRUCTURE TO TEN (10) FEET BEYOND TOE OF DIKE - RCP - CLASS B
 - REMAINDER OF PIPE TO BE 36" C.M.P. ASPHALT COATED PAVED 40"
 - WHEN TWO PIPES ARE Banded TOGETHER, THE INVERT BETWEEN THE PIPES IN THE Banded AREA IS TO BE PAVED TO THE SAME THICKNESS AS THE PAVED PIPE.

MATERIAL

- 36" DIA CONC. PIPE ... 245 LIN FT
 36" DIA CONC. PIPE ... 112 LIN FT
 36" DIA CORR. M. PIPE ... 400 LIN FT
 30" DIA CORR. M. PIPE ... 354 LIN FT
- REVISION # 3**
 36" DIA STEEL PIPE 160 LIN FT
- CORRUGATED PIPE & SEEP RINGS
 BY: WHEELING CORR. METAL CO.
 ORD. # 08522-84-4
- CONCRETE PIPE
 BY: PRICE BROS. CO.
 ORD. # 0875-84-4
- CORRUGATED PIPE (30" DIA)
 BY: REMCO STEEL CORP.
 ORD. # 0214-84-5

DATE	NO.	DESCRIPTION	APPD.
3/1	1	REVISED SECT. 2-E, 5-D, 7-K & 9-C	HJS
3/1	2	ADDED SECT. 9-C	HJS
3/1	3	SECTIONS REVISED	HJS
3/1	4	SECTIONS REVISED & ADDED	HJS
3/1	5	RELEASED FOR CONSTRUCTION	HJS

THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE A.E.P. SERVICE CORP. OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

OHIO POWER COMPANY
 MITCHELL PLANT
 CRESAP, WEST VIRGINIA

BOTTOM ASH STORAGE AREA SECTIONS

DR. NO. 12-3434A-3

ARCH.	ELEC.	MECH.	STR.
SCALE: 1" = 20'	ENGINEERING BY: J.P. Steingart		
DR. C.N.J.	DESIGN BY: J.P. Steingart		
CH.	DATE: 2/19/74		
SO. LDR. M.E.	AMERICAN ELECTRIC POWER SERVICE CORP. 2 BROADWAY NEW YORK		

WORK THIS DWG WITH 12-3433

GENERAL NOTES

- DO NOT SCALE THIS DWG.
- CONCRETE**
 - ALL CONCRETE MATERIALS AND WORKMANSHIP SHALL CONFORM TO THE A.E.P.S. CORP. SPECIFICATION # 10002.
 - CONSTRUCTION JOINTS ARE NOT TO BE ADDED, OMITTED OR RELOCATED, EXCEPT WITH THE WRITTEN APPROVAL OF THE N.Y. OFFICE, AND FURTHER PROVIDED THAT THE CONTRACTORS MIXING AND PLACING EQUIPMENT IS PROPERLY SIZED SO THAT NO COLD JOINTS WILL RESULT IN THE CONCRETE.
 - ALL EXPOSED EDGES SHALL HAVE A 1" HIGH BEVEL.
 - ALL EXPOSED VERTICAL EXTERIOR CONCRETE SURFACES TO HAVE RUBBED FINISH.
 - CONCRETE SHALL HAVE MINIMUM COMPRESSIVE STRENGTH (FC) OF 3000 PSI AT 28 DAYS.
- FOUNDATION**
 - SOIL PRESSURE = 2.25

MATERIAL

CONCRETE: APPROX. 22 YDS.
4-1/2" Y INSERTS BY: FIELD

REFERENCE DRAWINGS

- 12-3439 - DOTT. ASH STORAGE AREA DIKES
- 12-3434 - DOTT. ASH STORAGE AREA DIKE SECTIONS
- 12-3437A - OVERFLOW STRUCTURE REINFORCEMENT
- 25-48 - REINFORCEMENT SCHEDULE
- 12-3439 - OVERFLOW STRUCTURE SKIMMERS

DATE	NO.	DESCRIPTION	APP.
REVISIONS			

"THIS DRAWING IS THE PROPERTY OF THE AMERICAN ELECTRIC POWER SERVICE CORP. AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE A.E.P. SERVICE CORP. OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST."








OHIO POWER COMPANY
MITCHELL PLANT
CRESAP, WEST VIRGINIA

BOTTOM-ASH STORAGE AREA
OVERFLOW STRUCTURE
MASONRY

DR. NO. 12-3437




ARCH.	ELEC.	MECH.	STL.
SCALE: 1/8"=1'-0"	ENGINEERING DIV.		
DR. D.V.	DESIGNED BY		
CH. R.M.M.	CHECKED BY		
SO. LDR. M.M.	DATE: 8/1/54		

WOLCHUK AND MAYBAURL
CONSULTING ENGINEERS, NEW YORK, N. Y.










- NOTES**
1. PLAN ADAPTED FROM DRAWINGS PROVIDED BY AEPSC, DATED 11-10-10.
 2. CTB DRAIN LINES AND SECTION LINES BASED ON DRAWINGS PROVIDED BY AEP SERVICE CORPORATION.




THESE DRAWINGS ARE PART OF A SET OF DESIGN DOCUMENTS WHICH ALSO CONTAINS A WRITTEN TEXT. THAT TEXT EXPLAINS SOME OF THE DETAILS SHOWN HEREIN AND THEREFORE THESE DRAWINGS SHOULD ONLY BE USED IN CONJUNCTION WITH THE TEXT.

DATE	REVISIONS	BY
PLAN VIEW		
MITCHELL BLOWDOWN WATER REROUTE		
BOTTOM ASH COMPLEX		
MARSHALL COUNTY, WEST VIRGINIA		
SCALE: AS SHOWN	BY: PAR	CHK: RWC
PREPARED FOR:	AEP SERVICE CORPORATION	
PREPARED BY:	Geo/Environmental Associates, Inc.	
PROJ: 01-2698A	DATE: 9-26-14	SHEET 1 OF 2

NOTE:
 CTR DISCHARGE LINES AND APPURTENANCES LOCATED
 BASED ON DRAWINGS PROVIDED BY AEP SERVICE CORPORATION.




BOTTOM ASH POND OPEN CHANNEL OUTLET PROFILE



**TYPICAL INSTALLATION DETAIL
 (ONE 6-INCH PIPE)**

SCALE: 1" = 1'




**TYPICAL INSTALLATION DETAIL
 (ONE 10-INCH PIPE SLEEVE)**

SCALE: 1" = 1'

MATERIAL PLACEMENT CRITERIA


MATERIAL	MAXIMUM LIFT THICKNESS	COMPACTION
GRANULAR PIPE BEDDING MATERIAL	4"	95 % (ASTM D 698)
GRANULAR PIPE EMBEDMENT MATERIAL	3"	95 % (ASTM D 698)
TRENCH BACKFILL MATERIAL	12"	95 % (ASTM D 698)

NOTE:
 PIPE BEDDING MATERIAL, PIPE EMBEDMENT MATERIAL, AND TRENCH BACKFILL MATERIAL SHALL BE PLACED IN ACCORDANCE WITH THE CONSTRUCTION SPECIFICATIONS AND COMPACTED TO AT LEAST 95 % OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY (ASTM D 698).




**TYPICAL INSTALLATION DETAIL
 (TWO 6-INCH PIPES)**

SCALE: 1" = 1'




**TYPICAL INSTALLATION DETAIL
 (TWO 10-INCH PIPE SLEEVES)**

SCALE: 1" = 1'



**BOTTOM ASH POND OPEN CHANNEL
 OUTLET SECTION (TYP)**



THESE DRAWINGS ARE PART OF A SET OF DESIGN DOCUMENTS WHICH ALSO CONTAINS A WRITTEN TEXT, THAT TEXT EXPLAINS SOME OF THE DETAILS SHOWN HEREIN AND THEREFORE THESE DRAWINGS SHOULD ONLY BE USED IN CONJUNCTION WITH THE TEXT.

DATE	REVISIONS	BY

SECTIONS AND DETAILS
 MITCHELL BLOWDOWN WATER REROUTE
 BOTTOM ASH COMPLEX
 MARSHALL COUNTY, WEST VIRGINIA

SCALE: AS SHOWN | PREPARED FOR: AEP SERVICE CORPORATION

PREPARED BY: GA Geo/Environmental Associates, Inc.
 5000 OVERLOOK CIRCLE • BRISTOL, TENNESSEE 37609-0803 564-0544


PROJ: 01-2692A | DATE: 9-26-14 | SHEET 2 OF 2

ATTACHMENT D

INSTRUMENTATION LOCATION MAP


- NOTES**
1. PLAN ADAPTED FROM DRAWINGS PROVIDED BY AEPSC, DATED 4-13-01
 2. BOREHOLE LOCATIONS AND ELEVATIONS PROVIDED BY AEPSC, SURVEYED 3-5-09.

LEGEND



ID: 4106
 E: 1598326.62
 N: 485316.55
 ELEV: 646.06

ID: 4107
 E: 1599432.55
 N: 485009.99
 ELEV: 683.25



"I, the undersigned, hereby certify that this map is correct and shows, to the best of my knowledge and belief, all the information required by the surface mining laws of the State of West Virginia."

ROSEY W. DEOL, R.P.E. No. 14367
 State of Tennessee, County of Knox, taken, subscribed, and sworn to before me this _____ day of _____, 2009.
 Notary Public
 My Commission Expires _____

THESE DRAWINGS ARE PART OF A SET OF DESIGN DOCUMENTS WHICH ALSO CONTAINS A WRITTEN TEXT THAT TEXT EXPLAINS SOME OF THE DETAILS SHOWN HEREIN AND THEREFORE THESE DRAWINGS SHOULD ONLY BE USED IN CONJUNCTION WITH THE TEXT.

DATE	REVISIONS	BY

PLAN VIEW
 WVDWMM ORDER RESPONSES (ITEM 2)
 MITCHELL BOTTOM ASH COMPLEX
 MARSHALL COUNTY, WEST VIRGINIA

SCALE: AS SHOWN OR RWC OR SWF OR RWC
 PREPARED FOR:
AEP SERVICE CORPORATION

PREPARED BY:
 Geo/Environmental Associates, Inc.
 3502 OVERLOOK CIRCLE • ENDRYVILLE, TENNESSEE 37609 • (865) 664-0344
 PROJ: 09-379 | DATE: 3-18-09 | SHEET 1 OF 3

ATTACHMENT E

HYDROLOGY AND HYDROLOGIC REPORT



We **power** life's possibilities™

**CCR RULES ASSESSMENT AND CERTIFICATION
MITCHELL PLANT BOTTOM ASH COMPLEX
KENTUCKY POWER COMPANY
AEP SERVICE CORPORATION**



**PREPARED BY:
GEO/ENVIRONMENTAL ASSOCIATES, INC.
A SCHNABEL ENGINEERING COMPANY
KNOXVILLE, TENNESSEE**

**PROJECT NUMBER 15055013.00
DECEMBER 22, 2015**



TABLE OF CONTENTS

SITE DESCRIPTION 1
 General 1
 Approximate Existing Conditions 2

SITE INSPECTION 3

FIELD, LABORATORY AND INSTRUMENTATION DATS 3

HYDRAULICS AND HYDROLOGY 4

SLOPE STABILITY ANALYSES 4
 General 4
 Static Factor of Safety Under Long-Term, Maximum Storage Pool Loading Conditions.. 5
 Static Factor of Safety Under Maximum Surcharge Pool Loading Conditions..... 5
 Seismic Factor of Safety 6
 Liquefaction Assessment 6
 End-of-Construction Analyses 7
 Assumptions and Parameters 7
 Summary of Results 8

CERTIFICATION STATEMENT 10

APPENDICES

FIELD AND LABORATORY DATA APPENDIX I

HYDRAULICS AND HYDROLOGY APPENDIX II

STABILITY ANALYSES APPENDIX III

DRAWING APPENDIX IV



**CCR RULES ASSESSMENT AND CERTIFICATION
MITCHELL POWER PLANT BOTTOM ASH COMPLEX
KENTUCKY POWER COMPANY
MARSHALL COUNTY, WEST VIRGINIA
DECEMBER 22, 2015**

INTRODUCTION

Geo/Environmental Associates, Inc. (GA) has performed a site inspection, conducted an engineering assessment, and prepared a certification statement for the Mitchell Power Plant Bottom Ash Complex. These services were performed to meet specific requirements set forth in the Environmental Protection Agency's CCR Rules.⁽¹⁾ Provided in this report is a discussion of GA's findings and a certification statement pertaining to the facility. Field and laboratory data, engineering analyses, and a drawing are included in the appendices.

SITE DESCRIPTION

General

The Mitchell Bottom Ash Complex is equally owned by American Electric Power Generation Resources, Inc. and Kentucky Power Company (KPC) and it is operated by KPC to provide disposal capacity for bottom ash generated at the Mitchell Power Plant. AEPSC, based in Columbus, Ohio, provides engineering support for the Bottom Ash Complex. The Mitchell Bottom Ash Complex is located near Cresap in Marshall County, West Virginia at approximately latitude 39° 49' 30" and longitude 80° 48' 56".

The complex is surrounded by: (1) the Mitchell Power Plant on its north side, (2) West Virginia State Route 2 on its east side, (3) the adjacent wallboard facility and ancillary structures on its south side, and (4) the metal cleaning tank, railroad tracks, and the Ohio River on its west side. As shown on drawing sheet 1 in Appendix IV, the Mitchell Bottom Ash Complex consists of two impounding facilities: (1) the Bottom Ash Pond and (2) the Clear Water Pond. The Bottom Ash Pond comprises the north portion of the complex and the Clear Water Pond comprises the southern portion. The Mitchell Bottom Ash Complex is regulated by the West Virginia Division of Water and Waste Management (WVDWWM) as a Hazard Class "2" structure.

The Bottom Ash Pond is separated into ponding areas in its western and northeastern portions. In general, bottom ash is sluiced into the northeastern portion of the pond; where after, the sluice water is routed through an interior splitter dike to the western portion of the pond. Flow through the western portion of the pond is routed around three interior flow diversion dikes. The southeastern portion of the Bottom Ash Pond is above the normal operating pool (pond) level

(1) Environmental Protection Agency, 40 CFR Parts 257 and 261, "Hazardous and Solid Waste Management System; Disposal of Coal combustion Residuals from Electric Utilities; Final Rule," April 17, 2015



and is used as an excavation and loadout area for bottom ash. The Bottom Ash Pond was constructed partially as an incised pond and partially using raised dike construction. Specifically, the pool level on the east side of the pond is generally below the bottom elevation of the east dike (i.e., it is incised). The inside slopes of the Bottom Ash Pond are lined with a composite soil and PVC liner. The southern dike separates the Bottom Ash Pond and Clear Water Pond.

Overflow from the western portion of the Bottom Ash Pond is conveyed to the Clear Water Pond via a concrete overflow shaft and a 30-inch diameter reinforced concrete pipe to a 30-inch diameter perforated distribution pipe in the Clear Water Pond. The Clear Water Pond was constructed using both incised pond and diked pond construction methods. In general, the pool levels along the southern and eastern sides of the Clear Water Pond are primarily incised. Similar to the Bottom Ash Pond, the inside slopes of the Clear Water Pond are lined with a composite soil and PVC liner. Overflow from the Clear Water Pond is conveyed through an overflow tower into a 36-inch diameter reinforced concrete pipe through the embankment and then a series of 36-inch diameter corrugated metal pipes which discharge into a riprap-lined channel leading to the Ohio River.

Approximate Existing Conditions

A summary of the approximate existing conditions for the Mitchell Bottom Ash Complex is provided in List 1. A site plan view of the facility is included in Appendix IV.



LIST 1
SUMMARY OF APPROXIMATE EXISTING CONDITIONS
FOR MITCHELL BOTTOM ASH COMPLEX

Bottom Ash Pond Crest Elevation	690 feet, NAVD
Bottom Ash Pond Normal Operating Pool Level	681 feet, NAVD
Bottom Ash Pond Design Storm Level ⁽¹⁾	682.98 feet, NAVD
Bottom Ash Pond Bottom Level.....	660 feet, NAVD
Clear Water Pond Crest Elevation	675 feet, NAVD
Clear Water Pond Normal Operating Pool Level	664 feet, NAVD
Clear Water Pond Design Storm Level ⁽²⁾	665.62 feet, NAVD
Clear Water Pond Bottom Level.....	645 feet, NAVD

Notes:

- (1) The Bottom Ash Pond maximum design storm level is based on a normal operating pool elevation of 681 feet, NAVD and a pool increase of 1.98 feet during the 1/2 PMP 6-hour storm event.
- (2) The Clear Water Pond maximum design storm level is based on a normal operating pool elevation of 664 feet, NAVD and a pool increase of 1.62 feet during the 1/2 PMP 6-hour storm event.

SITE INSPECTION

At the request of AEPSC, GA personnel performed a site inspection of the Bottom Ash Complex to observe and document the prevalent site conditions. Specifically, Seth W. Frank, P.E. (GA) performed a site inspection of the Bottom Ash Complex on July 14, 2015. It is GA's opinion that the Bottom Ash Complex is in good condition. Moreover, GA believes that the conditions observed, during the July 14, 2015, site inspection, are representative of the conditions modeled in the assessments and analyses provided in this report.

FIELD, LABORATORY, AND INSTRUMENTATION DATA

For reference, pertinent field and laboratory data for the Bottom Ash Complex is provided in Appendix I. The field and laboratory data were gathered during a subsurface investigation coordinated by GA in 2009. The field data includes detailed borehole logs and results of in-situ testing (i.e., standard penetration testing). Laboratory data provided in Appendix I includes: (1) grain size distributions, (2) Atterberg limits test results, (3) unconfined compressive strength test results, and (4) triaxial compressive strength test results.

AEP monitors four standpipe piezometers, at the Bottom Ash Complex facility, monthly. Results of instrumentation monitoring are collected and summarized in annual inspection reports.



Locations of the site boreholes/piezometers are shown on the Site Plan View drawing in Appendix IV.

HYDRAULICS AND HYDROLOGY

Flood routing analyses were developed for the existing conditions at the Bottom Ash Complex using the *HEC-1* computer program, developed by the U.S. Army Corps of Engineers. Flood routing parameters and the *HEC-1* output are provided in Appendix II. In accordance with the 40 CFR Parts 257 and 261 (CCR Rules), the flood routing analyses were performed using the 1/2 PMP 6-hour storm event. A summary of the flood routing results is provided in Table 1.

TABLE 1 SUMMARY OF FLOOD ROUTING ANALYSES FOR EXISTING CONDITIONS							
Pond	Crest Elevation (ft, NAVD)	Design Storm	Principal Spillway/Overflow Structure Invert Elevation/Pool at Start of storm (ft, NAVD)	Peak Inflow (cfs)	Peak Outflow (cfs)	Peak Stage (ft, NAVD)	Minimum Freeboard (ft)
Bottom Ash	690'	1/2 PMP6-hour	681'	111.08	23.83	683.51	6.49
Clearwater	675'	1/2 PMP6-hour	664'	71.44	44.76	666.50	8.50

As shown in Table 1, the as-built Bottom Ash Pond and Clearwater Pond are capable of storing/routing the 1/2 PMP 6-hour storm event, while providing at least 3 feet of freeboard for the minimum embankment crest elevations of 690 feet, NAVD and 675 feet, NAVD respectively. Note that the storm routing analyses assume a constant, peak inflow of 7.5 million gallons per day from plant processes, in addition to the storm runoff.

SLOPE STABILITY ANALYSES

General

The computer program *SLOPE/W*, developed by GEO-SLOPE International, Ltd., was used to perform slope stability analyses on two critical embankment profiles for the as-built Bottom Ash Complex. Specifically, the Morgenstern-Price limit equilibrium method was applied in the slope stability analyses. The slope stability analyses were conducted for the as-built Bottom Ash Complex Profiles SP1-SP1 and SP2-SP2. Locations of the critical profiles are shown on the



CERTIFICATION STATEMENT

Based on the site inspections, review of construction monitoring and periodic inspection data, the results of the field and laboratory testing of the materials used in the embankment construction, and our review of the as-built embankment geometry; it is our opinion that the embankments within the Bottom Ash Complex have slope stability factors of safety that meet or exceed the requirements in the CCR Rules. Furthermore, based on our review of the as-built embankment geometries, current operating pool levels, and the existing spillway and overflow system; we believe that the facility is capable of storing/routing the runoff from the 1/2 PMP 6-hour storm event.


Accordingly, I hereby certify that the Bottom Ash Complex is generally maintained in good condition and the facility generally meets the stability requirements in the CCR Rules. It should be clearly noted that this certification is not a legal guarantee. This certification is merely a statement by a registered professional engineer that, to the best of his knowledge, the facility was generally constructed according to the approved plan and that it meets the applicable stability requirements set forth in the CCR Rules. No warranties, expressed or implied, are provided. If you have any questions regarding the information provided, please contact me at 865-584-0344.



Seth W. Frank, P.E.
West Virginia R.P.E. No. 20574

12-22-2015

Date



Appendix II

Hydraulics and Hydrology



Bottom Ash Pond

**SUMMARY OF INFLOW HYDROGRAPH
AND FLOOD ROUTING THROUGH
MITCHELL BOTTOM ASH POND
FOR ½ 6-HOUR PMP STORM EVENT**

Starting Pool Elevation	=	681 ft, NAVD
Pipe Spillway Invert Elevation	=	681 ft, NAVD
Crest Elevation	=	690 ft, NAVD
Peak Inflow	=	111.08 cfs
Peak Outflow	=	23.83 cfs
Peak Storage	=	10.75 ac-ft
Maximum Impoundment Level During Storm	=	683.51 ft, NAVD
Minimum Freeboard During Storm	=	6.49 ft

```

1*****
*
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
*
* RUN DATE 12/21/2015 TIME 10:40:34 *
*
*****

```

```

*****
*
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*
*****

```

```

X X XXXXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE. THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
 KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

*** FREE ***

```

1 ID *****
2 ID * Mitchell Bottom Ash Pond File: MBAP.inp *
3 ID * GA Project No. 15055007.00 *
4 ID * Storm Storage for 1/2 6-Hour PMP *
5 ID * Crest Elevation = 690' *
6 ID *****
7 ID * Analyses by: Geo/Environmental Associates, Inc. *
8 ID * Knoxville, TN *
9 ID * Seth W. Frank P.E. *
10 ID * August 2014 *
11 ID *****
12 IT 5 0 0 300
13 IO 1
14 JR PRECIP 0.5
15 VS BASIN BASE IN IMP IMP IMP
16 VV 2.11 2.11 2.11 2.11 6.11 7.11
17 IN 15

18 KK BASIN
19 KM COMPUTE INFLOW HYDROGRAPH FOR MITCHELL BOTTOM ASH POND USING SCS METHOD
20 PB 0
21 PI 0.258 0.347 0.420 0.478 0.520 0.546 0.624 0.804 0.790 0.939
22 PI 2.264 4.483 4.834 3.277 1.215 0.797 0.831 0.735 0.553 0.535
23 PI 0.501 0.451 0.386 0.305
24 BA 0.016
25 LU 0 0.05 44.8
26 UD 0.0

27 KK BASE
28 KM BASE FLOW
29 IN 360
30 QI 11.6 11.6 11.6

31 KK IN
32 KM COMBINE BASIN INFLOW AND BASEFLOW
33 KO 1
34 HC 2

35 KK IMP
36 KM ROUTE COMPUTED HYDROGRAPH AND BASE FLOW THROUGH CLEAR WATER POND
37 RS 1 ELEV 681
38 SA 4.03 4.18 4.45 4.72 6.27 7.81 8.03 8.26 8.48 8.71
39 SQ 0 6.90 17.82 29.62 40.80 50.31 57.32 61.12 61.12 61.12
40 SE 681 682 683 684 685 686 687 688 689 690
41 ZZ

```

```

1*****
*
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
*
* RUN DATE 12/21/2015 TIME 10:40:34 *
*
*****

```

```

*****
*
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*
*****

```

```

*****
* Mitchell Bottom Ash Pond File: MBAP.inp *
* GA Project No. 15055007.00 *
* Storm Storage for 1/2 6-Hour PMP *
* Crest Elevation = 690' *
*****
* Analyses by: Geo/Environmental Associates, Inc. *
* Knoxville, TN *
* Seth W. Frank P.E. *
* August 2014 *
*****

```

```

13 IO OUTPUT CONTROL VARIABLES
      IPRNT 1 PRINT CONTROL
      IPLOT 0 PLOT CONTROL
      QSCAL 0. HYDROGRAPH PLOT SCALE

```

```

IT HYDROGRAPH TIME DATA
      NMIN 5 MINUTES IN COMPUTATION INTERVAL
      IDATE 1 0 STARTING DATE
      ITIME 0000 STARTING TIME
      NQ 300 NUMBER OF HYDROGRAPH ORDINATES
      NDDATE 2 0 ENDING DATE
      NDTIME 0055 ENDING TIME
      ICENT 19 CENTURY MARK

```

```

      COMPUTATION INTERVAL .08 HOURS
      TOTAL TIME BASE 24.92 HOURS

```

```

ENGLISH UNITS
      DRAINAGE AREA SQUARE MILES
      PRECIPITATION DEPTH INCHES
      LENGTH, ELEVATION FEET
      FLOW CUBIC FEET PER SECOND
      STORAGE VOLUME ACRE-FEET
      SURFACE AREA ACRES
      TEMPERATURE DEGREES FAHRENHEIT

```

USER-DEFINED OUTPUT SPECIFICATIONS

TABLE 1

VS STATION	BASIN	BASE	IN	IMP	IMP	IMP				
VV VARIABLE CODE	2.11	2.11	2.11	2.11	6.11	7.11	.00	.00	.00	.00

```

JP MULTI-PLAN OPTION
      NPLAN 1 NUMBER OF PLANS

```

```

JR MULTI-RATIO OPTION
      RATIOS OF PRECIPITATION
      .50

```

*** **

```

*****
*
* BASIN *
*
*****

```

COMPUTE INFLOW HYDROGRAPH FOR MITCHELL BOTTOM ASH POND USING SCS METHOD

```

17 IN TIME DATA FOR INPUT TIME SERIES
      JXMIN 15 TIME INTERVAL IN MINUTES
      JXDATE 1 0 STARTING DATE
      JXTIME 0 STARTING TIME

```

SUBBASIN RUNOFF DATA

24 BA SUBBASIN CHARACTERISTICS
TAREA .02 SUBBASIN AREA

PRECIPITATION DATA

20 PB STORM 26.89 BASIN TOTAL PRECIPITATION

21 PI INCREMENTAL PRECIPITATION PATTERN

.09	.09	.09	.12	.12	.12	.14	.14	.14	.16
.16	.16	.17	.17	.17	.18	.18	.18	.21	.21
.21	.27	.27	.27	.26	.26	.26	.31	.31	.31
.75	.75	.75	1.49	1.49	1.49	1.61	1.61	1.61	1.09
1.09	1.09	.41	.40	.41	.27	.27	.27	.28	.28
.28	.25	.24	.25	.18	.18	.18	.18	.18	.18
.17	.17	.17	.15	.15	.15	.13	.13	.13	.10
.10	.10								

25 LU UNIFORM LOSS RATE
STRTL .00 INITIAL LOSS
CNSTL .05 UNIFORM LOSS RATE
RTIMP 44.80 PERCENT IMPERVIOUS AREA

26 UD SCS DIMENSIONLESS UNITGRAPH
TLAG .00 LAG

PEAK FLOW	TIME	MAXIMUM AVERAGE FLOW			
		6-HR	24-HR	72-HR	24.92-HR
+ (CFS)	(HR)				
+ 24.	4.58	21.	15.	14.	14.
		(INCHES)	6.212	17.047	17.093
		(AC-FT)	11.	29.	29.
PEAK STORAGE	TIME	MAXIMUM AVERAGE STORAGE			
		6-HR	24-HR	72-HR	24.92-HR
+ (AC-FT)	(HR)				
+ 11.	4.58	10.	7.	7.	7.
PEAK STAGE	TIME	MAXIMUM AVERAGE STAGE			
		6-HR	24-HR	72-HR	24.92-HR
+ (FEET)	(HR)				
+ 683.51	4.58	683.30	682.70	682.64	682.64
CUMULATIVE AREA =		.03 SQ MI			

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE MILES
 TIME TO PEAK IN HOURS

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO PRECIPITATION	
				RATIO	1
					.50
HYDROGRAPH AT					
+	BASIN	.02	1	FLOW	99.
				TIME	3.25
HYDROGRAPH AT					
+	BASE	.02	1	FLOW	12.
				TIME	.08
2 COMBINED AT					
+	IN	.03	1	FLOW	111.
				TIME	3.25
ROUTED TO					
+	IMP	.03	1	FLOW	24.
				TIME	4.58
				** PEAK STAGES IN FEET **	
			1	STAGE	683.51
				TIME	4.58

STATION	BASIN	BASE	IN	IMP	IMP	IMP
PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE
RATIO	1	1	1	1	1	1
	.50	.50	.50	.50	.50	.50

PER DAY MON HRMN

1	1	0000	.00	11.60	11.60	.00	.00	681.00
2	1	0005	3.75	11.60	15.35	.16	.09	681.02
3	1	0010	4.80	11.60	16.40	.34	.20	681.05
4	1	0015	5.00	11.60	16.60	.52	.31	681.08
5	1	0020	6.41	11.60	18.01	.72	.43	681.10
6	1	0025	6.79	11.60	18.39	.92	.55	681.13
7	1	0030	6.87	11.60	18.47	1.12	.67	681.16
8	1	0035	8.00	11.60	19.60	1.32	.79	681.19
9	1	0040	8.31	11.60	19.91	1.54	.91	681.22
10	1	0045	8.38	11.60	19.98	1.75	1.04	681.25
11	1	0050	9.28	11.60	20.88	1.96	1.17	681.28
12	1	0055	9.53	11.60	21.13	2.18	1.30	681.32
13	1	0100	9.58	11.60	21.18	2.40	1.43	681.35
14	1	0105	10.23	11.60	21.83	2.62	1.56	681.38
15	1	0110	10.41	11.60	22.01	2.84	1.69	681.41
16	1	0115	10.45	11.60	22.05	3.06	1.82	681.44
17	1	0120	10.85	11.60	22.45	3.28	1.95	681.48
18	1	0125	10.96	11.60	22.56	3.51	2.09	681.51
19	1	0130	10.99	11.60	22.59	3.73	2.22	681.54
20	1	0135	12.19	11.60	23.79	3.95	2.35	681.57
21	1	0140	12.52	11.60	24.12	4.18	2.49	681.61
22	1	0145	12.59	11.60	24.19	4.41	2.62	681.64
23	1	0150	15.36	11.60	26.96	4.65	2.77	681.67
24	1	0155	16.14	11.60	27.74	4.91	2.92	681.71
25	1	0200	16.29	11.60	27.89	5.18	3.08	681.75
26	1	0205	16.10	11.60	27.70	5.44	3.24	681.79
27	1	0210	16.04	11.60	27.64	5.69	3.39	681.83
28	1	0215	16.03	11.60	27.63	5.95	3.54	681.86
29	1	0220	18.32	11.60	29.92	6.21	3.69	681.90
30	1	0225	18.96	11.60	30.56	6.49	3.86	681.94
31	1	0230	19.08	11.60	30.68	6.76	4.02	681.98
32	1	0235	39.43	11.60	51.03	7.28	4.26	682.04
33	1	0240	45.13	11.60	56.73	8.09	4.57	682.11
34	1	0245	46.24	11.60	57.84	8.94	4.91	682.19
35	1	0250	80.51	11.60	92.11	10.08	5.36	682.29
36	1	0255	90.04	11.60	101.64	11.58	5.95	682.43
37	1	0300	91.92	11.60	103.52	13.15	6.58	682.57
38	1	0305	97.68	11.60	109.28	14.77	7.21	682.72
39	1	0310	99.18	11.60	110.78	16.41	7.86	682.87
40	1	0315	99.48	11.60	111.08	18.05	8.51	683.02
41	1	0320	75.65	11.60	87.25	19.47	9.06	683.14
42	1	0325	68.96	11.60	80.56	20.61	9.50	683.24
43	1	0330	67.65	11.60	79.25	21.65	9.91	683.32
44	1	0335	35.75	11.60	47.35	22.38	10.19	683.39
45	1	0340	26.89	11.60	38.49	22.74	10.33	683.42
46	1	0345	25.15	11.60	36.75	23.00	10.43	683.44
47	1	0350	18.39	11.60	29.99	23.18	10.50	683.45
48	1	0355	16.60	11.60	28.20	23.29	10.54	683.46
49	1	0400	16.24	11.60	27.84	23.37	10.58	683.47
50	1	0405	16.70	11.60	28.30	23.45	10.61	683.48

TABLE 1 (CONT.)		STATION	BASIN	BASE	IN	IMP	IMP	IMP	
		PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE	
		RATIO	.50	.50	.50	.50	.50	.50	
PER	DAY	MON	HRMN						
51	1		0410	16.84	11.60	28.44	23.54	10.64	683.48
52	1		0415	16.87	11.60	28.47	23.63	10.68	683.49
53	1		0420	15.40	11.60	27.00	23.70	10.70	683.50
54	1		0425	14.99	11.60	26.59	23.75	10.72	683.50
55	1		0430	14.91	11.60	26.51	23.80	10.74	683.51
56	1		0435	12.10	11.60	23.70	23.83	10.75	683.51
57	1		0440	11.32	11.60	22.92	23.82	10.75	683.51
58	1		0445	11.17	11.60	22.77	23.80	10.74	683.51
59	1		0450	10.86	11.60	22.46	23.78	10.73	683.51
60	1		0455	10.78	11.60	22.38	23.75	10.72	683.50
61	1		0500	10.77	11.60	22.37	23.73	10.72	683.50
62	1		0505	10.24	11.60	21.84	23.70	10.70	683.50
63	1		0510	10.10	11.60	21.70	23.67	10.69	683.50
64	1		0515	10.07	11.60	21.67	23.63	10.68	683.49
65	1		0520	9.29	11.60	20.89	23.59	10.66	683.49
66	1		0525	9.08	11.60	20.68	23.54	10.64	683.48
67	1		0530	9.04	11.60	20.64	23.49	10.62	683.48
68	1		0535	8.03	11.60	19.63	23.43	10.60	683.48
69	1		0540	7.75	11.60	19.35	23.36	10.57	683.47
70	1		0545	7.70	11.60	19.30	23.29	10.55	683.46
71	1		0550	6.44	11.60	18.04	23.21	10.51	683.46
72	1		0555	6.10	11.60	17.70	23.12	10.48	683.45
73	1		0600	6.03	11.60	17.63	23.02	10.44	683.44
74	1		0605	1.55	11.60	13.15	22.89	10.39	683.43
75	1		0610	.29	11.60	11.89	22.71	10.32	683.41
76	1		0615	.05	11.60	11.65	22.51	10.24	683.40
77	1		0620	.00	11.60	11.60	22.32	10.17	683.38
78	1		0625	.00	11.60	11.60	22.13	10.09	683.37
79	1		0630	.00	11.60	11.60	21.95	10.02	683.35
80	1		0635	.00	11.60	11.60	21.77	9.95	683.33
81	1		0640	.00	11.60	11.60	21.59	9.88	683.32
82	1		0645	.00	11.60	11.60	21.41	9.81	683.30
83	1		0650	.00	11.60	11.60	21.24	9.75	683.29
84	1		0655	.00	11.60	11.60	21.07	9.68	683.28
85	1		0700	.00	11.60	11.60	20.90	9.62	683.26
86	1		0705	.00	11.60	11.60	20.74	9.55	683.25
87	1		0710	.00	11.60	11.60	20.58	9.49	683.23
88	1		0715	.00	11.60	11.60	20.42	9.43	683.22
89	1		0720	.00	11.60	11.60	20.27	9.37	683.21
90	1		0725	.00	11.60	11.60	20.11	9.31	683.19
91	1		0730	.00	11.60	11.60	19.97	9.25	683.18
92	1		0735	.00	11.60	11.60	19.82	9.20	683.17
93	1		0740	.00	11.60	11.60	19.67	9.14	683.16
94	1		0745	.00	11.60	11.60	19.53	9.08	683.15
95	1		0750	.00	11.60	11.60	19.39	9.03	683.13
96	1		0755	.00	11.60	11.60	19.26	8.98	683.12
97	1		0800	.00	11.60	11.60	19.12	8.92	683.11
98	1		0805	.00	11.60	11.60	18.99	8.87	683.10
99	1		0810	.00	11.60	11.60	18.86	8.82	683.09
100	1		0815	.00	11.60	11.60	18.73	8.77	683.08

TABLE 1 (CONT.)	STATION PLAN RATIO	BASIN FLOW	BASE FLOW	IN FLOW	IMP FLOW	IMP STORAGE	IMP STAGE
		1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER	DAY	MON	HRMN						
101	1		0820	.00	11.60	11.60	18.61	8.72	683.07
102	1		0825	.00	11.60	11.60	18.48	8.68	683.06
103	1		0830	.00	11.60	11.60	18.36	8.63	683.05
104	1		0835	.00	11.60	11.60	18.24	8.58	683.04
105	1		0840	.00	11.60	11.60	18.13	8.54	683.03
106	1		0845	.00	11.60	11.60	18.01	8.49	683.02
107	1		0850	.00	11.60	11.60	17.90	8.45	683.01
108	1		0855	.00	11.60	11.60	17.79	8.41	683.00
109	1		0900	.00	11.60	11.60	17.68	8.36	682.99
110	1		0905	.00	11.60	11.60	17.58	8.32	682.98
111	1		0910	.00	11.60	11.60	17.47	8.28	682.97
112	1		0915	.00	11.60	11.60	17.37	8.24	682.96
113	1		0920	.00	11.60	11.60	17.27	8.20	682.95
114	1		0925	.00	11.60	11.60	17.17	8.16	682.94
115	1		0930	.00	11.60	11.60	17.08	8.13	682.93
116	1		0935	.00	11.60	11.60	16.98	8.09	682.92
117	1		0940	.00	11.60	11.60	16.89	8.05	682.91
118	1		0945	.00	11.60	11.60	16.80	8.02	682.91
119	1		0950	.00	11.60	11.60	16.71	7.98	682.90
120	1		0955	.00	11.60	11.60	16.62	7.95	682.89
121	1		1000	.00	11.60	11.60	16.53	7.91	682.88
122	1		1005	.00	11.60	11.60	16.45	7.88	682.87
123	1		1010	.00	11.60	11.60	16.37	7.84	682.87
124	1		1015	.00	11.60	11.60	16.28	7.81	682.86
125	1		1020	.00	11.60	11.60	16.20	7.78	682.85
126	1		1025	.00	11.60	11.60	16.12	7.75	682.84
127	1		1030	.00	11.60	11.60	16.04	7.72	682.84
128	1		1035	.00	11.60	11.60	15.97	7.69	682.83
129	1		1040	.00	11.60	11.60	15.89	7.66	682.82
130	1		1045	.00	11.60	11.60	15.82	7.63	682.82
131	1		1050	.00	11.60	11.60	15.74	7.60	682.81
132	1		1055	.00	11.60	11.60	15.67	7.57	682.80
133	1		1100	.00	11.60	11.60	15.60	7.54	682.80
134	1		1105	.00	11.60	11.60	15.53	7.52	682.79
135	1		1110	.00	11.60	11.60	15.47	7.49	682.78
136	1		1115	.00	11.60	11.60	15.40	7.46	682.78
137	1		1120	.00	11.60	11.60	15.33	7.44	682.77
138	1		1125	.00	11.60	11.60	15.27	7.41	682.77
139	1		1130	.00	11.60	11.60	15.21	7.39	682.76
140	1		1135	.00	11.60	11.60	15.14	7.36	682.75
141	1		1140	.00	11.60	11.60	15.08	7.34	682.75
142	1		1145	.00	11.60	11.60	15.02	7.31	682.74
143	1		1150	.00	11.60	11.60	14.96	7.29	682.74
144	1		1155	.00	11.60	11.60	14.90	7.27	682.73
145	1		1200	.00	11.60	11.60	14.85	7.24	682.73
146	1		1205	.00	11.60	11.60	14.79	7.22	682.72
147	1		1210	.00	11.60	11.60	14.74	7.20	682.72
148	1		1215	.00	11.60	11.60	14.68	7.18	682.71
149	1		1220	.00	11.60	11.60	14.63	7.16	682.71
150	1		1225	.00	11.60	11.60	14.58	7.14	682.70

TABLE 1	STATION	BASIN	BASE	IN	IMP	IMP	IMP
(CONT.)	PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE
	RATIO	1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER DAY MON HRMN

151	1	1230	.00	11.60	11.60	14.52	7.12	682.70
152	1	1235	.00	11.60	11.60	14.47	7.10	682.69
153	1	1240	.00	11.60	11.60	14.42	7.08	682.69
154	1	1245	.00	11.60	11.60	14.38	7.06	682.68
155	1	1250	.00	11.60	11.60	14.33	7.04	682.68
156	1	1255	.00	11.60	11.60	14.28	7.02	682.68
157	1	1300	.00	11.60	11.60	14.23	7.00	682.67
158	1	1305	.00	11.60	11.60	14.19	6.98	682.67
159	1	1310	.00	11.60	11.60	14.14	6.97	682.66
160	1	1315	.00	11.60	11.60	14.10	6.95	682.66
161	1	1320	.00	11.60	11.60	14.06	6.93	682.66
162	1	1325	.00	11.60	11.60	14.01	6.92	682.65
163	1	1330	.00	11.60	11.60	13.97	6.90	682.65
164	1	1335	.00	11.60	11.60	13.93	6.88	682.64
165	1	1340	.00	11.60	11.60	13.89	6.87	682.64
166	1	1345	.00	11.60	11.60	13.85	6.85	682.64
167	1	1350	.00	11.60	11.60	13.81	6.84	682.63
168	1	1355	.00	11.60	11.60	13.77	6.82	682.63
169	1	1400	.00	11.60	11.60	13.74	6.81	682.63
170	1	1405	.00	11.60	11.60	13.70	6.79	682.62
171	1	1410	.00	11.60	11.60	13.66	6.78	682.62
172	1	1415	.00	11.60	11.60	13.63	6.76	682.62
173	1	1420	.00	11.60	11.60	13.59	6.75	682.61
174	1	1425	.00	11.60	11.60	13.56	6.74	682.61
175	1	1430	.00	11.60	11.60	13.52	6.72	682.61
176	1	1435	.00	11.60	11.60	13.49	6.71	682.60
177	1	1440	.00	11.60	11.60	13.46	6.70	682.60
178	1	1445	.00	11.60	11.60	13.43	6.68	682.60
179	1	1450	.00	11.60	11.60	13.40	6.67	682.59
180	1	1455	.00	11.60	11.60	13.36	6.66	682.59
181	1	1500	.00	11.60	11.60	13.33	6.65	682.59
182	1	1505	.00	11.60	11.60	13.30	6.63	682.59
183	1	1510	.00	11.60	11.60	13.27	6.62	682.58
184	1	1515	.00	11.60	11.60	13.25	6.61	682.58
185	1	1520	.00	11.60	11.60	13.22	6.60	682.58
186	1	1525	.00	11.60	11.60	13.19	6.59	682.58
187	1	1530	.00	11.60	11.60	13.16	6.58	682.57
188	1	1535	.00	11.60	11.60	13.13	6.57	682.57
189	1	1540	.00	11.60	11.60	13.11	6.56	682.57
190	1	1545	.00	11.60	11.60	13.08	6.55	682.57
191	1	1550	.00	11.60	11.60	13.06	6.54	682.56
192	1	1555	.00	11.60	11.60	13.03	6.53	682.56
193	1	1600	.00	11.60	11.60	13.01	6.52	682.56
194	1	1605	.00	11.60	11.60	12.98	6.51	682.56
195	1	1610	.00	11.60	11.60	12.96	6.50	682.55
196	1	1615	.00	11.60	11.60	12.93	6.49	682.55
197	1	1620	.00	11.60	11.60	12.91	6.48	682.55
198	1	1625	.00	11.60	11.60	12.89	6.47	682.55
199	1	1630	.00	11.60	11.60	12.87	6.46	682.55
200	1	1635	.00	11.60	11.60	12.84	6.45	682.54

TABLE 1	STATION	BASIN	BASE	IN	IMP	IMP	IMP
(CONT.)	PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE
	RATIO	1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER DAY MON HRMN

201	1	1640	.00	11.60	11.60	12.82	6.44	682.54
202	1	1645	.00	11.60	11.60	12.80	6.44	682.54
203	1	1650	.00	11.60	11.60	12.78	6.43	682.54
204	1	1655	.00	11.60	11.60	12.76	6.42	682.54
205	1	1700	.00	11.60	11.60	12.74	6.41	682.53
206	1	1705	.00	11.60	11.60	12.72	6.40	682.53
207	1	1710	.00	11.60	11.60	12.70	6.40	682.53
208	1	1715	.00	11.60	11.60	12.68	6.39	682.53
209	1	1720	.00	11.60	11.60	12.66	6.38	682.53
210	1	1725	.00	11.60	11.60	12.65	6.37	682.53
211	1	1730	.00	11.60	11.60	12.63	6.37	682.52
212	1	1735	.00	11.60	11.60	12.61	6.36	682.52
213	1	1740	.00	11.60	11.60	12.59	6.35	682.52
214	1	1745	.00	11.60	11.60	12.58	6.35	682.52
215	1	1750	.00	11.60	11.60	12.56	6.34	682.52
216	1	1755	.00	11.60	11.60	12.54	6.33	682.52
217	1	1800	.00	11.60	11.60	12.53	6.33	682.52
218	1	1805	.00	11.60	11.60	12.51	6.32	682.51
219	1	1810	.00	11.60	11.60	12.49	6.31	682.51
220	1	1815	.00	11.60	11.60	12.48	6.31	682.51
221	1	1820	.00	11.60	11.60	12.46	6.30	682.51
222	1	1825	.00	11.60	11.60	12.45	6.30	682.51
223	1	1830	.00	11.60	11.60	12.43	6.29	682.51
224	1	1835	.00	11.60	11.60	12.42	6.29	682.51
225	1	1840	.00	11.60	11.60	12.41	6.28	682.50
226	1	1845	.00	11.60	11.60	12.39	6.27	682.50
227	1	1850	.00	11.60	11.60	12.38	6.27	682.50
228	1	1855	.00	11.60	11.60	12.36	6.26	682.50
229	1	1900	.00	11.60	11.60	12.35	6.26	682.50
230	1	1905	.00	11.60	11.60	12.34	6.25	682.50
231	1	1910	.00	11.60	11.60	12.33	6.25	682.50
232	1	1915	.00	11.60	11.60	12.31	6.24	682.50
233	1	1920	.00	11.60	11.60	12.30	6.24	682.49
234	1	1925	.00	11.60	11.60	12.29	6.23	682.49
235	1	1930	.00	11.60	11.60	12.28	6.23	682.49
236	1	1935	.00	11.60	11.60	12.26	6.22	682.49
237	1	1940	.00	11.60	11.60	12.25	6.22	682.49
238	1	1945	.00	11.60	11.60	12.24	6.22	682.49
239	1	1950	.00	11.60	11.60	12.23	6.21	682.49
240	1	1955	.00	11.60	11.60	12.22	6.21	682.49
241	1	2000	.00	11.60	11.60	12.21	6.20	682.49
242	1	2005	.00	11.60	11.60	12.20	6.20	682.49
243	1	2010	.00	11.60	11.60	12.19	6.19	682.48
244	1	2015	.00	11.60	11.60	12.18	6.19	682.48
245	1	2020	.00	11.60	11.60	12.17	6.19	682.48
246	1	2025	.00	11.60	11.60	12.16	6.18	682.48
247	1	2030	.00	11.60	11.60	12.15	6.18	682.48
248	1	2035	.00	11.60	11.60	12.14	6.17	682.48
249	1	2040	.00	11.60	11.60	12.13	6.17	682.48
250	1	2045	.00	11.60	11.60	12.12	6.17	682.48

TABLE 1	STATION	BASIN	BASE	IN	IMP	IMP	IMP
(CONT.)	PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE
	RATIO	1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER	DAY	MON	HRMN						
251	1		2050	.00	11.60	11.60	12.11	6.16	682.48
252	1		2055	.00	11.60	11.60	12.10	6.16	682.48
253	1		2100	.00	11.60	11.60	12.09	6.16	682.48
254	1		2105	.00	11.60	11.60	12.09	6.15	682.47
255	1		2110	.00	11.60	11.60	12.08	6.15	682.47
256	1		2115	.00	11.60	11.60	12.07	6.15	682.47
257	1		2120	.00	11.60	11.60	12.06	6.14	682.47
258	1		2125	.00	11.60	11.60	12.05	6.14	682.47
259	1		2130	.00	11.60	11.60	12.05	6.14	682.47
260	1		2135	.00	11.60	11.60	12.04	6.13	682.47
261	1		2140	.00	11.60	11.60	12.03	6.13	682.47
262	1		2145	.00	11.60	11.60	12.02	6.13	682.47
263	1		2150	.00	11.60	11.60	12.02	6.13	682.47
264	1		2155	.00	11.60	11.60	12.01	6.12	682.47
265	1		2200	.00	11.60	11.60	12.00	6.12	682.47
266	1		2205	.00	11.60	11.60	11.99	6.12	682.47
267	1		2210	.00	11.60	11.60	11.99	6.11	682.47
268	1		2215	.00	11.60	11.60	11.98	6.11	682.47
269	1		2220	.00	11.60	11.60	11.97	6.11	682.46
270	1		2225	.00	11.60	11.60	11.97	6.11	682.46
271	1		2230	.00	11.60	11.60	11.96	6.10	682.46
272	1		2235	.00	11.60	11.60	11.95	6.10	682.46
273	1		2240	.00	11.60	11.60	11.95	6.10	682.46
274	1		2245	.00	11.60	11.60	11.94	6.10	682.46
275	1		2250	.00	11.60	11.60	11.94	6.09	682.46
276	1		2255	.00	11.60	11.60	11.93	6.09	682.46
277	1		2300	.00	11.60	11.60	11.93	6.09	682.46
278	1		2305	.00	11.60	11.60	11.92	6.09	682.46
279	1		2310	.00	11.60	11.60	11.91	6.09	682.46
280	1		2315	.00	11.60	11.60	11.91	6.08	682.46
281	1		2320	.00	11.60	11.60	11.90	6.08	682.46
282	1		2325	.00	11.60	11.60	11.90	6.08	682.46
283	1		2330	.00	11.60	11.60	11.89	6.08	682.46
284	1		2335	.00	11.60	11.60	11.89	6.08	682.46
285	1		2340	.00	11.60	11.60	11.88	6.07	682.46
286	1		2345	.00	11.60	11.60	11.88	6.07	682.46
287	1		2350	.00	11.60	11.60	11.87	6.07	682.46
288	1		2355	.00	11.60	11.60	11.87	6.07	682.46
289	2		0000	.00	11.60	11.60	11.86	6.07	682.45
290	2		0005	.00	11.60	11.60	11.86	6.06	682.45
291	2		0010	.00	11.60	11.60	11.85	6.06	682.45
292	2		0015	.00	11.60	11.60	11.85	6.06	682.45
293	2		0020	.00	11.60	11.60	11.85	6.06	682.45
294	2		0025	.00	11.60	11.60	11.84	6.06	682.45
295	2		0030	.00	11.60	11.60	11.84	6.06	682.45
296	2		0035	.00	11.60	11.60	11.83	6.05	682.45
297	2		0040	.00	11.60	11.60	11.83	6.05	682.45
298	2		0045	.00	11.60	11.60	11.83	6.05	682.45
299	2		0050	.00	11.60	11.60	11.82	6.05	682.45
300	2		0055	.00	11.60	11.60	11.82	6.05	682.45
			MAX	99.48	11.60	111.08	23.83	10.75	683.51
			MIN	.00	11.60	11.60	.00	.00	681.00
			AVE	5.49	11.60	17.09	14.14	6.88	682.64

*** NORMAL END OF HEC-1 ***

Clear Water Pond

**SUMMARY OF INFLOW HYDROGRAPH
AND FLOOD ROUTING THROUGH
MITCHELL CLEAR WATER POND
FOR ½ 6-HOUR PMP STORM EVENT**

Starting Pool Elevation	=	664 ft, NAVD
Pipe Spillway Invert Elevation	=	664 ft, NAVD
Crest Elevation	=	675 ft, NAVD
Peak Inflow	=	71.44 cfs
Peak Outflow	=	44.76 cfs
Peak Storage	=	5.65 ac-ft
Maximum Impoundment Level During Storm	=	666.50 ft, NAVD
Minimum Freeboard During Storm	=	8.50 ft

```

1*****
*
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
*
* RUN DATE 12/21/2015 TIME 11:05:16 *
*
*****

```

```

*****
*
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*
*****

```

```

X X XXXXXXXX XXXXX X
X X X X X XX
X X X X X X
XXXXXXXX XXXX X XXXXX X
X X X X X X
X X X X X X
X X XXXXXXXX XXXXX XXX

```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE. THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
 NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
 DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
 KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM

LINE ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

*** FREE ***

```

1 ID *****
2 ID * Mitchell Clear Water Pond File: MCWP.inp *
3 ID * GA Project No. 01-269BA *
4 ID * Storm Routing for 1/2 6-Hour PMP *
5 ID * Crest Elevation = 675' *
6 ID *****
7 ID * Analyses by: Geo/Environmental Associates, Inc. *
8 ID * Knoxville, TN *
9 ID * Seth W. Frank P.E. *
10 ID * August 2014 *
11 ID *****
12 IT 15 0 0 300
13 IO 1
14 JR PRECIP 0.5
15 VS BASIN BASE IN IMP IMP IMP
16 VV 2.11 2.11 2.11 2.11 6.11 7.11
17 IN 15

18 KK BASIN
19 KM COMPUTE INFLOW HYDROGRAPH FOR MITCHELL CLEAR WATER POND USING SCS METHOD
20 PB 0
21 PI 0.258 0.347 0.420 0.478 0.520 0.546 0.624 0.804 0.790 0.939
22 PI 2.264 4.483 4.834 3.277 1.215 0.797 0.831 0.735 0.553 0.535
23 PI 0.501 0.451 0.386 0.305
24 BA 0.008
25 LU 0 0.05 45.5
26 UD 0.0

27 KK BASE
28 KM BASE FLOW
29 IN 360
30 QI 23.83 23.83 23.83

31 KK IN
32 KM COMBINE BASIN INFLOW AND BASEFLOW
33 KO 1
34 HC 2

35 KK IMP
36 KM ROUTE COMPUTED HYDROGRAPH AND BASE FLOW THROUGH CLEAR WATER POND
37 RS 1 ELEV 664
38 SA 2.18 2.24 2.30 2.38 2.45 2.56 2.67 2.79 2.91 3.03
39 SA 3.15 3.30
40 SQ 0 12.15 32.67 56.9 68.98 71.79 74.50 77.12 79.65 82.10
41 SQ 84.48 86.79
42 SE 664 665 666 667 668 669 670 671 672 673
43 SE 674 675
44 ZZ

```

```

1*****
*
* FLOOD HYDROGRAPH PACKAGE (HEC-1) *
* SEPTEMBER 1990 *
* VERSION 4.0 *
*
* RUN DATE 12/21/2015 TIME 11:05:16 *
*
*****

```

```

*****
*
* U.S. ARMY CORPS OF ENGINEERS *
* HYDROLOGIC ENGINEERING CENTER *
* 609 SECOND STREET *
* DAVIS, CALIFORNIA 95616 *
* (916) 756-1104 *
*
*****

```

```

*****
* Mitchell Clear Water Pond File: MCWP.inp *
* GA Project No. 01-269BA *
* Storm Routing for 1/2 6-Hour PMP *
* Crest Elevation = 675' *
*****
* Analyses by: Geo/Environmental Associates, Inc. *
* Knoxville, TN *
* Seth W. Frank P.E. *
* August 2014 *
*****

```

```

13 IO OUTPUT CONTROL VARIABLES
      IPRNT 1 PRINT CONTROL
      IPLOT 0 PLOT CONTROL
      QSCAL 0. HYDROGRAPH PLOT SCALE

IT HYDROGRAPH TIME DATA
      NMIN 15 MINUTES IN COMPUTATION INTERVAL
      IDATE 1 0 STARTING DATE
      ITIME 0000 STARTING TIME
      NQ 300 NUMBER OF HYDROGRAPH ORDINATES
      NDDATE 4 0 ENDING DATE
      NDTIME 0245 ENDING TIME
      ICENT 19 CENTURY MARK

      COMPUTATION INTERVAL .25 HOURS
      TOTAL TIME BASE 74.75 HOURS

```

```

ENGLISH UNITS
DRAINAGE AREA SQUARE MILES
PRECIPITATION DEPTH INCHES
LENGTH, ELEVATION FEET
FLOW CUBIC FEET PER SECOND
STORAGE VOLUME ACRE-FEET
SURFACE AREA ACRES
TEMPERATURE DEGREES FAHRENHEIT

```

USER-DEFINED OUTPUT SPECIFICATIONS

TABLE 1

VS	STATION	BASIN	BASE	IN	IMP	IMP	IMP				
VV	VARIABLE CODE	2.11	2.11	2.11	2.11	6.11	7.11	.00	.00	.00	.00

```

JP MULTI-PLAN OPTION
  NPLAN 1 NUMBER OF PLANS

```

```

JR MULTI-RATIO OPTION
  RATIOS OF PRECIPITATION
  .50

```

*** ** ** ** **

```

*****
*
* BASIN *
*
*****

```

COMPUTE INFLOW HYDROGRAPH FOR MITCHELL CLEAR WATER POND USING SCS METHOD

```

17 IN TIME DATA FOR INPUT TIME SERIES
      JXMIN 15 TIME INTERVAL IN MINUTES
      JXDATE 1 0 STARTING DATE
      JXTIME 0 STARTING TIME

```

SUBBASIN RUNOFF DATA

24 BA SUBBASIN CHARACTERISTICS
 TAREA .01 SUBBASIN AREA

PRECIPITATION DATA

20 PB STORM 26.89 BASIN TOTAL PRECIPITATION

21 PI INCREMENTAL PRECIPITATION PATTERN
 .26 .35 .42 .48 .52 .55 .62 .80 .79 .94
 2.26 4.48 4.83 3.28 1.22 .80 .83 .74 .55 .53
 .50 .45 .39 .31

25 LU UNIFORM LOSS RATE
 STRTL .00 INITIAL LOSS
 CNSTL .05 UNIFORM LOSS RATE
 RTIMP 45.50 PERCENT IMPERVIOUS AREA

26 UD SCS DIMENSIONLESS UNITGRAPH
 TLAG .00 LAG

W						
PEAK FLOW	TIME	MAXIMUM AVERAGE FLOW				
		6-HR	24-HR	72-HR	74.75-HR	
+ (CFS)	(HR)					
+ 45.	3.75	(CFS)	33.	26.	25.	24.
		(INCHES)	19.054	60.757	171.538	175.055
		(AC-FT)	16.	52.	146.	149.
PEAK STORAGE	TIME	MAXIMUM AVERAGE STORAGE				
		6-HR	24-HR	72-HR	74.75-HR	
+ (AC-FT)	(HR)					
+ 6.	3.75	4.	4.	4.	4.	
PEAK STAGE	TIME	MAXIMUM AVERAGE STAGE				
		6-HR	24-HR	72-HR	74.75-HR	
+ (FEET)	(HR)					
+ 666.50	3.75	665.99	665.68	665.60	665.58	
CUMULATIVE AREA =		.02 SQ MI				

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
 FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE MILES
 TIME TO PEAK IN HOURS

OPERATION	STATION	AREA	PLAN	RATIOS APPLIED TO PRECIPITATION	
				RATIO 1	
					.50
HYDROGRAPH AT					
+	BASIN	.01	1	FLOW	48.
				TIME	3.25
HYDROGRAPH AT					
+	BASE	.01	1	FLOW	24.
				TIME	.25
2 COMBINED AT					
+	IN	.02	1	FLOW	71.
				TIME	3.25
ROUTED TO					
+	IMP	.02	1	FLOW	45.
				TIME	3.75
				** PEAK STAGES IN FEET **	
			1	STAGE	666.50
				TIME	3.75

TABLE 1			STATION	BASIN	BASE	IN	IMP	IMP	IMP
			PLAN	FLOW	FLOW	FLOW	FLOW	STORAGE	STAGE
			RATIO	1	1	1	1	1	1
			.50	.50	.50	.50	.50	.50	.50
PER	DAY	MON	HRMN						
1	1		0000	.00	23.83	23.83	.00	.00	664.00
2	1		0015	1.87	23.83	25.70	2.66	.48	664.22
3	1		0030	3.08	23.83	26.91	5.20	.95	664.43
4	1		0045	3.94	23.83	27.77	7.58	1.38	664.62
5	1		0100	4.60	23.83	28.43	9.79	1.78	664.81
6	1		0115	5.08	23.83	28.91	11.82	2.15	664.97
7	1		0130	5.40	23.83	29.23	14.57	2.48	665.12
8	1		0145	6.08	23.83	29.91	17.13	2.76	665.24
9	1		0200	7.64	23.83	31.47	19.45	3.02	665.36
10	1		0215	7.96	23.83	31.79	21.53	3.25	665.46
11	1		0230	9.15	23.83	32.98	23.38	3.45	665.55
12	1		0245	19.64	23.83	43.47	25.92	3.73	665.67
13	1		0300	39.57	23.83	63.40	30.62	4.25	665.90
14	1		0315	47.61	23.83	71.44	37.46	4.94	666.20
15	1		0330	37.46	23.83	61.29	43.05	5.48	666.43
16	1		0345	18.64	23.83	42.47	44.76	5.65	666.50
17	1		0400	10.37	23.83	34.20	43.51	5.53	666.45
18	1		0415	8.74	23.83	32.57	41.56	5.34	666.37
19	1		0430	7.72	23.83	31.55	39.72	5.16	666.29
20	1		0445	6.10	23.83	29.93	37.99	4.99	666.22
21	1		0500	5.53	23.83	29.36	36.37	4.84	666.15
22	1		0515	5.15	23.83	28.98	34.98	4.70	666.10
23	1		0530	4.67	23.83	28.50	33.77	4.59	666.05
24	1		0545	4.05	23.83	27.88	32.69	4.48	666.00
25	1		0600	3.26	23.83	27.09	31.80	4.38	665.96
26	1		0615	.82	23.83	24.65	30.79	4.27	665.91
27	1		0630	.15	23.83	23.98	29.68	4.15	665.85
28	1		0645	.02	23.83	23.85	28.70	4.04	665.81
29	1		0700	.00	23.83	23.83	27.87	3.95	665.77
30	1		0715	.00	23.83	23.83	27.18	3.87	665.73
31	1		0730	.00	23.83	23.83	26.61	3.81	665.70
32	1		0745	.00	23.83	23.83	26.13	3.76	665.68
33	1		0800	.00	23.83	23.83	25.74	3.71	665.66
34	1		0815	.00	23.83	23.83	25.41	3.68	665.65
35	1		0830	.00	23.83	23.83	25.14	3.65	665.63
36	1		0845	.00	23.83	23.83	24.92	3.62	665.62
37	1		0900	.00	23.83	23.83	24.73	3.60	665.61
38	1		0915	.00	23.83	23.83	24.58	3.58	665.61
39	1		0930	.00	23.83	23.83	24.45	3.57	665.60
40	1		0945	.00	23.83	23.83	24.34	3.56	665.59
41	1		1000	.00	23.83	23.83	24.26	3.55	665.59
42	1		1015	.00	23.83	23.83	24.18	3.54	665.59
43	1		1030	.00	23.83	23.83	24.12	3.53	665.58
44	1		1045	.00	23.83	23.83	24.07	3.53	665.58
45	1		1100	.00	23.83	23.83	24.03	3.52	665.58
46	1		1115	.00	23.83	23.83	24.00	3.52	665.58
47	1		1130	.00	23.83	23.83	23.97	3.52	665.58
48	1		1145	.00	23.83	23.83	23.94	3.51	665.57
49	1		1200	.00	23.83	23.83	23.93	3.51	665.57
50	1		1215	.00	23.83	23.83	23.91	3.51	665.57

TABLE 1 (CONT.)	STATION PLAN RATIO	BASIN FLOW	BASE FLOW	IN FLOW	IMP FLOW	IMP STORAGE	IMP STAGE
		1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER	DAY	MON	HRMN						
51	1		1230	.00	23.83	23.83	23.90	3.51	665.57
52	1		1245	.00	23.83	23.83	23.88	3.51	665.57
53	1		1300	.00	23.83	23.83	23.88	3.51	665.57
54	1		1315	.00	23.83	23.83	23.87	3.51	665.57
55	1		1330	.00	23.83	23.83	23.86	3.51	665.57
56	1		1345	.00	23.83	23.83	23.86	3.50	665.57
57	1		1400	.00	23.83	23.83	23.85	3.50	665.57
58	1		1415	.00	23.83	23.83	23.85	3.50	665.57
59	1		1430	.00	23.83	23.83	23.84	3.50	665.57
60	1		1445	.00	23.83	23.83	23.84	3.50	665.57
61	1		1500	.00	23.83	23.83	23.84	3.50	665.57
62	1		1515	.00	23.83	23.83	23.84	3.50	665.57
63	1		1530	.00	23.83	23.83	23.84	3.50	665.57
64	1		1545	.00	23.83	23.83	23.84	3.50	665.57
65	1		1600	.00	23.83	23.83	23.83	3.50	665.57
66	1		1615	.00	23.83	23.83	23.83	3.50	665.57
67	1		1630	.00	23.83	23.83	23.83	3.50	665.57
68	1		1645	.00	23.83	23.83	23.83	3.50	665.57
69	1		1700	.00	23.83	23.83	23.83	3.50	665.57
70	1		1715	.00	23.83	23.83	23.83	3.50	665.57
71	1		1730	.00	23.83	23.83	23.83	3.50	665.57
72	1		1745	.00	23.83	23.83	23.83	3.50	665.57
73	1		1800	.00	23.83	23.83	23.83	3.50	665.57
74	1		1815	.00	23.83	23.83	23.83	3.50	665.57
75	1		1830	.00	23.83	23.83	23.83	3.50	665.57
76	1		1845	.00	23.83	23.83	23.83	3.50	665.57
77	1		1900	.00	23.83	23.83	23.83	3.50	665.57
78	1		1915	.00	23.83	23.83	23.83	3.50	665.57
79	1		1930	.00	23.83	23.83	23.83	3.50	665.57
80	1		1945	.00	23.83	23.83	23.83	3.50	665.57
81	1		2000	.00	23.83	23.83	23.83	3.50	665.57
82	1		2015	.00	23.83	23.83	23.83	3.50	665.57
83	1		2030	.00	23.83	23.83	23.83	3.50	665.57
84	1		2045	.00	23.83	23.83	23.83	3.50	665.57
85	1		2100	.00	23.83	23.83	23.83	3.50	665.57
86	1		2115	.00	23.83	23.83	23.83	3.50	665.57
87	1		2130	.00	23.83	23.83	23.83	3.50	665.57
88	1		2145	.00	23.83	23.83	23.83	3.50	665.57
89	1		2200	.00	23.83	23.83	23.83	3.50	665.57
90	1		2215	.00	23.83	23.83	23.83	3.50	665.57
91	1		2230	.00	23.83	23.83	23.83	3.50	665.57
92	1		2245	.00	23.83	23.83	23.83	3.50	665.57
93	1		2300	.00	23.83	23.83	23.83	3.50	665.57
94	1		2315	.00	23.83	23.83	23.83	3.50	665.57
95	1		2330	.00	23.83	23.83	23.83	3.50	665.57
96	1		2345	.00	23.83	23.83	23.83	3.50	665.57
97	2		0000	.00	23.83	23.83	23.83	3.50	665.57
98	2		0015	.00	23.83	23.83	23.83	3.50	665.57
99	2		0030	.00	23.83	23.83	23.83	3.50	665.57
100	2		0045	.00	23.83	23.83	23.83	3.50	665.57

TABLE 1 (CONT.)	STATION PLAN RATIO	BASIN FLOW 1 .50	BASE FLOW 1 .50	IN FLOW 1 .50	IMP FLOW 1 .50	IMP STORAGE 1 .50	IMP STAGE 1 .50
--------------------	--------------------------	---------------------------	--------------------------	------------------------	-------------------------	----------------------------	--------------------------

PER DAY MON HRMN

101	2	0100	.00	23.83	23.83	23.83	3.50	665.57
102	2	0115	.00	23.83	23.83	23.83	3.50	665.57
103	2	0130	.00	23.83	23.83	23.83	3.50	665.57
104	2	0145	.00	23.83	23.83	23.83	3.50	665.57
105	2	0200	.00	23.83	23.83	23.83	3.50	665.57
106	2	0215	.00	23.83	23.83	23.83	3.50	665.57
107	2	0230	.00	23.83	23.83	23.83	3.50	665.57
108	2	0245	.00	23.83	23.83	23.83	3.50	665.57
109	2	0300	.00	23.83	23.83	23.83	3.50	665.57
110	2	0315	.00	23.83	23.83	23.83	3.50	665.57
111	2	0330	.00	23.83	23.83	23.83	3.50	665.57
112	2	0345	.00	23.83	23.83	23.83	3.50	665.57
113	2	0400	.00	23.83	23.83	23.83	3.50	665.57
114	2	0415	.00	23.83	23.83	23.83	3.50	665.57
115	2	0430	.00	23.83	23.83	23.83	3.50	665.57
116	2	0445	.00	23.83	23.83	23.83	3.50	665.57
117	2	0500	.00	23.83	23.83	23.83	3.50	665.57
118	2	0515	.00	23.83	23.83	23.83	3.50	665.57
119	2	0530	.00	23.83	23.83	23.83	3.50	665.57
120	2	0545	.00	23.83	23.83	23.83	3.50	665.57
121	2	0600	.00	23.83	23.83	23.83	3.50	665.57
122	2	0615	.00	23.83	23.83	23.83	3.50	665.57
123	2	0630	.00	23.83	23.83	23.83	3.50	665.57
124	2	0645	.00	23.83	23.83	23.83	3.50	665.57
125	2	0700	.00	23.83	23.83	23.83	3.50	665.57
126	2	0715	.00	23.83	23.83	23.83	3.50	665.57
127	2	0730	.00	23.83	23.83	23.83	3.50	665.57
128	2	0745	.00	23.83	23.83	23.83	3.50	665.57
129	2	0800	.00	23.83	23.83	23.83	3.50	665.57
130	2	0815	.00	23.83	23.83	23.83	3.50	665.57
131	2	0830	.00	23.83	23.83	23.83	3.50	665.57
132	2	0845	.00	23.83	23.83	23.83	3.50	665.57
133	2	0900	.00	23.83	23.83	23.83	3.50	665.57
134	2	0915	.00	23.83	23.83	23.83	3.50	665.57
135	2	0930	.00	23.83	23.83	23.83	3.50	665.57
136	2	0945	.00	23.83	23.83	23.83	3.50	665.57
137	2	1000	.00	23.83	23.83	23.83	3.50	665.57
138	2	1015	.00	23.83	23.83	23.83	3.50	665.57
139	2	1030	.00	23.83	23.83	23.83	3.50	665.57
140	2	1045	.00	23.83	23.83	23.83	3.50	665.57
141	2	1100	.00	23.83	23.83	23.83	3.50	665.57
142	2	1115	.00	23.83	23.83	23.83	3.50	665.57
143	2	1130	.00	23.83	23.83	23.83	3.50	665.57
144	2	1145	.00	23.83	23.83	23.83	3.50	665.57
145	2	1200	.00	23.83	23.83	23.83	3.50	665.57
146	2	1215	.00	23.83	23.83	23.83	3.50	665.57
147	2	1230	.00	23.83	23.83	23.83	3.50	665.57
148	2	1245	.00	23.83	23.83	23.83	3.50	665.57
149	2	1300	.00	23.83	23.83	23.83	3.50	665.57
150	2	1315	.00	23.83	23.83	23.83	3.50	665.57

TABLE 1 (CONT.)	STATION PLAN RATIO	BASIN FLOW	BASE FLOW	IN FLOW	IMP FLOW	IMP STORAGE	IMP STAGE
		1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER	DAY	MON	HRMN						
151	2		1330	.00	23.83	23.83	23.83	3.50	665.57
152	2		1345	.00	23.83	23.83	23.83	3.50	665.57
153	2		1400	.00	23.83	23.83	23.83	3.50	665.57
154	2		1415	.00	23.83	23.83	23.83	3.50	665.57
155	2		1430	.00	23.83	23.83	23.83	3.50	665.57
156	2		1445	.00	23.83	23.83	23.83	3.50	665.57
157	2		1500	.00	23.83	23.83	23.83	3.50	665.57
158	2		1515	.00	23.83	23.83	23.83	3.50	665.57
159	2		1530	.00	23.83	23.83	23.83	3.50	665.57
160	2		1545	.00	23.83	23.83	23.83	3.50	665.57
161	2		1600	.00	23.83	23.83	23.83	3.50	665.57
162	2		1615	.00	23.83	23.83	23.83	3.50	665.57
163	2		1630	.00	23.83	23.83	23.83	3.50	665.57
164	2		1645	.00	23.83	23.83	23.83	3.50	665.57
165	2		1700	.00	23.83	23.83	23.83	3.50	665.57
166	2		1715	.00	23.83	23.83	23.83	3.50	665.57
167	2		1730	.00	23.83	23.83	23.83	3.50	665.57
168	2		1745	.00	23.83	23.83	23.83	3.50	665.57
169	2		1800	.00	23.83	23.83	23.83	3.50	665.57
170	2		1815	.00	23.83	23.83	23.83	3.50	665.57
171	2		1830	.00	23.83	23.83	23.83	3.50	665.57
172	2		1845	.00	23.83	23.83	23.83	3.50	665.57
173	2		1900	.00	23.83	23.83	23.83	3.50	665.57
174	2		1915	.00	23.83	23.83	23.83	3.50	665.57
175	2		1930	.00	23.83	23.83	23.83	3.50	665.57
176	2		1945	.00	23.83	23.83	23.83	3.50	665.57
177	2		2000	.00	23.83	23.83	23.83	3.50	665.57
178	2		2015	.00	23.83	23.83	23.83	3.50	665.57
179	2		2030	.00	23.83	23.83	23.83	3.50	665.57
180	2		2045	.00	23.83	23.83	23.83	3.50	665.57
181	2		2100	.00	23.83	23.83	23.83	3.50	665.57
182	2		2115	.00	23.83	23.83	23.83	3.50	665.57
183	2		2130	.00	23.83	23.83	23.83	3.50	665.57
184	2		2145	.00	23.83	23.83	23.83	3.50	665.57
185	2		2200	.00	23.83	23.83	23.83	3.50	665.57
186	2		2215	.00	23.83	23.83	23.83	3.50	665.57
187	2		2230	.00	23.83	23.83	23.83	3.50	665.57
188	2		2245	.00	23.83	23.83	23.83	3.50	665.57
189	2		2300	.00	23.83	23.83	23.83	3.50	665.57
190	2		2315	.00	23.83	23.83	23.83	3.50	665.57
191	2		2330	.00	23.83	23.83	23.83	3.50	665.57
192	2		2345	.00	23.83	23.83	23.83	3.50	665.57
193	3		0000	.00	23.83	23.83	23.83	3.50	665.57
194	3		0015	.00	23.83	23.83	23.83	3.50	665.57
195	3		0030	.00	23.83	23.83	23.83	3.50	665.57
196	3		0045	.00	23.83	23.83	23.83	3.50	665.57
197	3		0100	.00	23.83	23.83	23.83	3.50	665.57
198	3		0115	.00	23.83	23.83	23.83	3.50	665.57
199	3		0130	.00	23.83	23.83	23.83	3.50	665.57
200	3		0145	.00	23.83	23.83	23.83	3.50	665.57

TABLE 1 (CONT.)	STATION PLAN RATIO	BASIN FLOW	BASE FLOW	IN FLOW	IMP FLOW	IMP STORAGE	IMP STAGE
		1	1	1	1	1	1
		.50	.50	.50	.50	.50	.50

PER	DAY	MON	HRMN						
201	3		0200	.00	23.83	23.83	23.83	3.50	665.57
202	3		0215	.00	23.83	23.83	23.83	3.50	665.57
203	3		0230	.00	23.83	23.83	23.83	3.50	665.57
204	3		0245	.00	23.83	23.83	23.83	3.50	665.57
205	3		0300	.00	23.83	23.83	23.83	3.50	665.57
206	3		0315	.00	23.83	23.83	23.83	3.50	665.57
207	3		0330	.00	23.83	23.83	23.83	3.50	665.57
208	3		0345	.00	23.83	23.83	23.83	3.50	665.57
209	3		0400	.00	23.83	23.83	23.83	3.50	665.57
210	3		0415	.00	23.83	23.83	23.83	3.50	665.57
211	3		0430	.00	23.83	23.83	23.83	3.50	665.57
212	3		0445	.00	23.83	23.83	23.83	3.50	665.57
213	3		0500	.00	23.83	23.83	23.83	3.50	665.57
214	3		0515	.00	23.83	23.83	23.83	3.50	665.57
215	3		0530	.00	23.83	23.83	23.83	3.50	665.57
216	3		0545	.00	23.83	23.83	23.83	3.50	665.57
217	3		0600	.00	23.83	23.83	23.83	3.50	665.57
218	3		0615	.00	23.83	23.83	23.83	3.50	665.57
219	3		0630	.00	23.83	23.83	23.83	3.50	665.57
220	3		0645	.00	23.83	23.83	23.83	3.50	665.57
221	3		0700	.00	23.83	23.83	23.83	3.50	665.57
222	3		0715	.00	23.83	23.83	23.83	3.50	665.57
223	3		0730	.00	23.83	23.83	23.83	3.50	665.57
224	3		0745	.00	23.83	23.83	23.83	3.50	665.57
225	3		0800	.00	23.83	23.83	23.83	3.50	665.57
226	3		0815	.00	23.83	23.83	23.83	3.50	665.57
227	3		0830	.00	23.83	23.83	23.83	3.50	665.57
228	3		0845	.00	23.83	23.83	23.83	3.50	665.57
229	3		0900	.00	23.83	23.83	23.83	3.50	665.57
230	3		0915	.00	23.83	23.83	23.83	3.50	665.57
231	3		0930	.00	23.83	23.83	23.83	3.50	665.57
232	3		0945	.00	23.83	23.83	23.83	3.50	665.57
233	3		1000	.00	23.83	23.83	23.83	3.50	665.57
234	3		1015	.00	23.83	23.83	23.83	3.50	665.57
235	3		1030	.00	23.83	23.83	23.83	3.50	665.57
236	3		1045	.00	23.83	23.83	23.83	3.50	665.57
237	3		1100	.00	23.83	23.83	23.83	3.50	665.57
238	3		1115	.00	23.83	23.83	23.83	3.50	665.57
239	3		1130	.00	23.83	23.83	23.83	3.50	665.57
240	3		1145	.00	23.83	23.83	23.83	3.50	665.57
241	3		1200	.00	23.83	23.83	23.83	3.50	665.57
242	3		1215	.00	23.83	23.83	23.83	3.50	665.57
243	3		1230	.00	23.83	23.83	23.83	3.50	665.57
244	3		1245	.00	23.83	23.83	23.83	3.50	665.57
245	3		1300	.00	23.83	23.83	23.83	3.50	665.57
246	3		1315	.00	23.83	23.83	23.83	3.50	665.57
247	3		1330	.00	23.83	23.83	23.83	3.50	665.57
248	3		1345	.00	23.83	23.83	23.83	3.50	665.57
249	3		1400	.00	23.83	23.83	23.83	3.50	665.57
250	3		1415	.00	23.83	23.83	23.83	3.50	665.57

TABLE 1 (CONT.)		STATION	BASIN	BASE	IN	IMP	IMP	IMP
PER	DAY	MON	HRMN	FLOW	FLOW	FLOW	STORAGE	STAGE
				1	1	1	1	1
				.50	.50	.50	.50	.50
251	3	1430	.00	23.83	23.83	23.83	3.50	665.57
252	3	1445	.00	23.83	23.83	23.83	3.50	665.57
253	3	1500	.00	23.83	23.83	23.83	3.50	665.57
254	3	1515	.00	23.83	23.83	23.83	3.50	665.57
255	3	1530	.00	23.83	23.83	23.83	3.50	665.57
256	3	1545	.00	23.83	23.83	23.83	3.50	665.57
257	3	1600	.00	23.83	23.83	23.83	3.50	665.57
258	3	1615	.00	23.83	23.83	23.83	3.50	665.57
259	3	1630	.00	23.83	23.83	23.83	3.50	665.57
260	3	1645	.00	23.83	23.83	23.83	3.50	665.57
261	3	1700	.00	23.83	23.83	23.83	3.50	665.57
262	3	1715	.00	23.83	23.83	23.83	3.50	665.57
263	3	1730	.00	23.83	23.83	23.83	3.50	665.57
264	3	1745	.00	23.83	23.83	23.83	3.50	665.57
265	3	1800	.00	23.83	23.83	23.83	3.50	665.57
266	3	1815	.00	23.83	23.83	23.83	3.50	665.57
267	3	1830	.00	23.83	23.83	23.83	3.50	665.57
268	3	1845	.00	23.83	23.83	23.83	3.50	665.57
269	3	1900	.00	23.83	23.83	23.83	3.50	665.57
270	3	1915	.00	23.83	23.83	23.83	3.50	665.57
271	3	1930	.00	23.83	23.83	23.83	3.50	665.57
272	3	1945	.00	23.83	23.83	23.83	3.50	665.57
273	3	2000	.00	23.83	23.83	23.83	3.50	665.57
274	3	2015	.00	23.83	23.83	23.83	3.50	665.57
275	3	2030	.00	23.83	23.83	23.83	3.50	665.57
276	3	2045	.00	23.83	23.83	23.83	3.50	665.57
277	3	2100	.00	23.83	23.83	23.83	3.50	665.57
278	3	2115	.00	23.83	23.83	23.83	3.50	665.57
279	3	2130	.00	23.83	23.83	23.83	3.50	665.57
280	3	2145	.00	23.83	23.83	23.83	3.50	665.57
281	3	2200	.00	23.83	23.83	23.83	3.50	665.57
282	3	2215	.00	23.83	23.83	23.83	3.50	665.57
283	3	2230	.00	23.83	23.83	23.83	3.50	665.57
284	3	2245	.00	23.83	23.83	23.83	3.50	665.57
285	3	2300	.00	23.83	23.83	23.83	3.50	665.57
286	3	2315	.00	23.83	23.83	23.83	3.50	665.57
287	3	2330	.00	23.83	23.83	23.83	3.50	665.57
288	3	2345	.00	23.83	23.83	23.83	3.50	665.57
289	4	0000	.00	23.83	23.83	23.83	3.50	665.57
290	4	0015	.00	23.83	23.83	23.83	3.50	665.57
291	4	0030	.00	23.83	23.83	23.83	3.50	665.57
292	4	0045	.00	23.83	23.83	23.83	3.50	665.57
293	4	0100	.00	23.83	23.83	23.83	3.50	665.57
294	4	0115	.00	23.83	23.83	23.83	3.50	665.57
295	4	0130	.00	23.83	23.83	23.83	3.50	665.57
296	4	0145	.00	23.83	23.83	23.83	3.50	665.57
297	4	0200	.00	23.83	23.83	23.83	3.50	665.57
298	4	0215	.00	23.83	23.83	23.83	3.50	665.57
299	4	0230	.00	23.83	23.83	23.83	3.50	665.57
300	4	0245	.00	23.83	23.83	23.83	3.50	665.57
		MAX	47.61	23.83	71.44	44.76	5.65	666.50
		MIN	.00	23.83	23.83	.00	.00	664.00
		AVE	.91	23.83	24.74	24.14	3.52	665.58

*** NORMAL END OF HEC-1 ***