

History of Construction

40 CFR 257.73(c)

Ash Pond

Cabin Creek Site

Chelyan, West Virginia

February 2026

Prepared for: Appalachian Power Company

Prepared by: American Electric Power Service Corporation

1 Riverside Plaza

Columbus, OH 43215



Cabin Creek Ash Pond

History of Construction

PREPARED BY Dan Murphy Digitally signed by Dan Murphy
DN: cn=Dan Murphy, c=US,
email=dsmurphy1@aep.com
Date: 2026.02.03 08:39:22 -05'00' DATE _____


Dan Murphy, P.E.

REVIEWED BY Blake Arthur, PE Digitally signed by Blake Arthur,
PE
DN: cn=Blake Arthur, PE, c=US,
email=barthur@aep.com
Date: 2026.02.03 09:26:32 -05'00' DATE _____

Blake Arthur, P.E.

APPROVED BY David Anthony Miller DATE 02.02.2026

David A. Miller, P.E.
Director – Ash Management Services



I certify to the best of my knowledge, information, and belief the information contained in this report meets the requirements of 40 CFR § 257.73(c).

Table of CONTENTS

1.0 OBJECTIVE.....	4
2.0 DESCRIPTION OF CCR THE IMPOUNDMENT.....	4
3.0 SUMMARY OF OWNERSHIP 275.73(c)(1)(i).....	5
4.0 LOCATION OF THE CCR UNIT 275.73 (c)(1)(ii).....	5
5.0 STATEMENT OF PURPOSE 275.73 (c)(1)(iii).....	5
6.0 NAME AND SIZE OF WATERSHED THE CCR UNIT IS LOCATED 275.73 (c)(1)(iv).....	5
7.0 DESCRIPTION OF THE FOUNDATION AND ABUTMENT MATERIALS 275.73(c)(1)(v).....	6
8.0 DESCRIPTION OF EACH CONSTRUCTED ZONE OR STAGE OF THE CCR UNIT 275.73 (c)(1)(vi).....	6
9.0 ENGINEERING STRUCTURES AND APPURTENANCES, 275.73 (c)(1)(vii).....	7
10.0 SUMMARY OF POOL SURFACE ELEVATIONS, AND MAXIMUM DEPTH.....	7
OF CCR, 275.73 (c)(1)(vii).....	7
11.0 FEATURES THAT COULD ADVERSELY AFFECT OPERATION DUE TO MALFUNCTION OR MIS-OPERATION (275.73 (c)(1)(vii)).....	7
12.0 DESCRIPTION OF THE TYPE, PURPOSE AND LOCATION OF EXISTING INSTRUMENTATION 275.73 (c)(1)(viii).....	8
13.0 AREA – CAPACITY CURVES FOR THE CCR UNIT 275.73 (c)(1)(ix).....	8
14.0 275.73 (c)(1)(x) DESCRIPTION OF EACH SPILLWAY AND DIVERSION.....	9
15.0 SUMMARY CONSTRUCTION SPECIFICATIONS AND PROVISIONS FOR SURVEILLANCE, MAINTENANCE AND REPAIR 275.73 (c)(1)(xi).....	9
16.0 RECORD OR KNOWLEDGE OF STRUCTURAL INSTABILITY 275.73 (c)(1)(xii).....	9

Attachments

- Attachment A – Location Map
- Attachment B – Geotechnical Data Report
- Attachment C – Design Drawings

1.0 OBJECTIVE

The “Hazardous and Solid Waste Management System: Disposal of Coal Combustion Residuals From Electric Utilities; Legacy CCR Surface Impoundments”, 89 Fed. Reg. 38950 (May 8, 2024) (amending 40 C.F.R. §257) requires owners and operators of facilities with a legacy coal combustion residual (CCR) surface impoundment to prepare a history of construction document for each legacy CCR surface impoundment at the facility.

The Ash Pond at the Cabin Creek Site is subjected to this rule.

2.0 DESCRIPTION OF CCR THE IMPOUNDMENT

The Cabin Creek site is located near Chelyan, West Virginia, near the intersection of MacCorkle Ave SE and Cabin Creek Rd., Cabin Creek, WV 25035. The latitude/longitude of the facility is: 38°11'52"N / 81°29' 6" W. The Ash Pond is approximately 19 acres. The Cabin Creek Power Plant was placed in service in 1914, stopped generating electricity in 1977, retired in 1981 and the site was razed in 1985-1987. The Ash Pond was constructed sometime around 1956.

The Ash Pond is located near the Kanawha River on the west side of the plant property. The Ash Pond was located on the west side of Cabin Creek, and the Power Plant was located on the East side of Cabin Creek.

According to the 1956 U.S. Army Corps Permit application, the ash pond was constructed by building a dike around Cabin Creek Island and filling the former river backchannel with dredged river sediments. To offset the loss of channel volume, approximately 200,000 cubic yards of compensatory dredging was completed adjacent to the Cabin Creek Island within the main river channel. The dike included a 650-foot-long southwest section reinforced with 35-foot-deep wood piling and rockfill, and a similarly long northeast section protecting the shoreline with riprap armor. The exterior slope of the dike was designed at 2H:1V and the interior slope was designed at 1.5H:1V. The 2H:1V slope extends below the navigational pool of the Marmet Lock and Dam (590 ft-msl) to an elevation of 575 ft-msl, 15 below the normal pool.

The former discharge structure is a pipe and riser type structure located at the western end of the Ash Pond. The riser structure is made of concrete and has grooves for receiving stop logs for controlling the pool level when the pond was active. The outlet pipe is a 24-inch-diameter reinforced concrete pipe. The discharge structure no longer functions, and the facility no longer impounds water.

3.0 SUMMARY OF OWNERSHIP 275.73(c)(1)(i)

[The name and address of the person(s) owning or operating the CCR unit: the name associated with the CCR unit: and the identification number of the CCR unit if one has been assigned by the state.]

The name associated with the CCR unit is Ash Pond. Appalachian Power Company is the owner of the Ash Pond at the Cabin Creek Site. There are no known state identification numbers assigned to the facility.

Appalachian Power Company
Attn: Gary Spitznogle
1 Riverside Plaza
Columbus, OH 43215
Phone: 614-716-1774
Email: aepccrhelp@aep.com

4.0 LOCATION OF THE CCR UNIT 275.73 (c)(1)(ii)

[The location of the CCR unit identified on the most recent U.S. Geological Survey (USGS) 7 ½ minute or 15-minute topographic quadrangle map, or a topographic map of equivalent scale if a USGS map is not available.]

A location map is included in Attachment A.

5.0 STATEMENT OF PURPOSE 275.73 (c)(1)(iii)

[A statement of the purpose for which the CCR unit is being used.]

When the Cabin Creek Plant was operational, the Ash Pond was a surface impoundment for settling and storing coal ash. The decant water from the Ash Pond flows into the Kanawha River.

6.0 NAME AND SIZE OF WATERSHED THE CCR UNIT IS LOCATED 275.73 (c)(1)(iv)

[The name and size in acres of the watershed within which the CCR unit is located.]

The Ash Pond is configured such that there are diked embankments on all sides which direct stormwater away from the impoundment and limit runoff to that which falls directly on the surface impoundment. Therefore, the areas surrounding the impoundments do not contribute to any runoff. The watershed for the ponds is equal to the surface areas of the ponds and is approximately 20 acres.

The Ash Pond is located within the Region 5 - Ohio Region Watershed and is part of the subgroup Hydrologic Unit Code = 050500060403 Fields Creek- Kanawha River watershed area.

7.0 DESCRIPTION OF THE FOUNDATION AND ABUTMENT MATERIALS

275.73(c)(1)(v)

[A description of the physical and engineering properties of the foundation and abutment materials on which the CCR unit is located.]

This section is a summary of Geotechnical Data Report included as Attachment B.

The Cabin Creek Ash Pond site lies centrally within the Alleghany Plateau of West Virginia. The terrain in the area is characterized by numerous steep hills and valleys, with the ridges consistently near elevation 1400 ft-msl and the valley bottoms nearly elevation 600 to 800 ft-msl.

The Cabin Creek Ash Pond is located adjacent to the Kanawha River within an area underlain by unconfined alluvial deposits. These deposits primary consist of the silty sands, gravels and clayey silts formed by fluvial processes.

The alluvium consists primarily of silt, silty clay, and lean clays with varying amounts of sand, gravel, and mica.

Field SPT N-values recorded in the alluvial soils ranged from Weight of Hammer (WOH) over 18 inches to 17 blows per foot, indicating very soft to very stiff consistency. Laboratory tests conducted on the alluvial soils indicate in situ moisture contents ranging from 19.7% to 29%. Atterberg Limits testing performed on samples of alluvial soils resulted in Liquid Limits ranging from NP (Non-plastic) to 23% and Plasticity Indices ranging from NP to 5%. Gradation testing performed on these samples showed 19.8% to 67.8% material passing the No. 200 sieve.

8.0 DESCRIPTION OF EACH CONSTRUCTED ZONE OR STAGE OF THE CCR UNIT 275.73 (c)(1)(vi)

[A statement of the type, size, range, and physical and engineering properties of the materials used in constructing each zone or stage of the CCR unit; and the approximate dates of construction of each successive stage of construction of the CCR unit.]

Based on readily available records, the dike was constructed in three stages. The first stage involved the construction of a dike on the east, west and north sides of the ash pond. The elevation of the crest for the first stage is approximately 605 ft-msl. Based on available documentation, this stage was constructed prior to 1957. The first stage of the embankment was constructed from dredged alluvial sediments, commonly consisting of SP-SM soils with SPT blow counts ranging from 2 to 8 blows per foot, indicating consistency from very loose to loose.

When the surface of the ash inside the pond reached elevation 605 ft-msl, a southern leg of the dike would have been constructed. This represents the second stage of construction, and the top of dike elevation is identified as 613 ft-msl. Based on available documentation, this stage was constructed prior to 1963. The

third and final stage of embankment construction raised the crest of the dam to elevation 620 ft-msl. The second and third raisings were constructed with soil and bottom ash.

Prior to 1971, a splitter dike traveling in the east/west direction was constructed to create two cells within the ash pond.

9.0 ENGINEERING STRUCTURES AND APPURTENANCES, 275.73 (c)(1)(vii)

[At a scale that details engineering structures and appurtenances relevant to the design, construction, operation, and maintenance of the CCR unit, detailed dimensional drawings of the CCR unit, including a plan view and cross sections of the length and width of the CCR unit, showing all zones, foundation improvements, drainage provisions, spillways, diversion ditches, outlets, instrument locations, and slope protection...]

AEP performed an extensive review to locate historical files, drawings, and other information for the Cabin Creek Ash Pond. All readily available drawings are included in Attachment C.

10.0 SUMMARY OF POOL SURFACE ELEVATIONS, AND MAXIMUM DEPTH OF CCR, 275.73 (c)(1)(vii)

[...in addition to the normal operating pool surface elevation and the maximum pool elevation following peak discharge from the inflow design flood, the expected maximum depth of CCR within the CCR surface impoundment.]

The Cabin Creek Ash Pond has CCR material roughly 30 feet deep and no longer receives CCR. The Cabin Creek Ash Pond no longer has ponded water, therefore the pool elevation sections are not applicable.

11.0 FEATURES THAT COULD ADVERSELY AFFECT OPERATION DUE TO MALFUNCTION OR MIS-OPERATION (275.73 (c)(1)(vii))

[...and any identifiable natural or manmade features that could adversely affect operations of the CCR unit due to malfunction or mis-operation]

There is a 24-inch-diameter concrete pipe for stormwater conveyance located underneath the western edge of the Cabin Creek Ash Pond. This pipe is roughly 30 feet deep and outlets into the Kanawha River near the northwestern corner of the Cabin Creek Ash Pond. The pipe was constructed to provide a new outlet for drainage structures from the neighboring village that formerly daylighted into the now filled in backchannel of Cabin Creek Island.

There is 24-inch-diameter former sewer pipe that is located underneath the eastern edge of the Cabin Creek Ash Pond. The pipe is roughly 30 feet deep and outlets into a ditch that flows into the Kanawha River along the eastern edge of the Ash Pond. The pipe was extended to provide a new outlet for a sewer system from the neighboring village that formerly daylighted into the now filled in backchannel of Cabin Creek Island.

12.0 DESCRIPTION OF THE TYPE, PURPOSE, AND LOCATION OF EXISTING INSTRUMENTATION 275.73 (c)(1)(VIII)


[A description of the type, purpose, and location of existing instrumentation.]

The Cabin Creek Ash Pond does not have any instrumentation.

13.0 AREA – CAPACITY CURVES FOR THE CCR UNIT 275.73 (c)(1)(IX)

[Area-capacity curves for the CCR unit.]

The area capacity curve shown below projects the interior toe of slope based on a 1.75H:1V slope. The assumed toe is located 50 feet to the interior of the pond from the edge of the crest as measured in the drawings in Attachment C. These measurements were also confirmed from observations of historical aerial photographs.



14.0 275.73 (c)(1)(x) DESCRIPTION OF EACH SPILLWAY AND DIVERSION

[A description of each spillway and diversion design features and capacities and calculations used in their determination.]

The former spillway of the Cabin Creek Ash Pond consists of stop-log riser structure and outlet pipe in the northwestern corner of the site. The Cabin Creek Ash Pond no longer has ponded water, the spillway no longer functions, and this section is not applicable.

15.0 SUMMARY CONSTRUCTION SPECIFICATIONS AND PROVISIONS FOR SURVEILLANCE, MAINTENANCE AND REPAIR 275.73 (c)(1)(xi)

[The construction specifications and provisions for surveillance, maintenance, and repair of the CCR unit.]

There are no readily available portions of the original construction specifications.

As required by the CCR rules, the Cabin Creek Ash Pond is inspected at least every 7 days by a qualified person. Also, as a requirement of the CCR rules the impoundment is also inspected annually by a qualified professional engineer.

If repairs are found to be necessary during any inspection they will be completed as soon as feasible.

16.0 RECORD OR KNOWLEDGE OF STRUCTURAL INSTABILITY 275.73 (c)(1)(xii)

[Any record or knowledge of the structural instability of the CCR unit.]

To date, there has been no known record or knowledge of the structural instability of the CCR unit.


ATTACHMENT A

LOCATION MAP

Legend

Legacy CCR Surface Impoundment

AEP Property Boundary



Location Map
Cabin Creek Ash Pond
By: Dan Murphy
Date: December 23, 2025



0 250 500 Feet

ATTACHMENT B

GEOTECHNICAL DATA REPORT



REPORT

Geotechnical Data Report

Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, West Virginia

Submitted to:

Ms. Jane Petrie

American Electric Power Company, Inc.
Project Manager
1 Riverside Plaza,
Columbus, OH 43215

Submitted by:

WSP USA Inc.

3348 Peachtree Road NE, Suite 1100, Atlanta, Georgia, 30326

+1 404 237 2115

US0041868.3924

January 28, 2026



Distribution List

Dan Murphy (dsmurphy1@aep.com)

Benjamin J Hackett (bjhackett@aep.com)

Table of Contents

1 INTRODUCTION1

2 SITE VISIT.....1

3 FIELD EXPLORATIONS AND LABORATORY TESTING PROGRAM AND LABORATORY TESTING PROGRAM2

3.1 Field Explorations.....2

3.2 Laboratory Testing Program3

4 SITE GEOLOGY3

5 SUBSURFACE CONDITIONS.....4

5.1 Fill and Embankment Materials.....4

5.2 Coal Combustion Residuals.....5

5.3 Alluvium.....5

5.4 Groundwater.....6

6 GEOTECHNICAL MATERIAL PROPERTIES.....6

7 LIMITATIONS.....6

8 REFERENCES7

TABLES

Table 1: Summary of Subsurface Exploration10

Table 2: Summary of Geotech Laboratory Test Results11

Table 3: Summary of Engineering Material Properties.....12

FIGURES

- Figure 1: Site Location Plan
- Figure 2: Geotechnical Exploration Locations Plan (Aerial)
- Figure 3: Potentiometric Map
- Figure 4: Isopach Map of CCR Thickness
- Figure 5: Subsurface Cross Sections and Interpreted Stratigraphy

APPENDICES

APPENDIX A

Site Reconnaissance Photo Log

APPENDIX B

Previous Geotechnical Investigations

APPENDIX C

Geotechnical Boring Logs

APPENDIX D

Geotechnical Laboratory Test Reports

1 INTRODUCTION

WSP USA Inc. (WSP) was retained by Appalachian Power Company, a subsidiary to American Electric Power Company, Inc., (AEP) to provide Coal Combustion Residual (CCR) Legacy Unit Engineering Support for AEP's ash pond located at the former Cabin Creek Power Plant in Cabin Creek, West Virginia (Site), as shown in **Figure 1**. The Site is a legacy CCR surface impoundment located in Chelyan, Kanawha County, adjacent to the Kanawha River, and is subject to the requirements of the Federal CCR Rule (40 Code of Federal Regulations (CFR) Part 257, Subpart D).

The purpose of this Geotechnical Data Report (GDR) is to document the field exploration and laboratory testing performed at the Site to support subsequent engineering evaluations required under the Federal CCR rule. As part of the scope of services, WSP performed a geotechnical exploration focused on identifying subsurface stratigraphy, characterizing the shear strengths of the materials encountered, and documenting qualitative groundwater conditions. Prior to WSP's investigation, AEP conducted a geoprobe investigation and a geophysical survey across the Cabin Creek Ash Pond to primarily evaluate the depth of ash within the ash pond.

WSP's field program was developed to supplement previous investigations and to obtain quantitative geotechnical data to support the safety factor assessment and structural stability assessment in compliance with the Federal CCR Rule (40 CFR §§257.73).

This GDR presents a summary of the available data collected from the previous investigations, results of WSP's field and laboratory testing, and the documented subsurface conditions encountered at the Site. This GDR includes descriptions of field exploration, laboratory testing, site geology, subsurface conditions, and geotechnical material properties obtained from the investigation.

2 SITE VISIT

WSP conducted a site visit to the Cabin Creek Ash Pond on July 16, 2025, to observe current site conditions, verify proposed boring locations, evaluate site accessibility for drilling equipment, and identify any logistical constraints. Mr. Steven Moeller and Mr. Naveen Kumar Ganji conducted the site visit on behalf of WSP. WSP personnel performed the following:

- Observed site conditions related to the structural stability of the impoundment, including berms, dikes, erosion protection, vegetation, slopes, stormwater drainage features, etc.
- Reviewed site access routes, working areas, and potential safety hazards
- Confirmed proposed boring locations and access to these locations
- Photographed site features for documentation in the GDR (**APPENDIX A**)

During the site reconnaissance, the site observations were limited to features and structures that could be visually observed at the ground surface, and did not include invasive inspection, investigation, or exploration of the Site, embankments, or structures. WSP noted the following observations at the Site:

- The top of the former impoundment was recently cleared of trees and vegetation
- The principal spillway structure for the former impoundment was not properly abandoned and had been filled with soil and organic materials

- Several pipelines and manholes are located within the limits of the Cabin Creek Ash Pond, primarily related to routing stormwater around the ash pond
- The northern slope of the ash pond along the Kanawha River and the northeastern slope are heavily wooded with trees and vegetation, making it difficult to inspect
- Uprooted fallen trees were observed at the crest of the northern slope of the ash pond along the Kanawha River
- Due to the heavy vegetation observed on the exterior dike slopes, only limited areas of erosion were observed

3 FIELD EXPLORATIONS AND LABORATORY TESTING PROGRAM

3.1 Field Explorations

Triad Engineering performed environmental and geotechnical investigations in the former underground storage tank area located east of the ash pond to evaluate subsurface and groundwater conditions. As part of these investigations, eight monitoring wells were installed in 2006 to depths ranging from approximately 25 to 27 feet below ground surface (bgs), and ten soil borings were advanced in 2013 to depths of about 15 feet bgs. The boring location plan, potentiometric map, and detailed soil boring and well logs are provided in **APPENDIX B**.

Schnabel Engineering performed a geotechnical investigation at the Site in 2019 to evaluate the subsurface conditions for a new transmission line that was proposed to be located slightly east of the existing on-site substation to across the Kanawha River. As part of this investigation, three borings were advanced, two adjacent to the existing substation at the Site and one on the northern side of the Kanawha River. Specific observations, remarks, and logs for the borings; classification criteria; drilling methods; and sampling protocols are included in **APPENDIX B**.

EHS Support (EHS) performed a subsurface investigation in mid-2025 to evaluate the extent of ash in the Cabin Creek Ash Pond and the area east of the ash pond at the Former Cabin Creek Power Plant (Plant). The evaluation included a surface geophysical survey, confirmation soil geoprobe borings, and development of a three-dimensional (3D) model. A technical memorandum, dated September 12, 2025, was prepared by EHS summarizing the findings of the investigations. Excerpts from this memorandum relevant to this GDR are included in **APPENDIX B**. The geoprobe locations from the EHS investigation are shown in **Figure 2**.

In mid to late 2025, EHS installed monitoring wells and piezometers within and outside the footprint of the Cabin Creek impoundment. The location of these monitoring wells and piezometers is shown in **Figure 3**.

WSP used the static groundwater elevation data measured in December 2025 at these monitoring wells and piezometers, to interpret subsurface water levels at the Site. An interpreted potentiometric map is included in **Figure 3**.

WSP's field exploration included 16 soil borings that were advanced from 25 feet to approximately 50 feet below ground surface (bgs). The location of these borings is shown in **Figure 2**. The borings were advanced as follows:

- 4 borings within the ash deposit areas (A-series)
- 9 borings along the perimeter dike (E-series)
- 3 borings in the former river back-channel area (B-series)

The drilling and sampling program was completed in accordance with ASTM standards and included:

- Standard Penetration Tests (SPT) performed at 2.5-foot intervals to 10 feet bgs, and at 5-foot intervals thereafter to the target termination depth, per ASTM D1586
- Nine undisturbed samples using Shelby tubes were collected from native foundation soils, embankment materials, and representative CCR materials
- Field classification and logging of all recovered samples were performed using the Unified Soil Classification System (USCS)
- Boreholes were advanced using Hollow Stem Auger, Mud Rotary, and Direct Push techniques. Based on a review of the SPT data, it appears that the Direct Push method overestimates the SPT blow counts, as such, SPTs (boring B-3) using this method were not used in the engineering evaluations

3.2 Laboratory Testing Program

WSP coordinated and performed laboratory testing on selected soil and CCR samples collected during the subsurface investigation. The purpose of the testing was to determine index, strength, and compressibility properties required for geotechnical characterization and engineering analysis of the ash, underlying native soils, and embankment materials.

Testing was performed by a certified geotechnical laboratory in accordance with applicable ASTM standards. Laboratory tests included:

- Index Properties:
 - Moisture Content (ASTM D2216)
 - Atterberg Limits (ASTM D4318)
 - Particle Size Distribution (ASTM D6913)
 - Specific Gravity (ASTM D854)
- Unit weight determination (ASTM D7263)
- Consolidated-undrained triaxial shear with pore pressure measurements (CU, ASTM D4767)

Sample selection for testing was based on visual classification/ field logs, SPT values, and undisturbed sample recovery, with a focus on identifying critical layers (CCR materials, embankment materials, foundation soils, potentially liquefiable zones, etc.) in the subsurface.

Boring logs and laboratory data sheets are included in **APPENDIX C** and **APPENDIX D**, respectively.

4 SITE GEOLOGY

The project site lies centrally within the Alleghany Plateau of West Virginia, a more specific region of the larger Appalachian Plateau. The terrain in the area is characterized by numerous steep hills and valleys, with ridges consistently near 1400 feet above mean sea level (MSL) and valleys ranging from 600 feet to 800 feet MSL. The physical geography of the area is most influenced by dendritic drainage and erosion towards the Kanawha River.

Geologic mapping within the county (Windolph 1987) has provided detailed descriptions for subsurface lithology within the area, which is characterized by Pennsylvanian-aged siliclastic and mudrock strata with subdued folding and faulting. The Site sits between the Warfield anticline and Handley syncline that, along with the sedimentary strata, exhibits a general northeast–southwest strike, with very gentle southeast dips.

The most prevalent formations are middle to upper Pennsylvanian sedimentary formations, described below from oldest to youngest:

- Kanawha Formation (Middle Pennsylvanian) - Sandstone, light gray, fine to coarse-grained quartz rich; Siltstone, thin-bedded, gray to black, carbonaceous; Coal, bright to dull, medium cleated; Chert, gray to black, conchoidal fractured.
- Charleston Sandstone (Middle Pennsylvanian) - Sandstone, light gray, very fine to coarse-grained, well-rounded conglomerates; Shale and Siltstone, gray to black, poorly bedded; Coal, bright to dull, coarsely cleated.
- Conemaugh Formation (Upper Pennsylvanian) - Sandstone, medium gray, very fine to coarse-grained, locally conglomeratic with subangular limestone and shale fragments; Siltstone and Shale, medium gray to green, some red, includes hematite nodules; Coal, dull and impure; Limestone, gray to brown, nodular, mudstone to packstone.

The Site is located in the Kanawha River Valley, situated within the Appalachian Plateau, characterised by gently folded sedimentary rocks of Pennsylvanian and Mississippian age. The geologic stratigraphy in this area typically consists of sequences of sandstone, shale, siltstone, claystone, and coal beds. The bedrock is overlain by unconsolidated alluvial deposits, especially along the river floodplain, which include silty sands, gravels, and clayey silts deposited by fluvial processes.

5 SUBSURFACE CONDITIONS

The Site is located adjacent to the Kanawha River within an area underlain by unconfined alluvial deposits. These deposits primarily consist of silty sands, gravels, and clayey silts formed by fluvial processes. Beneath the alluvium lies bedrock that begins at approximately 25 to 35 feet below the natural ground surface prior to fill placement in the area (560 feet MSL to 570 feet MSL). Based on the available data from the multiple site investigations, WSP has identified the following stratigraphy at the Cabin Creek Ash Pond.

5.1 Fill and Embankment Materials

The Cabin Creek Ash Pond was constructed in the 1950s by constructing a perimeter berm around Cabin Creek Island and infilling a back channel that separated the island from the southern riverbank. During construction, the river channel north of the island and northern portions of the island were excavated/dredged, and spoils from the dredging activities were placed into the back channel (identified as Dredge Spoil in this GDR). Additional fill material (identified as Earthfill in this GDR) was placed to construct berms around the perimeter of the island. Prior to filling, the ground surface elevation of the island was approximately 595 feet MSL. Based on boring data along the embankment alignment, it appears that Earthfill material was used to construct the perimeter berm on the north side of the island to an approximate elevation of 605 feet MSL. The berms were further raised over time to an approximate elevation of 620 feet MSL using Earthfill, Earthfill with CCR inclusions (identified as CCR-Soil Mix (Embankment) in the boring logs), and CCR materials (identified as CCR (Embankment) in the boring logs). CCR–Soil Mix refers to Earthfill material that contains inclusions of CCR. It is not meant to imply a uniformly blended mix of CCR and Earthfill.

Dredge Spoils were encountered in borings B-1, B-2, E-1, E-8, and E-9 and were visually classified predominantly as silty sand. Field SPT N-values recorded in this material ranged from 2 to 8 blows per foot (bpf), with an average of SPT-N of 5 bpf, indicating very loose to loose relative density. Laboratory tests indicated the in-situ moisture contents ranging from 20% to 51.4%. Gradation tests performed on two samples showed 22.1% and 96.1% material passing the No. 200 sieve.

Earthfills used to construct the perimeter berms were identified in boreholes E-1 through E-7, and E-9, and were visually classified as silt and silty sand. Field SPT N-values recorded in this material ranged from 0 to 44 bpf, with most of the blow counts ranging between 5 to 25 bpf, indicating loose to compact relative density. The average of SPT-N values for this material was 12 bpf. Laboratory tests indicated the in-situ moisture contents ranging from 6.7% to 29.2%. Gradation tests performed on four samples showed 22.6% to 52.6% material passing the No. 200 sieve.

CCR-Soil Mix (Embankment) and CCR (Embankment) materials used to raise the perimeter berms were identified in boreholes E-1 through E-9 and were also visually classified as silt and silty sand. SPT N-values for these materials ranged from 1 to 24 bpf, with most values between 5 and 15 bpf indicating loose to compact relative density. The average of SPT-N values for these materials was 11 bpf. Laboratory tests showed in-situ moisture contents ranging from 15% to 41.9%. Gradation tests on four samples showed that 18.9% to 78.6% of the material passed the No. 200 sieve.

5.2 Coal Combustion Residuals

CCRs, including fly ash and bottom ash, are byproducts of coal-fired power generation. At the Cabin Creek Ash Pond, CCR materials were used as construction materials for the perimeter embankment, as discussed in the previous section, and were sluiced into the interior of the impoundment. In the impoundments where CCRs are sluiced (identified as sluiced CCR), the materials are generally deposited in a loose, saturated condition. CCR materials sluiced into the impoundment were placed from an approximate elevation of 595 feet MSL to an approximate elevation of 618 to 620 feet MSL. An approximate 3-foot-thick layer of CCR-Soil Mix (identified as CCR-Soil Mix (Impoundment)) was also encountered at the surface within the impoundment area.

CCR-Soil Mix (Impoundment) and the Sluiced CCR were identified in boreholes A-1 through A-4 and B-1 through B-3 and were visually classified as silt and silty sand. Field SPT N-values recorded in these materials ranged from 4 to 14 bpf indicating loose to compact relative density. The average of SPT-N values for these materials was 4 bpf. On the south end of the impoundment, a mound of material similar to CCR-Soil Mix (Impoundment) was encountered (See Figure 4). This localized material is referred to as CCR-Stockpiled as the material had been previously stockpiled at its current location. For engineering evaluations, this material should perform like CCR-Soil Mix (Impoundment).

Laboratory tests conducted on the CCR materials (CCR-Soil Mix (Impoundment) and the Sluiced CCR) indicated in situ moisture contents ranging from 11.2% to 99.2%. Gradation testing performed on the three samples showed 57.5% to 69.6% material passing the No. 200 sieve.

5.3 Alluvium

Alluvial soils deposited by the Kanawha River were encountered in the borings either beneath the Earthfill/Dredge Spoil materials within the embankment or beneath the CCR materials in the ash pond. Generally, the alluvial soils at the site were encountered at an approximate elevation of 595 feet MSL, which is consistent with earlier drawings showing the elevation of Cabin Creek Island at 595 feet MSL.

The alluvium consists primarily of silt, silty clay, and lean clays with varying amounts of sand, gravel, and mica. Field SPT N-values recorded in the alluvial soils ranged from Weight of Hammer (WOH) over 18 inches to 17 bpf, indicating very soft to very stiff consistency.

Laboratory tests conducted on the alluvial soils indicate in situ moisture contents ranging from 19.7% to 29%. Atterberg Limits testing performed on samples of the alluvial soils resulted in Liquid Limits ranging from NP (Non-Plastic) to 23% and Plasticity Indices ranging from NP to 5%. Gradation testing performed on these samples showed 19.8% to 67.8% material passing the No. 200 sieve.

An isopach illustrating CCR thickness was developed for the Cabin Creek Ash Pond based on subsurface investigations by EHS and WSP and is presented in **Figure 4**. Representative subsurface stratigraphy cross-sections across site-cardinal directions of the pond and along the dike are shown in **Figure 5**.

5.4 Groundwater

Groundwater levels at the Cabin Creek Ash Pond were inferred by observing the saturation of the soils and/or CRR materials sampled during subsurface investigations conducted by EHS and WSP. The estimated groundwater level was observed in the borings at an approximate elevation of 595 feet MSL. No long-term water level readings were recorded at the Site.

The test boring logs in **APPENDIX C** include groundwater observations obtained during our subsurface exploration. The groundwater levels on the logs indicate our estimate of the hydrostatic water table at the time of our subsurface exploration. Additionally, a potentiometric map was developed using data collected during EHS's and WSP's investigations, as presented in **Figure 3**.

6 GEOTECHNICAL MATERIAL PROPERTIES

Consolidated undrained triaxial tests were performed on representative samples collected from the Site to determine shear strength parameters under controlled conditions. The results provide insight into the material behavior under both drained and undrained loading scenarios, which is critical for stability analyses and closure design.

SPT Correlation and Strength Parameters: SPT values were correlated with shear strength parameters using established empirical relationships commonly applied in geotechnical engineering practice. These correlations consider soil type, relative density, and consistency, and were used to estimate cohesion (c) and friction angle (ϕ). The calculations followed procedures outlined in ASTM D1586 and supplemented by published correlations (Peck, Hanson & Thornburn, 1974). A summary table of SPT-based correlations and corresponding strength parameters is presented in Table 3.

In previous investigations conducted at AEP's Kanawha River Site (located three to four miles upstream of the Cabin Creek Ash Pond on the Kanawha River), triaxial compression tests performed on samples of ash from the East Fly Ash Pond yielded effective shear strengths with friction angle (ϕ) values ranging from 30.5° to 32.8° and apparent cohesions (c) ranging from 0 to 0.27 kips per square foot (ksf). The effective shear strength obtained from samples of alluvium sampled and tested in 2005 yielded effective shear strengths with ϕ' values = 32° to 36.4° and $c' = 0.1$ to 0.46 ksf.

7 LIMITATIONS

The information, data, and interpretations presented in this GDR are based on the conditions encountered at the specific locations and depths of the subsurface explorations performed for this project. Subsurface conditions can

vary significantly between and beyond these exploration points. No warranty is expressed or implied regarding the continuity of soil, rock, or groundwater conditions across the Site.

This report is intended solely to document factual subsurface data obtained during the field and laboratory investigations. It does not provide engineering analyses, design recommendations, or opinions regarding the suitability of the Site for any specific purpose. Any use of this report for purposes other than its intended scope is at the discretion and risk of the user.

Groundwater levels reported herein represent conditions observed at the time of exploration and may fluctuate seasonally or due to construction activities. The data should not be interpreted as absolute or permanent groundwater conditions.

The findings in this report should be considered in conjunction with the limitations inherent in geotechnical investigations, including variability of natural materials and the restricted number of sampling locations. Additional investigations may be warranted if significant changes in Site conditions occur or if the proposed development differs from the assumptions made during this study.

8 REFERENCES

Cardwell, D.H., Erwin, R.B., & Woodward, H.P. (1968). Geologic Map of West Virginia. West Virginia Geological and Economic Survey.

EHS Support LLC. (EHS 2025). Technical Memorandum, Cabin Creek – Ash Depth Investigation. Cabin Creek Ash Pond. September 2025.

Peck, R. B., Hanson, W. E., & Thornburn, T. H. (1974). Foundation engineering (2nd ed.). New York, NY: John Wiley & Sons.

Schnabel Engineering (Schnabel 2019). AEP Cabin Creek - London 46kV, Geotechnical Engineering Report, Kanawha County, West Virginia. September 2019.

USGS (United States Geological Survey) (1996). Ground Water Atlas of the United States: Segment 12, West Virginia.

Windolph, J. F. (1987). Geologic Map of the Big Chimney quadrangle, Kanawha County, West Virginia (Geologic Quadrangle Map GQ-1612). U.S. Geological Survey. <https://doi.org/10.3133/gq1612>

Wilson, D. (1979). Hydrogeology of the Kanawha River Alluvial Aquifer. West Virginia Geological and Economic Survey Bulletin.

Signature Page

We appreciate the opportunity to provide CCR Legacy Unit Engineering Support for AEP's Cabin Creek ash pond. If you have questions regarding our report, please contact the undersigned.

Sincerely,

WSP USA Inc.



Naveen Kumar Ganji, PE (GA, TN, TX, VA)
Senior Consultant



Steven J. Moeller, PE (AL, GA, NC, TN, WV)
Senior Vice President

PG/NG/SM/ng

[https://wspnlinenam.sharepoint.com/sites/us-aep-cabin-creek-c/shared documents/5 technical work/gdr/gdr_cabincreek_ashpond_ccr_engsupport.docx](https://wspnlinenam.sharepoint.com/sites/us-aep-cabin-creek-c/shared%20documents/5%20technical%20work/gdr/gdr_cabincreek_ashpond_ccr_engsupport.docx)

Tables

Table 1: Summary of Subsurface Exploration

Boring ID	Date	Latitude	Longitude	Ground Surface Elevation (feet MSL)	Borehole Depth (feet)	Groundwater Elevation (feet MSL)	Bottom of Ash Elevation (feet MSL)
A-1	9/5/2025	38.1979	-81.4863	616.2	30	597.2	596.4
A-2	9/8/2025	38.1981	-81.4854	618	30	598	598.2
A-3	9/10/2025	38.1981	-81.4839	619.7	30	596.2	600.4
A-4	8/29/2025	38.1974	-81.4853	616.3	35	NA	592.8
B-1	9/4/2025	38.1973	-81.4866	619	35	NA	594.5
B-2	9/10/2025	38.1971	-81.4849	625.9	40	597.4	597.4
B-3	8/27/2025	38.1974	-81.4839	617.4	37	588.9	590.6
E-1	9/12/2025	38.1978	-81.4879	618	50	NA	598.2
E-2	9/15/2025	38.1981	-81.4873	619.4	25	NE	605.2
E-3	9/16/2025	38.1984	-81.4863	617.9	20	NE	609.4
E-4	9/16/2025	38.1985	-81.4854	619	25	NE	604.6
E-5	9/16/2025	38.1987	-81.4847	619	25	NE	604.8
E-6	9/17/2025	38.1988	-81.4836	624.2	30	NE	605.4
E-7	9/17/2025	38.1983	-81.4829	619.9	20	NE	612.4
E-8	9/11/2025	38.1971	-81.4841	618.8	35	589.8	604.3
E-9	9/11/2025	38.1968	-81.4853	617.4	30	593.9	599.6

Notes:

1. NA = Not Available, could not be measured due to the drilling method
2. NE = Not Encountered
3. MSL = Mean Sea Level

Table 2: Summary of Geotechnical Laboratory Test Results

S. No.	Boring ID	Sample Type	Material Type	Depth (feet below ground surface)		Ground Surface Elevation (feet Mean Sea Level)	Soil Classification (Field and Lab observations)	Depth to Water (DTW) at the time of drilling (feet bgs) ¹	Blow Count (SPT N)	Moisture Content (ASTM D2216)	Atterberg Limits (ASTM D4318)			Particle Size Distribution (ASTM D6913)		Unit Weight (ASTM D7263) ²	Specific Gravity (ASTM D854)	Triaxial CU (ASTM D4767)				Direct Shear (ASTM D3080)	φ from SPT - N (Peck, Hanson, and Thornburn (1974))
				from	to						LL	PL	PI	% Finer No. 4	% Finer No. 200			c (psf)	φ (°)	c' (psf)	φ' (°)		
1	A-1	SPT	CCR-impounded	0.0	1.5	616.2	SM	19.0	5														28.60
2	A-1	SPT	Sluiced CCR	3.5	5.0	616.2	ML	19.0	3														28.00
3	A-1	SPT	Sluiced CCR	6.0	7.5	616.2	ML	19.0	3														28.00
4	A-1	SPT	Sluiced CCR	8.5	10.0	616.2	ML	19.0	4														28.30
5	A-1	SPT	Sluiced CCR	13.5	15.0	616.2	ML	19.0	3	70.2													28.00
6	A-1	SPT	Sluiced CCR	18.5	20.0	616.2	ML	19.0	2														27.70
7	A-1	SPT	Alluvium	23.5	25.0	616.2	SM	19.0	5	29.5	NP	NP	NP	100.0	49.7		2.7						28.60
8	A-1	SPT	Alluvium	28.5	30.0	616.2	SM	19.0	3														28.00
9	A-2	SPT	CCR-impounded	0.0	1.5	618.0	SM	20.0	4	61.8													28.30
10	A-2	SPT	Sluiced CCR	3.5	5.0	618.0	ML	20.0	4														28.30
11	A-2	SPT	Sluiced CCR	6.0	7.5	618.0	ML	20.0	4														28.30
12	A-2	SPT	Sluiced CCR	8.5	10.0	618.0	ML	20.0	2														27.70
13	A-2	Tube	Sluiced CCR	10.0	12.0	618.0	ML	20.0		80.3	NP	NP	NP	100.0	69.6	36.9	2.1	734.4	10.9	0.0	34.2		-
14	A-2	SPT	Sluiced CCR	13.5	15.0	618.0	ML	20.0	8	63.1													29.50
15	A-2	SPT	Sluiced CCR	18.5	20.0	618.0	ML	20.0	6														28.90
16	A-2	SPT	Alluvium	23.5	25.0	618.0	SM	20.0	2	22.8													27.70
17	A-2	Tube	Alluvium	25.0	27.0	618.0	SM	20.0															-
18	A-2	SPT	Alluvium	28.5	30.0	618.0	SM	20.0	6														28.90
19	A-3	SPT	CCR-impounded	0.0	1.5	619.7	SM	23.5	7	11.2													29.20
20	A-3	SPT	Sluiced CCR	3.5	5.0	619.7	ML	23.5	4														28.30
21	A-3	Tube	Sluiced CCR	5.0	7.0	619.7	ML	23.5		51.8	NP	NP	NP	99.9	57.5	46.4							-
22	A-3	SPT	Sluiced CCR	7.0	8.5	619.7	ML	23.5	4														28.30
23	A-3	SPT	Sluiced CCR	8.5	10.0	619.7	ML	23.5	2														27.70
24	A-3	SPT	Sluiced CCR	13.5	15.0	619.7	ML	23.5	0														27.10
25	A-3	SPT	Sluiced CCR	18.5	20.0	619.7	ML	23.5	14	52.8													31.20
26	A-3	SPT	Alluvium	18.5	20.0	619.7	SM	23.5															-
27	A-3	SPT	Alluvium	23.5	25.0	619.7	SM	23.5	10	19.7													30.00
28	A-3	SPT	Alluvium	28.5	30.0	619.7	SC	23.5	2	21.9	NP	NP	NP										27.70
29	A-4	SPT	CCR-impounded	0.0	1.5	616.3	SM	NA	3	25.7													28.00
30	A-4	SPT	CCR-impounded	3.5	5.0	616.3	SM	NA															-
31	A-4	SPT	CCR-impounded	6.0	7.5	616.3	ML	NA	13														30.90
32	A-4	SPT	Sluiced CCR	8.5	10.0	616.3	ML	NA	6														28.90
33	A-4	SPT	Sluiced CCR	13.5	15.0	616.3	ML	NA	8														29.50
34	A-4	Tube	Sluiced CCR	15.0	17.0	616.3	ML	NA		52.1	NP	NP	NP	92.9	64.0	56.4	2.1	14.4	26.3	0.0	35.0		27.70
35	A-4	SPT	Sluiced CCR	18.5	20.0	616.3	ML	NA	2														27.40
36	A-4	SPT	Alluvium	23.5	25.0	616.3	ML	NA	1	34.5	NP	NP	NP		60.2		2.6						27.70
37	A-4	SPT	Alluvium	28.5	30.0	616.3	SM	NA	2														30.00
38	A-4	SPT	Alluvium	33.5	35.0	616.3	SM	NA	10														28.90
39	B-1	SPT	CCR-impounded	0.0	1.5	619.0	SM	NA	6														28.60
40	B-1	SPT	Sluiced CCR	3.5	5.0	619.0	ML	NA	5														28.60
41	B-1	SPT	Sluiced CCR	6.0	7.5	619.0	ML	NA	5	49.2													28.00
42	B-1	SPT	Sluiced CCR	8.5	10.0	619.0	ML	NA	3														27.70
43	B-1	SPT	Sluiced CCR	13.5	15.0	619.0	ML	NA	2														27.10
44	B-1	SPT	Sluiced CCR	18.5	20.0	619.0	ML	NA	0	99.2													27.10
45	B-1	SPT	Sluiced CCR	23.5	25.0	619.0	ML	NA	0														28.30
46	B-1	SPT	Dredge Spoil	28.5	30.0	619.0	CL	NA	4	51.4	45	24	21	100.0	96.1								28.30
47	B-1	SPT	Alluvium	33.5	35.0	619.0	SM	NA	4														28.30
48	B-2	SPT	CCR-Stockpiled	0.0	1.5	625.9	SM	28.5	4														28.30
49	B-2	SPT	CCR-Stockpiled	3.5	5.0	625.9	ML	28.5	2														27.70
50	B-2	SPT	Sluiced CCR	8.5	10.0	625.9	ML	28.5	4														28.30
51	B-2	SPT	Sluiced CCR	13.5	15.0	625.9	ML	28.5	4														28.30
52	B-2	SPT	Sluiced CCR	18.5	20.0	625.9	ML	28.5	7														29.20
53	B-2	SPT	Sluiced CCR	23.5	25.0	625.9	ML	28.5	3	70.6													28.00
54	B-2	SPT	Dredge Spoil	28.5	30.0	625.9	SM	28.5	8	28.5					93.7	22.1							29.50
55	B-2	SPT	Dredge Spoil	33.5	35.0	625.9	SM	28.5	2														27.70
56	B-2	Tube	Dredge Spoil	35.0	37.0	625.9	SM	28.5															-
57	B-2	SPT	Alluvium	38.5	40.0	625.9	ML	28.5	0	30.4					100.0	67.8							27.10
58	B-3	SPT	CCR-impounded	0.0	1.5	617.4	SM	28.5	5														28.60
59	B-3	SPT	Sluiced CCR	3.5	5.0	617.4	ML	28.5	9	58.5													29.80
60	B-3	SPT	Sluiced CCR	8.5	10.0	617.4	ML	28.5	20														32.90
61	B-3	SPT	Sluiced CCR	13.5	15.0	617.4	ML	28.5	54														41.70
62	B-3	SPT	Sluiced CCR	18.5	20.0	617.4	ML	28.5	9														29.80
63	B-3	SPT	Sluiced CCR	23.5	25.0	617.4	ML	28.5	4														28.30
64	B-3	SPT	Alluvium	28.5	30.0	617.4	SM	28.5	17	27.4					99.7	19.8							32.00
65	B-3	SPT	Alluvium	33.5	35.0	617.4	SM	28.5	17														32.00
66	B-3	Tube	Alluvium	35.0	37.0	617.4	SM	28.5		48.0					98.1	37.6	65.8						-
67	E-1	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	618.0	SM	NA	15	17.8					76.1	18.9							31.50
68	E-1	SPT	CCR-Soil Mix (Embankment)	3.5	5.0	618.0	SM	NA	10														30.00
69	E-1	SPT	CCR (Embankment)	6.0	7.5	618.0	SM	NA	14														31.20
70	E-1	SPT	CCR (Embankment)	8.5	10.0	618.0	ML	NA	12														30.60
71	E-1	SPT	CCR (Embankment)	13.5	15.0	618.0	ML	NA	3														28.00
72	E-1	SPT	CCR (Embankment)	18.5	20.0	618.0	ML	NA	1	29.1													27.40
73	E-1	SPT	Earth Fill	25.0	26.5	618.0	ML	NA	0	29.2					99.1	52.6							27.10
74	E-1	SPT	Dredge Spoil	28.5	30.0	618.0	SM	NA	4														28.30

Table 2: Summary of Geotechnical Laboratory Test Results

S. No.	Boring ID	Sample Type	Material Type	Depth (feet below ground surface)		Ground Surface Elevation (feet Mean Sea Level)	Soil Classification (Field and Lab observations)	Depth to Water (DTW) at the time of drilling (feet bgs) ¹	Blow Count (SPT N)	Moisture Content (ASTM D2216)	Atterberg Limits (ASTM D4318)			Particle Size Distribution (ASTM D6913)		Unit Weight (ASTM D7263) ²	Specific Gravity (ASTM D854)	Triaxial CU (ASTM D4767)				Direct Shear (ASTM D3080)	φ from SPT - N (Peck, Hanson, and Thornburn (1974))
				from	to						LL	PL	PI	% Finer No. 4	% Finer No. 200			c (psf)	φ (°)	c' (psf)	φ' (°)		
75	E-1	SPT	Alluvium	33.5	35.0	618.0	CL-ML	NA	6														28.90
76	E-1	Tube	Alluvium	35.0	37.0	618.0	CL-ML	NA		22.6	23	18	5	99.9	56.6	104.1	2.7	0.0	21.4	0.0	37.5		-
77	E-1	SPT	Alluvium	38.5	40.0	618.0	CL-ML	NA	3														28.00
78	E-1	SPT	Alluvium	43.5	45.0	618.0	SM	NA	6														28.90
75	E-1	SPT	Alluvium	48.5	50.0	618.0	SM	NA	4	32.8													28.30
76	E-2	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	619.4	SM	NE	10	19.7													30.00
77	E-2	SPT	CCR (Embankment)	3.5	5.0	619.4	ML	NE	14														31.20
78	E-2	SPT	CCR (Embankment)	6.0	7.5	619.4	ML	NE	17	39.3													32.00
79	E-2	SPT	CCR (Embankment)	8.5	10.0	619.4	ML	NE	12														30.60
80	E-2	SPT	Earth Fill	13.5	15.0	619.4	SM	NE	10	13.9													30.00
81	E-2	SPT	Earth Fill	18.5	20.0	619.4	SM	NE	6														28.90
82	E-2	SPT	Earth Fill	23.5	25.0	619.4	SM	NE	7	17.7				99.9	47.3								29.20
83	E-3	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	617.9	SM	NE	7														29.20
84	E-3	SPT	CCR (Embankment)	3.5	5.0	617.9	ML	NE	6														28.90
85	E-3	Tube	CCR (Embankment)	5.0	7.0	617.9	ML	NE		35.3	NP	NP	NP	98.9	78.6	60.0							-
86	E-3	SPT	CCR (Embankment)	7.0	8.5	617.9	ML	NE	17														32.00
87	E-3	SPT	Earth Fill	8.5	10.0	617.9	SM	NE	27	8.1													34.80
88	E-3	SPT	Earth Fill	13.5	15.0	617.9	SM	NE	11														30.30
89	E-3	SPT	Earth Fill	18.5	20.0	617.9	SM	NE	9	14.9													29.80
90	E-4	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	619.0	SM	NE	17	19.7													32.00
91	E-4	SPT	CCR (Embankment)	3.5	5.0	619.0	ML	NE	13														30.90
92	E-4	SPT	CCR (Embankment)	6.0	7.5	619.0	ML	NE	15	40.4													31.50
93	E-4	SPT	CCR (Embankment)	8.5	10.0	619.0	ML	NE	5														28.60
94	E-4	SPT	CCR (Embankment)	13.5	15.0	619.0	ML	NE	8														29.50
95	E-4	SPT	Earth Fill	18.5	20.0	619.0	SM	NE	10														30.00
96	E-4	SPT	Earth Fill	23.5	25.0	619.0	SM	NE	5	18.5													28.60
97	E-5	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	619.0	SM	NE	13	15.0													30.90
98	E-5	SPT	CCR (Embankment)	3.5	5.0	619.0	ML	NE	11														30.30
99	E-5	SPT	CCR (Embankment)	6.0	7.5	619.0	ML	NE	9														29.80
100	E-5	SPT	CCR (Embankment)	8.5	10.0	619.0	ML	NE	12	41.9													30.60
101	E-5	SPT	CCR (Embankment)	13.5	15.0	619.0	ML	NE	9														29.80
102	E-5	SPT	Earth Fill	18.5	20.0	619.0	SM	NE	11	13.1													30.30
103	E-5	SPT	Earth Fill	23.5	25.0	619.0	SM	NE	2														27.70
104	E-6	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	624.2	SM	NE	7														29.20
105	E-6	SPT	CCR (Embankment)	3.5	5.0	624.2	ML	NE	3	33.6													28.00
106	E-6	SPT	CCR (Embankment)	6.0	7.5	624.2	ML	NE	3														28.00
107	E-6	SPT	CCR (Embankment)	8.5	10.0	624.2	ML	NE	2														27.70
108	E-6	SPT	CCR (Embankment)	13.5	15.0	624.2	SM	NE	7	35.4													29.20
109	E-6	SPT	Earth Fill	18.5	20.0	624.2	SM	NE	21														33.20
110	E-6	SPT	Earth Fill	23.5	25.0	624.2	SM	NE	8	8.9				97.7	22.6								29.50
111	E-6	SPT	Earth Fill	28.5	30.0	624.2	SM	NE	4														28.30
112	E-7	SPT	Earth Fill	0.0	1.5	619.9	SM	NE	10	15.4													30.00
113	E-7	SPT	CCR (Embankment)	3.5	5.0	619.9	SM	NE	7														29.20
114	E-7	SPT	CCR (Embankment)	6.0	7.5	619.9	SM	NE	23														33.70
115	E-7	SPT	Earth Fill	8.5	10.0	619.9	SM	NE	23														33.70
116	E-7	SPT	Earth Fill	13.5	15.0	619.9	SM	NE	6														28.90
117	E-7	SPT	Earth Fill	18.5	20.0	619.9	SM	NE	9	13.1				100.0	41.4								29.80
118	E-8	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	618.8	SM	29.0	11														30.30
119	E-8	SPT	CCR-Soil Mix (Embankment)	3.5	5.0	618.8	SM	29.0	17														32.00
120	E-8	SPT	CCR-Soil Mix (Embankment)	6.0	7.5	618.8	SM	29.0	21	20.4													33.20
121	E-8	SPT	CCR (Embankment)	8.5	10.0	618.8	ML	29.0	9														29.80
122	E-8	SPT	CCR (Embankment)	13.5	15.0	618.8	ML	29.0	6	40.5													28.90
123	E-8	SPT	Dredge Spoil	18.5	20.0	618.8	SM	29.0	4														28.30
124	E-8	SPT	Alluvium	23.5	25.0	618.8	SM	29.0	14	27.8													31.20
125	E-8	SPT	Alluvium	28.5	30.0	618.8	SM	29.0	2	37.5	NP	NP	NP										27.70
126	E-8	SPT	Alluvium	33.5	35.0	618.8	SM	29.0	7	26.2				99.6	22.7								29.20
127	E-9	SPT	CCR-Soil Mix (Embankment)	0.0	1.5	617.4	SM	23.5	10	30.1				87.4	25.7								30.00
128	E-9	SPT	Earth Fill	3.5	5.0	617.4	SM	23.5	44	6.7													39.30
129	E-9	SPT	CCR (Embankment)	6.0	7.5	617.4	ML	23.5	24														34.00
130	E-9	SPT	CCR (Embankment)	8.5	10.0	617.4	ML	23.5	19	38.5													32.60
131	E-9	SPT	CCR (Embankment)	13.5	15.0	617.4	ML	23.5	5														28.60
132	E-9	Tube	CCR (Embankment)	15.0	17.0	617.4	ML	23.5		28.0	NP	NP	NP	98.6	39.9	72.6	2.3	0.0	16.8	0.0	25.6	25.90	-
133	E-9	SPT	Dredge Spoil	18.5	20.0	617.4	SM	23.5	5	20.0													28.60
134	E-9	SPT	Alluvium	23.5	25.0	617.4	SM	23.5	2														27.70
135	E-9	SPT	Alluvium	28.5	30.0	617.4	SM	23.5	3	45.5				95.8	38.7								28.00

Notes:


1. NA = Not Available, could not be measured due to the drilling method. NE = Not Encountered

2. Unit weights for CCR materials are included for reference only; they should not be used for design purposes. The samples were disturbed during recovery and transport, resulting in non-representative unit weight measurements.

Table 3: Summary of Geotechnical Material Properties

Material	Unit Weight (pcf)	Drained Strength		Undrained Strength	
		Effective Internal Friction	Effective Cohesion	Total Internal Friction	Total Cohesion
		ϕ' (°)	c' (psf)	ϕ (°)	c (psf)
Fill and Embankment Materials					
CCR-Soil Mix (Embankment)	100	30	0	-	-
CCR (Embankment)	85-100	30	0	-	-
Dredge Spoil	100	28	0	-	-
Earthfill	120	30	100	-	-
Coal Combustion Residuals					
CCR-Soil Mix (Impounded)	85-100	28	0	-	-
Sluiced CCR	75	28	0	-	-
Alluvium	105	32	0	0	21

Figures



- LEGEND**
- EXISTING CONTOURS
 - EXISTING ROADS
 - EXISTING FENCE
 - EXISTING UTILITY POLES
 - LIMITS OF BATHYMETRIC SURVEY
 - CROSS SECTION LOCATIONS
 - WSP BORING LOCATIONS (A-, B-, AND E- SERIES), 2025
 - AEP/EHS GEOPROBE LOCATIONS (SB-XX), 2025
 - AEP/EHS MONITORING WELLS (MW-25XXS), 2025
 - AEP/EHS PIEZOMETERS (SB-XX), 2025
 - APPROX. FORMER BACK CHANNEL

- REFERENCES**
- EXISTING TOPOGRAPHY, BATHYMETRY AND AERIAL IMAGERY PROVIDED BY AMERICAN ELECTRIC POWER.



DATE	NO.	DESCRIPTION	APPD.

REVISIONS

THIS DRAWING IS CLASSIFIED AS:


REFERENCE AEP's CORPORATE INFORMATION SECURITY POLICY

"THIS DRAWING IS THE PROPERTY OF THE **AMERICAN ELECTRIC POWER SERVICE CORP.** AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE **AEP SERVICE CORP.** OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST"

APPALACHIAN POWER COMPANY
CABIN CREEK ASH POND
CABIN CREEK WEST VIRGINIA

GEOTECHNICAL EXPLORATION LOCATIONS PLAN

UNIT: FEET	DRAWING NUMBER: 2 OF 5	REV: -
SCALE: 1" = 100'	APPROVED BY	
DR: CCP		
CH: NG		
SUP: NG		
ENG: SUM	DATE: 01/27/2026	
		AEP SERVICE CORP. 1 RIVERSIDE PLAZA COLUMBUS, OH 43215



LEGEND

- EXISTING CONTOURS
- EXISTING ROADS
- EXISTING FENCE
- EXISTING UTILITY POLES
- LIMITS OF BATHYMETRIC SURVEY
- WSP BORING LOCATIONS
- AEP/EHS GEOPROBE LOCATIONS

NOTES

1. THE BOTTOM OF THE CCR MATERIALS WAS DETERMINED BASED ON THE DEPTH TO THE UNDERLYING ALLUVIAL SOILS OR DREDGE SPOILS.

REFERENCES

1. EXISTING TOPOGRAPHY, BATHYMETRY AND AERIAL IMAGERY PROVIDED BY AMERICAN ELECTRIC POWER.



DATE	NO.	DESCRIPTION	APPD.
REVISIONS			
THIS DRAWING IS CLASSIFIED AS:			
REFERENCE AEP's CORPORATE INFORMATION SECURITY POLICY			



THIS DRAWING IS THE PROPERTY OF THE **AMERICAN ELECTRIC POWER SERVICE CORP.** AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE **AEP SERVICE CORP.** OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST.

APPALACHIAN POWER COMPANY
CABIN CREEK ASH POND
CABIN CREEK WEST VIRGINIA

ISOPACH MAP OF CCR THICKNESS

UNIT: FEET	DRAWING NUMBER: 4 OF 5	REV: -
SCALE: 1" = 100'		
DR: CCP	APPROVED BY	
CH: NG		
SUP: NG		
ENG: SUM		
DATE: 01/27/2026		
AEP SERVICE CORP. 1 RIVERSIDE PLAZA COLUMBUS, OH 43215		

CCR THICKNESS TABLE		
RANGE		COLOR
0.0' to 5.0'		Red
5.0' to 10.0'		Orange
10.0' to 15.0'		Yellow
15.0' to 20.0'		Light Green
20.0' to 25.0'		Green
25.0' to 30.0'		Light Blue
30.0' to 33.4'		Dark Blue



THIS DRAWING IS CLASSIFIED AS:

REFERENCE AEP's CORPORATE INFORMATION SECURITY POLICY

THIS DRAWING IS THE PROPERTY OF THE **AMERICAN ELECTRIC POWER SERVICE CORP.**, AND IS LOANED UPON CONDITION THAT IT IS NOT TO BE REPRODUCED OR COPIED, IN WHOLE OR IN PART, OR USED FOR FURNISHING INFORMATION TO ANY PERSON WITHOUT THE WRITTEN CONSENT OF THE **AEP SERVICE CORP.**, OR FOR ANY PURPOSE DETRIMENTAL TO THEIR INTEREST, AND IS TO BE RETURNED UPON REQUEST"

APPALACHIAN POWER COMPANY

CABIN CREEK ASH POND


CABIN CREEK WEST VIRGINIA

SUBSURFACE CROSS SECTIONS AND INTERPRETED STRATIGRAPHY

UNIT:	DRAWING NUMBER:	REV:
FEET	5 OF 5	-

SCALE: 1" = 100'	
DR: CCP	APPROVED BY
CH: NG	
SUP: NG	
ENG: SJM	
DATE: 01/27/2026	

**AEP AMERICAN
ELECTRIC
POWER**



3348 Peachtree Road NE
Suite 1100
Atlanta, GA 30326

AEP SERVICE CORP.
1 RIVERSIDE PLAZA
COLUMBUS, OH 43215

APPENDIX A

Site Reconnaissance Photo Log



	Project Name: AEP Cabin Creek	
	Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV	
	Client: AEP	Project Code: US0041868.3924
	Preparer: Naveen Kumar Ganji	Reviewer: Steven Moeller
	Report Date: 2025-12-08	Page Number: 1 of 28



Media 1: Road adjacent to the ash pond

Media 2: Drainage pipe from the former power plant area

Latitude: 38.1979
Longitude: -81.4823
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1982
Longitude: -81.4822
Bearing: SE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 2 of 28



Media 3: Potential drainage outlet pipe at the downstream toe of the perimeter dike



Media 4: Drainage way near perimeter dike

Latitude: 38.1982
Longitude: -81.4823
Bearing: SW

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1984
Longitude: -81.4826
Bearing: NW

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 3 of 28



Media 5: Floodplain area located to the east of the ash pond near the perimeter dike toe of slope

Media 6: Floodplain area located to the east of the ash pond near the perimeter dike toe of slope

Latitude: 38.1986
Longitude: -81.4828
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1987
Longitude: -81.4829
Bearing: SE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 4 of 28



Media 7: Perimeter dike at the northeast corner of the ash pond

Media 8: Erosion control measures on perimeter dike

Latitude: 38.1988
Longitude: -81.4831
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1988
Longitude: -81.4832
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 5 of 28



Media 9: Erosion control measures on perimeter dike



Media 10: Access road on the north side of the ash pond (top of ash pond)

Latitude: 38.1987
Longitude: -81.4833
Bearing: W

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1987
Longitude: -81.4834
Bearing: NW

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 6 of 28



Media 11: Top of ash pond looking from north to south



Media 12: Top of ash pond looking southwest

Latitude: 38.1986
Longitude: -81.4835
Bearing: S

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1986
Longitude: -81.4844
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 7 of 28



Media 13: Access road along the north side of the ash pond (top of ash pond)



Media 14: Access road along north side of ash pond (top of ash pond)

Latitude: 38.1987
Longitude: -81.4845
Bearing: W

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1986
Longitude: -81.4850
Bearing: W

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 8 of 28



Media 15: Looking north towards the Kanawha River down the perimeter dike (heavy vegetation)



Media 16: Top of ash pond looking from north to south

Latitude: 38.1986
Longitude: -81.4855
Bearing: N

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1984
Longitude: -81.4859
Bearing: S

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 9 of 28



Media 17: Looking north towards the Kanawha River down the perimeter dike (heavy vegetation)

Latitude: 38.1985
Longitude: -81.4862
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 18: Looking north towards the Kanawha River down the perimeter dike (heavy vegetation)

Latitude: 38.1983
Longitude: -81.4867
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 10 of 28



Media 19: Access road along the north side of the ash pond (top of ash pond)



Media 20: Top of ash pond looking from north to south

Latitude: 38.1982
Longitude: -81.4868
Bearing: W

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1981
Longitude: -81.4872
Bearing: SE

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji


Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 11 of 28



Media 21: Access road along the north side of the ash pond (top of ash pond)



Media 22: Looking up the perimeter dike slope from the Kanawha River (heavy vegetation)

Latitude: 38.1980
Longitude: -81.4876
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1983
Longitude: -81.4874
Bearing: S

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 12 of 28



Media 23: Perimeter dike at the northwest end of the ash pond



Media 24: Heavy vegetation is shown on the perimeter dike at the northwest end of the ash pond adjacent to the Kanawha River

Latitude: 38.1982
Longitude: -81.4877
Bearing: S

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1982
Longitude: -81.4877
Bearing: S

Weather: Patchy light rain with
thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP


Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 13 of 28



Media 25: Heavy vegetation shown on the perimeter dike at the northwest end of the ash pond adjacent to the Kanawha River

Latitude: 38.1982
Longitude: -81.4877
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 26: Floodplain area shown to the northwest of the ash pond

Latitude: 38.1979
Longitude: -81.4886
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 14 of 28



Media 27: Corrugated metal storm water pipe by the concrete outlet pipe



Media 28: Concrete spillway outlet pipe

Latitude: 38.1979
Longitude: -81.4884
Bearing: E

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1979
Longitude: -81.4884
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 15 of 28



Media 29: Corrugated metal storm drain outlet



Media 30: View of perimeter dike adjacent to the Kanawha River

Latitude: 38.1979
Longitude: -81.4884
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1979
Longitude: -81.4884
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP


Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 16 of 28



Media 31: Floodplain area adjacent to the ash pond (northwest end of ash pond)

Media 32: ATV trail on perimeter dike at the northwest end of the ash pond

Latitude: 38.1980
Longitude: -81.4882
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1980
Longitude: -81.4882
Bearing: E

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 17 of 28



Media 33: Perimeter dike at the northwest end of the ash pond



Media 34: Remnants of old concrete outlet structure used when the ash pond was active

Latitude: 38.1979
Longitude: -81.4880
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Latitude: 38.1979
Longitude: -81.4878
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 18 of 28



Media 35: Remnants of an old concrete outlet structure used when the ash pond was active



Media 36: Cleared area on the top of the ash pond with in-place erosion control measures (recently cleared)

Latitude: 38.1979
Longitude: -81.4878
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1979
Longitude: -81.4878
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 19 of 28



Media 37: Top of ash pond near the northwest corner of the pond

Media 38: Looking west to east on top of the ash pond (area recently cleared)

Latitude: 38.1976
Longitude: -81.4877
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1976
Longitude: -81.4877
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 20 of 28



Media 39: Looking northwest across the top of the ash pond towards the Kanawha River

Media 40: Looking northeast across the top of the ash pond

Latitude: 38.1973
Longitude: -81.4872
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1973
Longitude: -81.4872
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 21 of 28




Media 41: Looking southeast across the top of the ash pond towards the neighborhood to the south

Latitude: 38.1973
Longitude: -81.4872
Bearing: SE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 42: Top of concrete stormwater manhole. Access point for stormwater drainage pipes that traverse the ash pond

Latitude: 38.1970
Longitude: -81.4868
Bearing: S

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 22 of 28



Media 43: Top of concrete stormwater manhole. Access point for stormwater drainage pipes that traverse the ash pond

Latitude: 38.1970
Longitude: -81.4868
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 44: Top of concrete stormwater manhole. Access point for stormwater drainage pipes that traverse the ash pond

Latitude: 38.1969
Longitude: -81.4869
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 23 of 28



Media 45: Looking towards the northeast across the top of the ash pond (area recently cleared)

Latitude: 38.1969
Longitude: -81.4867
Bearing: N

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 46: Looking east along the top of the perimeter dike south of the ash pond

Latitude: 38.1969
Longitude: -81.4865
Bearing: E

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 24 of 28



Media 47: Looking west along the top of the perimeter dike south of the ash pond

Latitude: 38.1968
Longitude: -81.4858
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Media 48: Looking west along the top of the perimeter dike south of the ash pond

Latitude: 38.1968
Longitude: -81.4852
Bearing: W

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 25 of 28



Media 49: Looking east along the top of the perimeter dike south of the ash pond

Media 50: Looking south from the top of the perimeter dike, showing manhole location in the adjacent street

Latitude: 38.1969
Longitude: -81.4846
Bearing: E

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1974
Longitude: -81.4831
Bearing: SE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP


Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 26 of 28



Media 51: Splitter dike running through the middle of the ash pond

Media 52: Looking west on the south side of the ash pond

Latitude: 38.1974
Longitude: -81.4830
Bearing: NW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Latitude: 38.1975
Longitude: -81.4828
Bearing: NE

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller

Report Date: 2025-12-08

Page Number: 27 of 28



Media 53: South side of ash pond on top of perimeter dike looking west

Latitude: 38.1974
Longitude: -81.4829
Bearing: SW

Weather: Patchy light rain with thunder
Date Taken: 07/16/2025
Taken By: Naveen Kumar Ganji

Tags: NA



Project Name: AEP Cabin Creek

Project Location: Cabin Creek Ash Pond, Former Cabin Creek Power Plant, Cabin Creek, WV

Client: AEP

Project Code: US0041868.3924

Preparer: Naveen Kumar Ganji

Reviewer: Steven Moeller


Report Date: 2025-12-08

Page Number: 28 of 28

APPENDIX B

Previous Geotechnical Investigations

Plotted by: sfore
y:\sw_sa_042013\1_1_04-13-0198 aep-cabin creek site assessment\cadd\13-0198 potentio fig 5.dwg



TRIAD ENGINEERING, INC.
4980 TEAYS VALLEY ROAD
SCOTT DEPOT, WV 25560
PH: 304.755.0721 FAX: 304.755.1880

OFFICE LOCATIONS
MARYLAND • PENNSYLVANIA • VIRGINIA • WEST VIRGINIA • OHIO

CADD FILE: 13-0198 Potentio Fig 5.dwg	CHECKED BY: DS	SCALE: 1" = 60'
PROJECT No.: 04-13-0198	DRAWN BY: LA/SJF	DATE: 6/27/2013

AEP - CABIN CREEK SITE ASSESSMENT
CHELYAN, KANAWHA COUNTY, WV

05/01/13

**POTENTIOMETRIC
SURFACE MAP**



FIGURE No.:
5

PROJECT No.: 04-13-0198

Project Name: AEP Cabin Creek				BORING LOG SB1	
Project Number: 04-13-0198					
Depth, feet	Symbol/USCS	Location: Lithologic Description	PID (ppm)	Sample ID	Observations
		TOPSOIL	0.0	SS1 0-2 ft	
		black <u>COAL</u>	0.0		
			0.0		
		brown to black, sandy, silty, <u>CLAY</u> , moist	0.0		
5			0.0		
			0.0		
			0.0		
			0.0		
			0.0		
10		brown to black, sandy, <u>CLAY</u> , moist	0.0		
			0.0		
			0.0		
			0.0		
			0.0		
15		Boring terminated at 15.0	0.0	SB1 10-12 ft	
			0.0		
			0.0		
			0.0		
20					

Completion Depth:	15.00	Remarks: Subsurface Soil Sample Collected at: 0900
Date Started:	5/1/2013	
Date Completed:	5/1/2013	
Scientist:	BAF	
Driller:	Direct Push	

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB2		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0	SS2 0-2 ft	
		brown, sandy, <u>CLAY</u> , with coal		0.0		
				0.0		
				0.0		
				0.0		
5				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
10				0.0		
				0.0		
				0.0		
				0.0		
15		0.0				
		Boring terminated at 15.0		0.0	SB2 10-12 ft	
				0.0		
				0.0		
				0.0		
				0.0		
20				0.0		

Completion Depth:	15.00	Remarks: Subsurface Soil Sample Collected at: 0945
Date Started:	5/1/2013	
Date Completed:	5/1/2013	
Scientist	BAF	
Driller:	Direct Push	

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB3		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0	SB3 10-12 ft	
		black, sandy, <u>CLAY</u> , moist		0.0		
				0.0		
				2.0		
				0.0		
5				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
10				0.0		
				0.0		
				0.0		
				0.0		
15				0.0		
		Boring terminated at 15.0		0.0		
				0.0		
				0.0		
				0.0		
20				0.0		
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1000				
Date Started: 5/1/2013						
Date Completed: 5/1/2013						
Scientist: BAF						
Driller: Direct Push						

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB4	
Project Number: 04-13-0198					
Depth, feet	Symbol/USCS	Location: Lithologic Description	PID (ppm)	Sample ID	Observations
		TOPSOIL	0.0		
5		brown, silty, sandy, <u>CLAY</u>	0.0		
			0.0		
			0.0		
			0.0		
			0.0		
			0.0		
			0.0		
10			0.0		
			0.0	SB4 10-12 ft	
			0.0		
15		Boring terminated at 15.0	0.0		
			0.0		
			0.0		
			0.0		
			0.0		
20					
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1015			
Date Started: 5/1/2013					
Date Completed: 5/1/2013					
Scientist: BAF					
Driller: Direct Push					

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB5		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0	SS5 0-2 ft	
		brown to black, sandy, <u>CLAY</u> , moist		0.0		
				0.0		
				0.0		
				0.0		
5				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
10				0.0		
				0.0		
				0.0		
				0.0		
15		0.0				
		Boring terminated at 15.0		0.0	SB5 5-8 ft	
20						
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1100				
Date Started: 5/1/2013						
Date Completed: 5/1/2013						
Scientist: BAF						
Driller: Direct Push						

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB6		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0	SS6 0-2 ft	
		brown and black, sandy, <u>CLAY</u> , with rock fragments		0.0		
				0.0		
				0.0		
				0.0		
5				0.0		
				0.0		
				0.0		
				0.0		
10		black <u>SAND</u> , moist		0.0	petroleum-like odor	
				10.5		
				22.5		
				33.5		
				20.5		
15		Boring terminated at 15.0		15.0	SB6 13-15 ft	
20						
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1130				
Date Started: 5/1/2013						
Date Completed: 5/1/2013						
Scientist: BAF						
Driller: Direct Push						

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB7	
Project Number: 04-13-0198					
Depth, feet	Symbol/USCS	Location: Lithologic Description	PID (ppm)	Sample ID	Observations
		TOPSOIL	0.0	SS7 0-2 ft	
		brown, sandy, <u>CLAY</u>	0.0		
			0.0		
			0.0		
5			0.0		
			0.0		
		black and brown, sandy, <u>CLAY</u> , with rock and brick fragments	0.0		
			0.0		
			0.0		
10			0.0		
			0.0		
		Boring terminated at 15.0	0.0	SB7 13-15 ft	
			0.0		
			0.0		
15			0.0		
			0.0		
20					

Completion Depth:	15.00	Remarks: Subsurface Soil Sample Collected at: 1115
Date Started:	5/1/2013	
Date Completed:	5/1/2013	
Scientist	BAF	
Driller:	Direct Push	

The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG SB8		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0		
		GRAVEL				
5		brown, sandy, <u>CLAY</u> , moist		0.0	SB8 13-15 ft	
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
10				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
15				0.0		
		Boring terminated at 15.0		0.0		
20						

Completion Depth:	15.00	Remarks: Subsurface Soil Sample Collected at: 1200
Date Started:	5/1/2013	
Date Completed:	5/1/2013	
Scientist	BAF	
Driller:	Direct Push	


The stratification lines represent approximate strata boundaries.
 Transition may be gradual.


Project Name: AEP Cabin Creek				BORING LOG SB9		
Project Number: 04-13-0198						
Depth, feet	Symbol/USCS	Location:		PID (ppm)	Sample ID	Observations
		Lithologic Description				
		TOPSOIL		0.0	SB9 13-15 ft	
		black, sandy, <u>CLAY</u>		0.0		
				0.0		
				0.0		
				0.0		
5				0.0		
				0.0		
				0.0		
				0.0		
				0.0		
10				0.0		
				0.0		
				0.0		
				0.0		
15		0.0				
		Boring terminated at 15.0		0.0		
20						
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1330				
Date Started: 5/1/2013						
Date Completed: 5/1/2013						
Scientist: BAF						
Driller: Direct Push						



The stratification lines represent approximate strata boundaries.
Transition may be gradual.



Project Name: AEP Cabin Creek				BORING LOG SB10	
Project Number: 04-13-0198					
Depth, feet	Symbol/USCS	Location: Lithologic Description	PID (ppm)	Sample ID	Observations
		TOPSOIL	0.0	SS10 0-2 ft	
		brown to black, sandy, <u>CLAY</u>	0.0		
			0.0		
			0.0		
5			0.0		
			0.0		
			0.0	SB10 6-8 ft	
			0.0		
			0.0		
10			0.0		
			0.0		
			0.0		
			0.0		
15			Boring terminated at 15.0	0.0	
20					
Completion Depth: 15.00		Remarks: Subsurface Soil Sample Collected at: 1400			
Date Started: 5/1/2013					
Date Completed: 5/1/2013					
Scientist: BAF					
Driller: Direct Push					




The stratification lines represent approximate strata boundaries.
Transition may be gradual.

Project Name: AEP Cabin Creek				BORING LOG	
Project Number: 04-05-0370				RW- 6	
Depth, feet	Symbol / USCS	Location: 38 11' 51.86"N 81 28' 49.39"W Well Elev.: 502.0 ft.	PID Reading	Sample I.D.	Well Registration Number:
		MATERIAL DESCRIPTION			Well Construction
5		FLY ASH and GRAVEL 5.0		No odor observed	
10		FLY ASH 20.0			
20		Greyish brown <u>SANDY CLAY</u> , very moist 25.0			
25		Bottom of Test Boring at 25.0 ft.			
35					
Completion Depth: 25.0 ft.		Remarks: Water was noted at a depth of 23.5 ft. below the ground surface upon drilling completion. ND - Not Detected (Absence of analytical data indicates sample was not tested.)			
Date Boring Started: 1/10/06					
Date Boring Completed: 1/10/06					
Engineer/Geologist: SLC					
Driller: Triad					

Project Name: AEP Cabin Creek				BORING LOG	
Project Number: 04-05-0370				RW- 8	
Depth, feet	Symbol / USCS	Location: 38 11' 50.91"N 81 28' 48.29"W Well Elev.: 501.0 ft.	PID Reading	Sample I.D.	Well Registration Number:
		MATERIAL DESCRIPTION			Well Construction
5		FLY ASH and GRAVEL 1.0		No odor observed	
		Brown <u>SANDY CLAY</u> , moist - greyish brown and very moist at 5 ft.			
		10.0			
		10			
15		Bottom of Test Boring at 27.0 ft.			
20					
25					
35					
Completion Depth: 27.0 ft.		Remarks: Water was noted at a depth of 13.5 ft. below the ground surface upon drilling completion. ND - Not Detected (Absence of analytical data indicates sample was not tested.)			
Date Boring Started: 1/10/06					
Date Boring Completed: 1/10/06					
Engineer/Geologist: SLC					
Driller: Triad					

Project Name: AEP Cabin Creek				BORING LOG	
Project Number: 04-05-0370				RW- 9	
Depth, feet	Symbol / USCS	Location: 38 11' 51.14"N 81 28' 50.27"W Well Elev.: 501.5 ft.	PID Reading	Sample I.D.	Well Registration Number:
		MATERIAL DESCRIPTION			Well Construction
5		FLY ASH and GRAVEL, moist - with some sand, very moist			
10		10.0			
15		Grey <u>SANDY CLAY</u> , very moist - wet at 18 ft. - brown at 20 ft.		Strong diesel odor	
20					
25		27.0		Diesel odor	
30					
35		Bottom of Test Boring at 27.0 ft.			
Completion Depth: 27.0 ft.		Remarks: Water was noted at a depth of 15.8 ft. below the ground surface upon drilling completion. ND - Not Detected (Absence of analytical data indicates sample was not tested.)			
Date Boring Started: 1/10/06					
Date Boring Completed: 1/10/06					
Engineer/Geologist: SLC					
Driller: Triad					

Project Name: AEP Cabin Creek				BORING LOG	
Project Number: 04-05-0370				RW-10	
Depth, feet	Symbol / USCS	Location: 38 11' 50.86"N 81 28' 49.54"W Well Elev.: 505.7 ft.	PID Reading	Sample I.D.	Well Registration Number:
		MATERIAL DESCRIPTION			Well Construction
5		FLY ASH and GRAVEL 2.0			
		FLY ASH 6.0			
		Grey <u>SANDY CLAY</u> and <u>GRAVEL</u> , wet			
		- brown at 12.0 ft.			
		18.0			
20		Grey <u>SILTY TO SANDY CLAY</u> , very moist			
		33.0			
		Bottom of Test Boring at 33.0 ft.			
Completion Depth: 33.0 ft.		Remarks: Water was noted at a depth of 8.5 ft. below the ground surface upon drilling completion. ND - Not Detected (Absence of analytical data indicates sample was not tested.)			
Date Boring Started: 1/9/06					
Date Boring Completed: 1/9/06					
Engineer/Geologist: SLC					
Driller: Triad					

Project Name: AEP Cabin Creek				BORING LOG		
Project Number: 04-05-0370				RW-13		
Depth, feet	Symbol / USCS	Location: 38 11' 49.96"N 81 28' 49.38"W Well Elev.: 503.0 ft.	PID Reading	Sample I.D.	Well Registration Number:	
		MATERIAL DESCRIPTION				Well Construction
5		FLY ASH and GRAVEL				
7.0						
10		Dark grey <u>SANDY CLAY</u> , moist		Strong diesel odor		
15						
20						
23		- brown and very moist at 23 ft.				
25						
25.0						
		Bottom of Test Boring at 25.0 ft.				
35						

Completion Depth: **25.0 ft.**

Date Boring Started: **1/10/06**


Date Boring Completed: **1/10/06**

Engineer/Geologist: **SLC**

Driller: **Triad**

Remarks: **Water was noted at a depth of 13.7 ft. below the ground surface upon drilling completion.**

ND - Not Detected
(Absence of analytical data indicates sample was not tested.)

Project Name: AEP Cabin Creek				BORING LOG	
Project Number: 04-05-0370				RW-14	
Depth, feet	Symbol / USCS	Location: 38 11' 50.38"N 81 28' 49.91"W Well Elev.: 502.3 ft.	PID Reading	Sample I.D.	Well Registration Number:
		MATERIAL DESCRIPTION			Well Construction
5		FLY ASH 1.0			
		Dark brown <u>SILTY TO SANDY CLAY</u> , moist			
		- very moist at 7 ft.			
10					
15					
		18.0			
20		Grey <u>SANDY CLAY</u> , very moist 20.0		Strong petroleum odor	
		Brown <u>SANDY CLAY</u> , moist			
25					
		27.0			
		Bottom of Test Boring at 27.0 ft.			
35					

Completion Depth:	27.0 ft.	Remarks: Water was noted at a depth of 12.5 ft. below the ground surface upon drilling completion. ND - Not Detected (Absence of analytical data indicates sample was not tested.)
Date Boring Started:	1/9/06	
Date Boring Completed:	1/9/06	
Engineer/Geologist:	SLC	
Driller:	Triad	

APPENDIX A

SUBSURFACE EXPLORATION DATA

Subsurface Exploration Procedures
General Notes for Subsurface Exploration Logs
Identification of Soil
Boring Logs, B-03, B-05, and B-06

SUBSURFACE EXPLORATION PROCEDURES

Test Borings – Hollow Stem Augers

The borings are advanced by turning a continuous flight auger with a center opening of 2¼ or 3¼ inches. A plug device blocks off the center opening while augers are advanced. Cuttings are brought to the surface by the auger flights. Sampling is performed through the center opening in the hollow stem auger, by standard methods, after removal of the plug. Usually, no water is introduced into the boring using this procedure.

Standard Penetration Test Results

The numbers in the Sampling Data column of the boring logs represent Standard Penetration Test (SPT) results. Each number represents the blows needed to drive a 2-inch O.D., 1⅝-inch I.D. split-spoon sampler 6 inches, using a 140-pound hammer falling 30 inches. The sampler is typically driven a total of 18 or 24 inches. The first 6 inches are considered a seating interval. The total of the number of blows for the second and third 6-inch intervals is the SPT “N-value.” The SPT is performed according to ASTM D1586.

The SPT samples were obtained using a hydraulically driven automatic trip hammer (ATH). Most correlations with SPT data are based on N-values collected with a safety hammer. The energy applied to the split-spoon sampler using the ATH is about 30 percent greater than that applied using the safety hammer, resulting in lower N-values. The hammer blows shown on the boring logs are uncorrected for the higher energy. However, we correct SPT N-values for the higher energy when using N-values in our analyses.

Soil Classification Criteria

The group symbols on the logs represent the Unified Soil Classification System Group Symbols (ASTM D2487) based on visual observation and limited laboratory testing of the samples. Criteria for visual identification of soil samples are included in this appendix. Some variation can be expected between samples visually classified and samples classified in the laboratory.

Residual soils are derived through the in-place physical and chemical weathering of the underlying rock. Disintegrated rock is defined as residual material with SPT N-values between 60 blows per foot and refusal. Refusal is defined as an N-value of 50 blows for a penetration of one inch or less.

Pocket Penetrometer Results

The values following “PP=” in the sampling data column of the logs represent pocket penetrometer readings. Pocket penetrometer readings provide an estimate of the unconfined compressive strength of fine-grained soils.

Boring Locations and Elevations

Boring locations were staked and collected after drilling using sub-meter GPS equipment. Approximate boring locations are shown on Figures 2 and 3. Ground surface elevations at the boring locations were provided by AEP and are indicated on the boring logs. Locations and elevations should be considered no more accurate than the methods used to determine them.

GENERAL NOTES FOR SUBSURFACE EXPLORATION LOGS

1. Numbers in sampling data column next to Standard Penetration Test (SPT) symbols indicate blows required to drive a 2-inch O.D., 1½-inch I.D. sampling spoon 6 inches using a 140 pound hammer falling 30 inches. The Standard Penetration Test (SPT) N-value is the number of blows required to drive the sampler 12 inches, after a 6 inch seating interval. The Standard Penetration Test is performed in general accordance with ASTM D1586.
2. Visual classification of soil is in accordance with terminology set forth in "Identification of Soil." The ASTM D2487 group symbols (e.g., CL) shown in the classification column are based on visual observations.
3. Estimated water levels indicated on the logs are only estimates from available data and may vary with precipitation, porosity of the soil, site topography, and other factors.
4. Refusal at the surface of rock, boulder, or other obstruction is defined as an SPT resistance of 50 blows for 1 inch or less of penetration.
5. The logs and related information depict subsurface conditions only at the specific locations and at the particular time when drilled or excavated. Soil conditions at other locations may differ from conditions occurring at these locations. Also, the passage of time may result in a change in the subsurface soil and water level conditions at the subsurface exploration location.
6. The stratification lines represent the approximate boundary between soil and rock types as obtained from the subsurface exploration. Some variation may also be expected vertically between samples taken. The soil profile, water level observations and penetration resistances presented on these logs have been made with reasonable care and accuracy and must be considered only an approximate representation of subsurface conditions to be encountered at the particular location.
7. Key to symbols and abbreviations:



S-1, SPT
5+10+1

Sample No., Standard Penetration Test
Number of blows in each 6-inch increment



UD-1, UNDIST
Rec=24", 100%

Sample No., 2" or 3" Undisturbed Tube Sample
Recovery in inches, Percent Recovery

LL

Liquid Limit

MC

Moisture Content (percent)

PL

Plastic Limit

PP

Pocket Penetrometer Reading (tsf)

%Passing#200

Percent by weight passing a No. 200 Sieve

IDENTIFICATION OF SOIL

I. DEFINITION OF SOIL GROUP NAMES (ASTM D2487)

SYMBOL GROUP NAME

Coarse-Grained Soils More than 50% retained on No. 200 sieve	Gravels – More than 50% of coarse fraction retained on No. 4 sieve Coarse, ¾" to 3" Fine, No. 4 to ¾"	Clean Gravels Less than 5% fines	GW	WELL GRADED GRAVEL
			GP	POORLY GRADED GRAVEL
		Gravels with fines More than 12% fines	GM	SILTY GRAVEL
			GC	CLAYEY GRAVEL
	Sands – 50% or more of coarse Fraction passes No. 4 sieve Coarse, No. 10 to No. 4 Medium, No. 40 to No. 10 Fine, No. 200 to No. 40	Clean Sands Less than 5% fines	SW	WELL GRADED SAND
			SP	POORLY GRADED SAND
		Sands with fines More than 12% fines	SM	SILTY SAND
			SC	CLAYEY SAND
Fine-Grained Soils 50% or more passes the No. 200 sieve	Silts and Clays – Liquid Limit less than 50 Low to medium plasticity	Inorganic	CL	LEAN CLAY
			ML	SILT
		Organic	OL	ORGANIC CLAY ORGANIC SILT
			Silts and Clays – Liquid Limit 50 or more Medium to high plasticity	Inorganic
	MH	ELASTIC SILT		
	Organic	OH		ORGANIC CLAY ORGANIC SILT
		Highly Organic Soils		Primarily organic matter, dark in color and organic odor

II. DEFINITION OF SOIL COMPONENT PROPORTIONS (ASTM D2487)

Examples

Adjective Form	GRAVELLY SANDY	>30% to <50% coarse grained component in a fine-grained soil	GRAVELLY LEAN CLAY
	CLAYEY SILTY	>12% to <50% fine grained component in a coarse-grained soil	SILTY SAND
"With"	WITH GRAVEL WITH SAND	>15% to <30% coarse grained component in a fine-grained soil	FAT CLAY WITH GRAVEL
	WITH GRAVEL WITH SAND	>15% to <50% coarse grained component in a coarse-grained soil	POORLY GRADED GRAVEL WITH SAND
	WITH SILT WITH CLAY	>5% to <12% fine grained component in a coarse-grained soil	POORLY GRADED SAND WITH SILT

III. GLOSSARY OF MISCELLANEOUS TERMS

SYMBOLS	Unified Soil Classification Symbols are shown above as group symbols. A dual symbol "-" indicates the soil belongs to two groups. A borderline symbol "/" indicates the soil belongs to two possible groups.
FILL	Man-made deposit containing soil, rock and often foreign matter.
PROBABLE FILL	Soils which contain no visually detected foreign matter but which are suspect with regard to origin.
DISINTEGRATED ROCK (DR)	Residual materials with a standard penetration resistance (SPT) between 60 blows per foot and refusal. Refusal is defined as an SPT of 100 blows for 2" or less penetration.
BOULDERS & COBBLES	Boulders are considered rounded pieces of rock larger than 12 inches, while cobbles range from 3 to 12-inch size.
LENSES	0 to ½-inch seam within a material in a test pit.
LAYERS	½ to 12-inch seam within a material in a test pit.
POCKET	Discontinuous body within a material in a test pit.
MOISTURE CONDITIONS	Wet, moist or dry to indicate visual appearance of specimen.
COLOR	Overall color, with modifiers such as light to dark or variation in coloration.

**TEST
BORING
LOG****Project:** AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia**Boring Number:** **B-03**
Contract Number: 19C16020.00
Sheet: 1 of 3

Contractor: Total Depth Drilling, Inc
Knoxville, Tennessee

Contractor Foreman: J. Chambliss

Schnabel Representative: John Krell

Equipment: CME-550X (ATV)

Method: 3-1/4" ID Hollow Stem Auger

Hammer Type: Auto Hammer (140 lb)

Dates Started: 8/21/19 **Finished:** 8/21/19

Latitude: 38.20231° **Longitude:** -81.47789°

Coordinate System: Lat-Long (Decimal Degrees)

Plunge: -90 **Bearing:**

Ground Surface Elevation: 644± (ft) **Total Depth:** 80.0 ft

Water Level Observations

	Date	Time	Depth	Casing	Caved
Encountered	8/21	---	58.5'	60.0'	---
Completion	8/21	---	58.5'	80.0'	---
Casing Pulled	8/21	---	57.0'	---	71.0'

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
					DEPTH	DATA		
	FILL, sampled as silty sand with gravel, fine to coarse; moist, black and brown, contains coal fragments, loose to medium dense, (mine spoil fill, material mostly comprised of coal and shale fragments)			A	5	S-01, SPT 1+1+3 REC=12", 67%	MC = 13.0%	Fill
						S-02, SPT 3+5+5 REC=12", 67%	MC = 5.6%	
						S-03, SPT 3+3+4 REC=12", 67%	MC = 25.0%	
						S-04, SPT 3+3+6 REC=12", 67%	MC = 16.1%	
						S-05, SPT 3+5+5 REC=15", 83%	MC = 11.1%	
						S-06, SPT 2+3+2 REC=12", 67%	MC = 10.7%	
					10	S-07, SPT 2+2+2 REC=6", 33%	MC = 13.3%	
					15	S-08, SPT 2+3+3 REC=15", 83%	MC = 17.0% % Passing #200 = 31.3	
				A	20	S-09, SPT 3+4+3 REC=12", 67%	MC = 15.0%	
						S-10, SPT 4+6+7 REC=18", 100%	MC = 17.9%	

(continued)



Schnabel
ENGINEERING

**TEST
BORING
LOG**

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia

Boring Number: **B-03**
Contract Number: 19C16020.00
Sheet: 2 of 3

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRATUM	SAMPLING DEPTH	DATA	TESTS	REMARKS
	FILL, sampled as silty sand with gravel, fine to coarse; moist, black and brown, contains coal fragments, loose to medium dense, (mine spoil fill, material mostly comprised of coal and shale fragments) <i>(continued)</i>	FILL		A				Fill
29.5	SANDY LEAN CLAY; moist, gray, contains root fragments, and mica, medium stiff, potential old topsoil layer	CL	614.0		30	S-11, SPT 2+4+2 REC=18", 100%	MC = 25.3%	Alluvial
32.0	LEAN CLAY WITH SAND; moist, brown, contains mica, stiff		611.5					
					35	S-12, SPT 4+4+5 REC=18", 100%	MC = 21.2% PP = 3.00 tsf	
						ST-1, UNDIST REC=24", 100%	LL = 32 PL = 22 MC = 22.7% % Passing #200 = 84.5 PP = 2.50 tsf MC = 22.4% PP = 2.50 tsf	
					40	S-13, SPT 3+3+4 REC=18", 100%		
		CL						
	Change: medium stiff, 3" pocket of clayey sand at 44.5			B	45	S-14, SPT 1+3+3 REC=18", 100%	MC = 26.2% PP = 2.00 tsf	
					50	S-15, SPT WOH+1+3 REC=18", 100%	MC = 23.0% PP = 1.50 tsf	
52.0	SANDY SILTY CLAY; moist to wet, brown, contains mica, very soft		591.5					
					55	S-16, SPT WOH/18" REC=18", 100%	LL = 25 PL = 20 MC = 22.2% % Passing #200 = 60.6 PP = 1.00 tsf	
	Change: no recovery	CL-ML				ST-2, UNDIST REC=0", 0%		Shelby tube pushed under weight of rods for 12"

(continued)

TEST BORING LOG AEP WO 42703738-02 BORING LOGS.GPJ SCHNABEL DATA TEMPLATE 2008 07_06.GDT 9/23/19



Schnabel
ENGINEERING

**TEST
BORING
LOG**

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia

Boring Number: **B-03**

Contract Number: 19C16020.00
Sheet: 3 of 3

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
					DEPTH	DATA		
59.0	CLAYEY SAND, fine; wet, brown, contains mica, loose, (sampler full of material, indicative of heaving sands) Change: gray, few gravel	SC	584.5	B	60	S-17, SPT WOH/12"+3 REC=18", 100%	MC = 22.0%	Heaving sands noted in augers; attempting to auger without center bit to prevent sandlock Alluvial Approx. 2 ft of heaving sand in auger, resuming use of center bit to advance boring
					65	S-18, SPT WOH+1+2 REC=18", 100%	MC = 23.8%	
					70	S-19, SPT 1+2+6 REC=18", 100%	MC = 32.6%	
72.0	SILTY SAND WITH GRAVEL, fine to coarse; wet, brown, contains mica, medium dense Change: may contain shell fragments	SM	571.5		75	S-20, SPT 10+8+9 REC=12", 67%	MC = 12.4% % Passing #200 = 18.0	
80.0			563.5		80	S-21, SPT 6+11+7 REC=18", 100%	MC = 15.0%	

Bottom of Boring at 80.0 ft.
Boring terminated at selected depth.
Boring backfilled with cuttings upon completion.

**TEST
BORING
LOG****Project:** AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia**Boring Number:** B-05
Contract Number: 19C16020.00
Sheet: 1 of 3

Contractor: Total Depth Drilling, Inc
Knoxville, Tennessee

Contractor Foreman: D. Hamilton

Schnabel Representative: John Krell

Equipment: CME-75 (Truck)

Method: 3-1/4" ID Hollow Stem Auger

Hammer Type: Auto Hammer (140 lb)

Dates Started: 8/20/19 **Finished:** 8/20/19

Latitude: 38.19951° **Longitude:** -81.47603°


Coordinate System: Lat-Long (Decimal Degrees)

Plunge: -90 **Bearing:**

Ground Surface Elevation: 625± (ft) **Total Depth:** 59.9 ft

Water Level Observations

	Date	Time	Depth	Casing	Caved
Encountered	8/20	---	34.5'	35.0'	---
Completion	8/20	---	34.0'	59.9'	---
Casing Pulled	8/20	---	33.0'	---	35.0'

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
					DEPTH	DATA		
0.2	Topsoil SANDY SILT; moist, brown and gray, contains mica, medium stiff to very stiff	 ML	624.5	B	5	S-01, SPT 9+7+9 REC=15", 83% S-02, SPT 5+5+5 REC=18", 100% S-03, SPT 2+4+4 REC=18", 100% S-04, SPT 3+4+5 REC=18", 100% S-05, SPT 3+3+4 REC=15", 83% S-06, SPT 1+2+2 REC=18", 100% S-07, SPT 1+2+3 REC=18", 100%	MC = 15.6% PP >4.50 tsf MC = 14.9% MC = 17.6% PP = 2.50 tsf MC = 17.3% PP = 2.50 tsf MC = 17.1% PP = 2.75 tsf LL = 23 PL = 21 MC = 18.9% % Passing #200 = 63.2 PP = 2.00 tsf MC = 20.7% PP = 3.00 tsf	Alluvial
					10	S-08, SPT 1+2+3 REC=18", 100%	MC = 19.0%	
17.0	SANDY SILTY CLAY; moist, brown, contains mica, medium stiff		607.7		20	S-09, SPT 1+2+3 REC=18", 100%	MC = 21.0% PP = 2.00 tsf	
						ST-1, UNDIST REC=24", 100%	LL = 27 PL = 20 MC = 20.8% % Passing #200 = 57.8 PP = 2.50 tsf MC = 19.6% PP = 1.00 tsf	
23.5	CLAYEY SAND, fine; moist, brown, contains mica, loose		601.2			S-10, SPT WOH+3+3 REC=18", 100%		

(continued)

TEST BORING LOG AEP WO 42703738-02 BORING LOGS.GPJ SCHNABEL DATA TEMPLATE 2008 07_06.GDT 9/23/19



Schnabel
ENGINEERING

**TEST
BORING
LOG**

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia

Boring Number: **B-05**

Contract Number: 19C16020.00
Sheet: 2 of 3

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
					DEPTH	DATA		
27.0	CLAYEY SAND, fine; moist, brown, contains mica, loose <i>(continued)</i>	SC	597.7					Alluvial
	SILTY SAND, fine; moist, brown, contains mica, trace gravel, loose				30	S-11, SPT 3+4+3 REC=18", 100%	MC = 15.3%	
	Change: wet, medium dense	SM			35	S-12, SPT 5+5+5 REC=18", 100%	MC = 26.0% % Passing #200 = 34.0	
	Change: brown and black, few gravel, dense				40	S-13, SPT 7+11+18 REC=18", 100%	MC = 20.4%	
42.0	POORLY GRADED SAND WITH GRAVEL, fine to coarse; wet, brown and black, contains mica, medium dense		582.7	B	45	S-14, SPT WOH+2+9 REC=18", 100%	MC = 21.7%	
	Change: no gravel	SP			50	S-15, SPT 7+5+6 REC=9", 50%	MC = 26.1%	
	Change: loose				55	S-16, SPT WOH/12"+3 REC=5", 28%	MC = 30.6%	

(continued)

TEST BORING LOG AEP WO 42703738-02 BORING LOGS.GPJ SCHNABEL DATA TEMPLATE 2008 07_06.GDT 9/23/19



Schnabel
ENGINEERING

**TEST
BORING
LOG**

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia

Boring Number: **B-05**
Contract Number: 19C16020.00
Sheet: 3 of 3

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL		ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
						DEPTH	DATA		
59.5	Change: dark brown, few gravel, dense	SP		565.2	B		S-17, SPT 10+18+50/5" REC=17", 100%	MC = 10.5%	Alluvial
59.9	DISINTEGRATED ROCK, sampled as poorly graded sand with gravel, fine to coarse; wet, mottled light brown and gray, contains mica, very dense	DR		564.8	C				Residual
Bottom of Boring at 59.9 ft. Boring terminated at selected depth. Boring backfilled with cuttings upon completion. Offset approximately 5 ft east of proposed location for access issues (clearing, working space).									

**TEST
BORING
LOG****Project:** AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, West Virginia**Boring Number:** B-06
Contract Number: 19C16020.00
Sheet: 1 of 2**Contractor:** Total Depth Drilling, Inc
Knoxville, Tennessee**Contractor Foreman:** T. Hall**Schnabel Representative:** John Krell**Equipment:** CME-75 (Truck)**Method:** 3-1/4" ID Hollow Stem Auger**Hammer Type:** Auto Hammer (140 lb)**Dates Started:** 8/20/19 **Finished:** 8/20/19**Latitude:** 38.19960° **Longitude:** -81.47599°**Coordinate System:** Lat-Long (Decimal Degrees)**Plunge:** -90**Bearing:****Ground Surface Elevation:** 624± (ft) **Total Depth:** 55.0 ft**Water Level Observations**

	Date	Time	Depth	Casing	Caved
Encountered	8/20	---	34.0'	35.0'	---
Completion	8/20	---	34.0'	55.0'	---
Casing Pulled	8/20	---	32.0'	---	34.0'

DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING		TESTS	REMARKS
					DEPTH	DATA		
0.4	Topsoil		623.6			S-01, SPT WOH+2+4 REC=10", 56%	MC = 12.8%	Alluvial
	SANDY LEAN CLAY; moist, brown, contains root fragments, and mica, medium stiff to stiff Change: root in shoe of sampler likely cause of low recovery	CL				S-02, SPT 5+5+6 REC=3", 17%	MC = 25.4%	
3.0			621.0			S-03, SPT 3+5+4 REC=18", 100%	MC = 16.3% PP = 2.50 tsf	
	SILTY SAND, fine; moist, brown, contains mica, loose to medium dense	SM			5	S-04, SPT 4+5+5 REC=18", 100%	LL = NP MC = 15.0% % Passing #200 = 44.5	
						S-05, SPT 3+5+5 REC=18", 100%	PP = 2.00 tsf MC = 17.9%	
						S-06, SPT 3+3+3 REC=18", 100%	MC = 18.3% PP = 2.50 tsf	
					10	S-07, SPT 1+4+3 REC=6", 33%	MC = 17.6%	
12.0	SANDY SILT; moist, brown, contains mica, medium stiff	ML	612.0	B		S-08, SPT 2+3+3 REC=18", 100%	LL = 21 PL = 18 MC = 19.1% % Passing #200 = 56.1 PP = 2.00 tsf	
					15			
					20	S-09, SPT WOH+1+3 REC=18", 100%	MC = 20.8%	
22.0	CLAYEY SAND, fine; moist, brown, contains mica, medium dense	SC	602.0					
						S-10, SPT 3+5+4 REC=18", 100%	MC = 16.4% PP = 2.00 tsf	

(continued)

TEST BORING LOG AEP WO 42703738-02 BORING LOGS.GPJ SCHNABEL DATA TEMPLATE 2008 07_06.GDT 9/23/19



DEPTH (ft)	MATERIAL DESCRIPTION	SYMBOL	ELEV (ft)	STRA TUM	SAMPLING DEPTH	DATA	TESTS	REMARKS
	CLAYEY SAND, fine; moist, brown, contains mica, medium dense (continued)							Alluvial
	Change: recovery, N-value indicative of sampling on gravel/cobble	SC			30	S-11, SPT 8+10+13 REC=4", 22%	MC = 16.6%	
34.0	POORLY GRADED SAND WITH CLAY, fine to medium; wet, brown and black, contains mica, medium dense	SP-SC	590.0		35	S-12, SPT 9+5+7 REC=18", 100%	MC = 24.6%	
39.0	POORLY GRADED GRAVEL WITH SAND, fine to coarse; wet, brown, contains mica, dense	GP	585.0	B	40	S-13, SPT 4+8+16 REC=15", 83%	MC = 15.7%	
42.0	SILTY SAND, fine to medium; wet, brown, few gravel, contains mica, medium dense	SM	582.0		45	S-14, SPT 7+7+7 REC=18", 100%	MC = 18.8% % Passing #200 = 23.5	
					50	S-15, SPT 6+5+7 REC=18", 100%	MC = 26.7%	thin (~1" to 2") layers of alternating colors (light brown, to reddish brown, to dark brown, to light brown, etc.)
52.0	POORLY GRADED SAND WITH GRAVEL, fine to coarse; wet, light brown, contains mica, dense	SP	572.0			S-16, SPT 4+11+11 REC=18", 100%	MC = 18.0%	
55.0			569.0		55			
Bottom of Boring at 55.0 ft. Boring terminated at selected depth. Boring backfilled with cuttings upon completion.								

APPENDIX B

LABORATORY TEST DATA

Summary of Laboratory Tests (2 pages)

Atterberg Limits (1 page)

Gradation Curves (10 pages)

Soil UCS Test Reports (2 pages)

Summary Of Laboratory Tests

Appendix
Sheet 1 of 2
Project Number: 19C16020.00

Boring No.	Sample Depth ft Elevation ft	Sample Type	Description of Soil Specimen	Wet Natural Density (pcf)	Natural Moisture (%)	Liquid Limit	Plasticity Index	% Passing No. 200 Sieve	Percent Sand	Percent Gravel	Testing Laboratory
B-03	13.5 - 15.0	Jar	SILTY SAND WITH GRAVEL (SM), f-c, black (Visual Class., Sample consists of coal and shale fragments)	--	17.0	--	--	31.3	46.8	21.9	BLAC
	630.0 - 628.5										
B-03	36.0 - 38.0	Tube	LEAN CLAY WITH SAND (CL), contains mica, brown	128.3	22.7	32	10	84.5	15.5	0.0	BLAC
	607.5 - 605.5										
B-03	53.5 - 55.0	Jar	SANDY SILTY CLAY (CL-ML), contains mica, brown	--	22.2	25	5	60.6	39.4	0.0	BLAC
	590.0 - 588.5										
B-03	73.5 - 75.0	Jar	SILTY SAND WITH GRAVEL (SM), fine to coarse, contains mica, brown (Visual Classification)	--	12.4	--	--	18.0	53.2	28.8	BLAC
	570.0 - 568.5										
B-05	7.5 - 9.0	Jar	SANDY SILT (ML), contains mica, brown	--	18.9	23	2	63.2	36.8	0.0	BLAC
	617.2 - 615.7										
B-05	21.0 - 23.0	Tube	SANDY SILTY CLAY (CL-ML), contains mica, brown	128.8	20.8	27	7	57.8	42.2	0.0	BLAC
	603.7 - 601.7										
B-05	33.5 - 35.0	Jar	SILTY SAND (SM), fine, trace gravel, contains mica, brown (Visual Classification)	--	26.0	--	--	34.0	65.9	0.1	BLAC
	591.2 - 589.7										

Notes:

1. Soil tests in general accordance with ASTM standards.
2. Soil classifications are in general accordance with ASTM D2487(as applicable), based on testing indicated and visual classification.
3. Key to abbreviations: NP=Non-Plastic; -- indicates no test performed



Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Summary Of Laboratory Tests

Appendix
Sheet 2 of 2
Project Number: 19C16020.00

Boring No.	Sample Depth ft	Sample Type	Description of Soil Specimen	Wet Natural Density (pcf)	Natural Moisture (%)	Liquid Limit	Plasticity Index	% Passing No. 200 Sieve	Percent Sand	Percent Gravel	Testing Laboratory
	Elevation ft										
B-06	4.5 - 6.0	Jar	SILTY SAND (SM), fine, contains mica, brown	--	15.0	NP	NP	44.5	55.5	0.0	BLAC
	619.5 - 618.0										
B-06	13.5 - 15.0	Jar	SANDY SILT (ML), contains mica, brown	--	19.1	21	3	56.1	43.9	0.0	BLAC
	610.5 - 609.0										
B-06	43.5 - 45.0	Jar	SILTY SAND (SM), fine to medium, few gravel, contains mica, brown (Visual Classification)	--	18.8	--	--	23.5	65.9	10.6	BLAC
	580.5 - 579.0										


- Notes:
1. Soil tests in general accordance with ASTM standards.
 2. Soil classifications are in general accordance with ASTM D2487(as applicable), based on testing indicated and visual classification.
 3. Key to abbreviations: NP=Non-Plastic; -- indicates no test performed



Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV



Contract: 19C16020.00



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-03	13.5 ft	SILTY SAND WITH GRAVEL (SM), f-c, black (Visual Class., Sample consists of coal and shale fragments)					--	--	--	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	19	1.873			21.9	46.8	31.3			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4	3/8 in.	3/4 in.
% Finer	31.3	35.1	38.5	42.8	49.2	60.9	78.1	92.2	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING


GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC

PERCENT FINER BY WEIGHT





COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-03	53.5 ft	SANDY SILTY CLAY (CL-ML), contains mica, brown					25	20	5	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	0.425				0.0	39.4	60.6			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4
% Finer	60.6	88.2	98.9	100.0	100.0	100.0	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-03	73.5 ft	SILTY SAND WITH GRAVEL (SM), fine to coarse, contains mica, brown (Visual Classification)					--	--	--	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	37.5	0.821	0.179		28.8	53.2	18.0			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4	3/8 in.	3/4 in.	1 in.	1.5 in.
% Finer	18.0	26.3	37.1	50.4	60.5	66.7	71.2	76.5	87.7	91.1	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC

PERCENT FINER BY WEIGHT



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-05	7.5 ft	SANDY SILT (ML), contains mica, brown					23	21	2	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	0.85				0.0	36.8	63.2			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4
% Finer	63.2	89.3	98.2	99.8	100.0	100.0	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC

PERCENT FINER BY WEIGHT



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-05 21.0 ft	SANDY SILTY CLAY (CL-ML), contains mica, brown					27	20	7		
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	2	0.08			0.0	42.2	57.8			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4
% Finer	57.8	83.8	97.6	99.6	99.9	100.0	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/27/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-05	33.5 ft	SILTY SAND (SM), fine, trace gravel, contains mica, brown (Visual Classification)					--	--	--	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	9.5	0.155			0.1	65.9	34.0			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4	3/8 in.
% Finer	34.0	58.1	86.7	98.8	99.7	99.8	99.9	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC

PERCENT FINER BY WEIGHT



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-06	4.5 ft	SILTY SAND (SM), fine, contains mica, brown					NP	NP	NP	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	2	0.108			0.0	55.5	44.5			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4
% Finer	44.5	74.2	93.0	99.3	99.8	100.0	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC

PERCENT FINER BY WEIGHT



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-06 13.5 ft	SANDY SILT (ML), contains mica, brown					21	18	3		
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	2	0.084			0.0	43.9	56.1			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4
% Finer	56.1	80.8	95.3	99.7	99.9	100.0	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	5/26/19	TTM	MJF




Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC



COBBLES	GRAVEL		SAND			SILT OR CLAY
	coarse	fine	coarse	medium	fine	

Specimen	Sample Description					LL	PL	PI		
B-06	43.5 ft	SILTY SAND (SM), fine to medium, few gravel, contains mica, brown (Visual Classification)					--	--	--	
Test Method	D100	D60	D30	D10	%Gravel	%Sand	%Silt		%Clay	
ASTM D422	19	0.279	0.124		10.6	65.9	23.5			

Percent Finer

Sieve Size	No. 200	No. 100	No. 60	No. 40	No. 20	No. 10	No. 4	3/8 in.	3/4 in.
% Finer	23.5	32.5	54.6	81.1	87.3	88.3	89.4	90.4	100.0

Tested By	Tested Date	Reviewed By	Calc By
MJF	8/26/19	TTM	MJF



Schnabel
ENGINEERING

GRADATION CURVE

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Kanawha County, WV

Contract: 19C16020.00 **Testing Lab:** BLAC



Unconfined Compression Test Report

ASTM D2166

Date: 9/18/2019

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Location: Kanawha County, WV

Schnabel No.: 19C16020.00
Boring No.: B-03
Depth: 36-38 ft.
Elevation: 607.5-605.5 ft.

Test Specimen Data	
Initial Diameter, in:	2.881
Initial Area, in ² :	6.522
Initial Height, in:	5.819
H/D Ratio:	2.0
Moisture Content, %:	22.7
Wet Unit Weight, pcf:	128.5
Dry Unit Weight, pcf:	104.7


Testing Information	
Test Procedure:	ASTM D2166
Type of Specimen:	Tube Sample
Load Cell No.:	1352472
Strain Rate, %/min.:	1.0

Remarks: Gs assumed.

Specimen Type: Tube Sample

Strength Data	
Strain at Failure, %:	5.4
Unconfined Strength (Qu), tsf:	1.12
Shear Strength (Su), tsf:	0.56

Failure Sketch




Reviewed by: CJS

Soil Desc.: LEAN CLAY WITH SAND (CL), contains mica, brown

LL, %:	32	% < 200:	84.5
PI, %:	10	Gs:	2.70

Test Data						
Reading No.	Axial Load (lbs)	Axial Displ. (in.)	Axial Strain (%)	Corrected Area ¹ (in ²)	Axial Stress (psi)	Axial Stress (tsf)
Zero	0.0	0.000	0.0	6.52	0.0	0.00
1	7.3	0.006	0.1	6.53	1.1	0.08
2	9.3	0.012	0.2	6.53	1.4	0.10
3	11.4	0.017	0.3	6.54	1.7	0.13
4	13.2	0.023	0.4	6.55	2.0	0.15
5	15.0	0.028	0.5	6.55	2.3	0.16
6	16.8	0.034	0.6	6.56	2.6	0.18
7	19.2	0.039	0.7	6.57	2.9	0.21
8	21.6	0.045	0.8	6.57	3.3	0.24
9	24.3	0.050	0.9	6.58	3.7	0.27
10	26.8	0.056	1.0	6.58	4.1	0.29
11	35.0	0.073	1.2	6.60	5.3	0.38
12	40.5	0.084	1.4	6.62	6.1	0.44
13	56.7	0.117	2.0	6.66	8.5	0.61
14	67.7	0.145	2.5	6.69	10.1	0.73
15	77.0	0.173	3.0	6.72	11.5	0.83
16	85.5	0.200	3.4	6.75	12.7	0.91
17	92.1	0.228	3.9	6.79	13.6	0.98
18	99.1	0.262	4.5	6.83	14.5	1.05
19	104.7	0.289	5.0	6.86	15.3	1.10
20	107.6	0.317	5.4	6.90	15.6	1.12
21	108.4	0.350	6.0	6.94	15.6	1.12
22	105.4	0.378	6.5	6.97	15.1	1.09
23	102.8	0.406	7.0	7.01	14.7	1.06
24	98.2	0.434	7.5	7.05	13.9	1.00
25	90.4	0.462	7.9	7.08	12.8	0.92
26	60.1	0.507	8.7	7.14	8.4	0.61

Axial Stress vs. Axial Strain Plot



Notes: 1. Right Cylinder Area Correction Method

Testing Lab: BLAC
UC 8/2006 Rev. 1



Unconfined Compression Test Report

ASTM D2166

Date: 9/18/2019

Project: AEP Work Order 42703738-02
Cabin Creek - London 46kV
Location: Kanawha County, WV

Schnabel No.: 19C16020.00
Boring No.: B-05
Depth: 21-23 ft.
Elevation: 603.7-601.7 ft.

Test Specimen Data	
Initial Diameter, in:	2.882
Initial Area, in ² :	6.524
Initial Height, in:	5.728
H/D Ratio:	2.0
Moisture Content, %:	20.8
Wet Unit Weight, pcf:	129.7
Dry Unit Weight, pcf:	107.4


Testing Information	
Test Procedure:	ASTM D2166
Type of Specimen:	Tube Sample
Load Cell No.:	1352472
Strain Rate, %/min.:	1.0

Remarks: Gs assumed.

Specimen Type: Tube Sample

Strength Data	
Strain at Failure, %:	6.5
Unconfined Strength (Qu), tsf:	0.74
Shear Strength (Su), tsf:	0.37

Failure Sketch




Reviewed by: CJS

Soil Desc.: SANDY SILTY CLAY (CL-ML), contains mica, brown

LL, %:	27	% < 200:	57.8
PI, %:	7	Gs:	2.70

Test Data						
Reading No.	Axial Load (lbs)	Axial Displ. (in.)	Axial Strain (%)	Corrected Area ¹ (in ²)	Axial Stress (psi)	Axial Stress (tsf)
Zero	0.0	0.000	0.0	6.52	0.0	0.00
1	2.3	0.006	0.1	6.53	0.4	0.03
2	4.5	0.011	0.2	6.54	0.7	0.05
3	5.6	0.017	0.3	6.54	0.9	0.06
4	6.4	0.022	0.4	6.55	1.0	0.07
5	7.6	0.028	0.5	6.56	1.2	0.08
6	8.7	0.033	0.6	6.56	1.3	0.09
7	9.6	0.039	0.7	6.57	1.5	0.11
8	10.8	0.045	0.8	6.57	1.6	0.12
9	12.1	0.050	0.9	6.58	1.8	0.13
10	13.2	0.056	1.0	6.59	2.0	0.14
11	19.1	0.083	1.5	6.62	2.9	0.21
12	25.8	0.111	1.9	6.65	3.9	0.28
13	32.6	0.139	2.4	6.69	4.9	0.35
14	39.9	0.172	3.0	6.73	5.9	0.43
15	46.1	0.200	3.5	6.76	6.8	0.49
16	51.6	0.228	4.0	6.79	7.6	0.55
17	56.7	0.256	4.5	6.83	8.3	0.60
18	61.6	0.283	4.9	6.86	9.0	0.65
19	65.7	0.311	5.4	6.90	9.5	0.69
20	69.3	0.339	5.9	6.93	10.0	0.72
21	72.2	0.372	6.5	6.98	10.3	0.74
22	70.1	0.400	7.0	7.01	10.0	0.72
23	65.6	0.428	7.5	7.05	9.3	0.67
24	60.9	0.456	8.0	7.09	8.6	0.62
25	45.8	0.511	8.9	7.16	6.4	0.46
26	39.3	0.550	9.6	7.22	5.4	0.39


Axial Stress vs. Axial Strain Plot




Notes: 1. Right Cylinder Area Correction Method

Testing Lab: BLAC
UC 8/2006 Rev. 1

Easting (ft) : 379768.96	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 6565629.19	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.56 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
612.0	1		0.00 - 3.30: Fill: Bottom ash, moist.	36		
611.0	2					
610.0	3					
609.26			3.30 - 12.20: Fill: Fly ash, moist.	41		
609.0	4					
608.0	5					
607.0	6					
606.0	7					
605.0	8					
604.0	9					
603.0						

Easting (ft) : 379768.96	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 6565629.19	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.56 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0	11		3.30 - 12.20: Fill: Fly ash, moist. (continued)	37		
601.0	12					
600.0	13		12.20 - 17.60: Alluvium: SILT (ML), brown, moist.	34		
599.0	14					
598.0	15					
597.0	16					
596.0	17					
595.0	18		17.60 - 25.00: Gray.			
594.0	19					
593.0						

Easting (ft) : 379768.96	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 6565629.19	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.56 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0	21		17.60 - 25.00: Gray. (continued)	29		
591.0	22					
590.0	23					
589.0	24					
588.0	25		25.00 - 28.00: Wet.		▼	
587.56	26					
587.0	27			57		
586.0	28		28.00 - 29.30: Alluvium: SILT (ML), brown, wet.			
584.56	29		29.30 - 35.00: Alluvium: SILT with sand (ML), brown, wet.			
584.0						
583.26						
583.0						

Easting (ft) : 379768.96	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 6565629.19	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.56 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
582.0	31		29.30 - 35.00: Alluvium: SILT with sand (ML), brown, wet. (continued)	44		
581.0	32					
580.0	33					
579.0	34					
578.0						
			SB - 1 Terminated at 35 Ft			



Easting (ft) : 457395.92	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227933.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
614.0	1		0.00 - 7.50: Fill: Bottom ash, moist.	31		
613.0	2					
612.0	3					
611.0	4					
610.0	5					
609.0	6					
608.0	7					
607.0 606.97	8		7.50 - 9.00: Fill: Fly ash, moist.	35		
606.0	9		9.00 - 20.00: Alluvium: SILT (ML), brown, moist.			
605.47						
605.0						



Easting (ft) : 457395.92	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227933.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.0	11		9.00 - 20.00: Alluvium: SILT (ML), brown, moist. (continued)	38		
603.0	12					
602.0	13					
601.0	14					
600.0	15			32		
599.0	16					
598.0	17					
597.0	18					
596.0	19					
595.0						

Easting (ft) : 457395.92	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227933.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
594.47			20.00 - 25.00: Red and brown.			
594.0	21					
593.0	22					
592.0	23			36		
591.0	24					
590.0						
589.47	25		25.00 - 30.00: Wet.		▼	
589.0	26					
588.0	27					
587.0	28			51		
586.0	29					
585.0						
SB - 2 Terminated at 30 Ft						

Easting (ft) : 457469.37	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227953.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
612.0	1		0.00 - 2.00: Fill: Bottom ash, moist.	48		
611.0	2		2.00 - 2.20: Fill: SAND (SP), brown, moist.			
610.49 610.29			2.20 - 8.20: Fill: Fly ash, moist.			
610.0	3			36		
609.0	4					
608.0	5			36		
607.0	6					
606.0	7					
605.0	8			36		
604.29			8.20 - 13.80: Alluvium: SILT (ML), brown, moist.			
604.0	9					
603.0						

Easting (ft) : 457469.37	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227953.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0	11		8.20 - 13.80: Alluvium: SILT (ML), brown, moist. (continued)	36		
601.0	12					
600.0	13			36		
599.0	14		13.80 - 15.00: Alluvium: SILT with sand (ML), wet.			
598.69	15		15.00 - 20.00: Alluvium: SILT (ML), gray, moist.	38		
598.0	16					
597.49	17					
597.0	18					
596.0	19					
595.0						
594.0						
593.0						

Easting (ft) : 457469.37	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227953.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0	21		20.00 - 24.80: Alluvium: SILT (ML), brown, moist.	38		
591.0	22					
590.0	23					
589.0	24					
588.0						
587.69	25		24.80 - 25.00: Wet.			
587.49			25.00 - 30.00: Alluvium: SILT with fine sand (ML), brown, wet.	60		
587.0	26					
586.0	27					
585.0	28					
584.0	29					
583.0						
SB - 3 Terminated at 30 Ft						

Easting (ft) : 457543.04	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227975.50	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.21 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
613.0			0.00-0.30: Fill: CLAY with gravel (CL), brown.			
			0.30-2.50: Fill: Bottom ash, moist.			
612.0	1					
611.0	2					
610.71			2.50-5.00: Fill: Fly ash, moist	46		
610.0	3					
609.0	4					
608.21	5		5.00-8.30: Wet.		▼	
608.0						
607.0	6					
606.0	7					
605.0	8			37		
			8.30-13.40: Fill: Moist, fly ash with brown silt.			
604.0	9					

Easting (ft) : 457543.04	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227975.50	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.21 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR


Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
603.0			8.30-13.40: Fill: Moist, fly ash with brown silt. (continued)	36		
602.0	11					
601.0	12					
600.0	13			35		
599.0	14		13.40-15.00: Alluvium: SILT with sand (ML), loose, brown, moist.			
598.21	15		15.00-19.10: Alluvium: SILT (ML), gray and brown, moist.			
598.0	16					
597.0	17					
596.0	18					
595.0	19		19.10-20.00: Alluvium: SAND (SP), very fine, loose, brown, moist.			
594.11						
594.0						

Easting (ft) : 457543.04	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227975.50	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.21 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
593.0	21		20.00-25.00: Alluvium: SILT (ML), brown, moist.	32		
592.0	22					
591.0	23					
590.0	24					
589.0	25		25.00-30.00: Wet.	60	▼	
588.21	26					
588.0	27					
587.0	28					
586.0	29					
585.0						
584.0						

SB-4 Terminated at 30 Ft




Easting (ft) : 457624.65	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227983.97	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 624.48 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
624.0	1		0.00-2.40: Fill: Bottom ash, moist.	37		
623.0	2					
622.0	3		2.40-8.80: Fill: Fly ash, moist.			
622.08	4			29		
621.0	5					
620.0	6					
619.0	7					
618.0	8					
617.0	9		8.80-12.10: Fill: Bottom ash, moist.			
616.0						
615.0						

Easting (ft) : 457624.65	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227983.97	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 624.48 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
614.0	11		8.80-12.10: Fill: Bottom ash, moist. (continued)	36		
613.0	12		12.10-14.20: Fill: Fly ash, moist.			
612.38	13					
612.0	14		14.20-18.40: Fill: Bottom ash, moist.	34		
611.0	15					
610.28	16					
610.0	17					
609.0	18					
608.0	19		18.40-20.00: Alluvium: SAND (SP), brown with black mottles, moist, sandstone fragments.			
607.0						
606.08						
606.0						
605.0						

Easting (ft) : 457624.65	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227983.97	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 624.48 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.0	21		20.00-24.10: Alluvium: SAND (SP), yellowish brown, moist, sandstone fragments.	36		
603.0	22					
602.0	23					
601.0	24					
600.38			24.10-27.60: Alluvium: SILT (ML), reddish brown, moist.	32		
600.0	25					
599.0	26					
598.0	27					
597.0			27.60-29.80: Rock: CONGLOMERATE, gray, black, and brown.			
596.88	28					
596.0	29					
595.0			29.80-30.00: Silt, sand, and gravel.			

Easting (ft) : 457624.65	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227983.97	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 624.48 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
594.0	31		30.00-35.00: Alluvium: SILT (ML), brown, wet.	60		
593.0	32					
592.0	33					
591.0	34					
590.0						
			SB-5 Terminated at 35 Ft			

Easting (ft) : 457772.15	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227969.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 593.37 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 10 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
593.0	1		0.00 - 3.90: Alluvium: SILT (ML), brown, wet, rootlets.	49		
592.0	2					
591.0	3					
590.0	4		3.90 - 5.00: Alluvium: SILT with fine sand (ML), dark grey, rootlets, wet.		▼	
589.47	5		5.00 - 10.00: Same as above, no roots.			
589.0	6					
588.37	7					
588.0	8			49		
587.0	9					
586.0						
585.0						
584.0						
SB - 7 Terminated at 10 Ft						




Easting (ft) : 457849.69
Northing (ft) : 4227987.21
Ground Elevation : 592.59 (Ft)
Total Depth : 15 Ft BGL

Drill Rig : Geoprobe 7822DT
Driller Supplier : Enviroprobe Integrated Solutions
Logged By : Greg Sowder
Reviewed By : Andrew Fowler
Date : 06/02/2025


Job Number : LLC.06149.0000
Client : American Electric Power (AEP)
Project : Cabin Creek
Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0	1		0.00 - 3.60: Alluvium: SILT with sand (ML), brown, wet.	52		
591.0	2					
590.0	3					
589.0 588.99	4		3.60 - 15.00: Alluvium: SILT with sand (ML), dark gray, wet.		▼	
588.0	5					
587.0	6					
586.0	7					
585.0	8			60		
584.0	9					
583.0						


Easting (ft) : 457849.69	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227987.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 592.59 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 15 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
582.0 581.0 580.0 579.0 578.0	11 12 13 14		3.60 - 15.00: Alluvium: SILT with sand (ML), dark gray, wet. (continued)	50		
			SB - 8 Terminated at 15 Ft			

Easting (ft) : 457262.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227865.05	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.63 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.0	1		0.00-2.70: Fill: Bottom ash, moist.	43		
603.0	2					
602.0 601.93	3		2.70-7.00: Fill: Fly ash, moist.			
601.0	4					
600.0	5			41		
599.0	6					
598.0	7		7.00-7.40: Fill: Bottom ash, moist.			
597.63						
597.23			7.40-10.00: Fill: Fly ash, moist.			
597.0	8					
596.0	9					
595.0						

Easting (ft) : 457262.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227865.05	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.63 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
594.0	11		10.00-16.40: Wet.	42		
593.0	12					
592.0	13					
591.0	14					
590.0	15					
589.0	16					
588.23			16.40-25.00: Alluvium: SILT (ML), brown, wet.	60		
588.0	17					
587.0	18					
586.0	19					
585.0						

Easting (ft) : 457262.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227865.05	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.63 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
584.0	21		16.40-25.00: Alluvium: SILT (ML), brown, wet. (continued)	60		
583.0	22					
582.0	23					
581.0	24					
580.0	25		25.00-30.00: Moist.	60		
579.63						
579.0	26					
578.0	27					
577.0	28					
576.0	29					
575.0						

Easting (ft) : 457262.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227865.05	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.63 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
574.0	31		30.00-33.40: Little fine grained gravel	48		
573.0	32					
572.0	33					
571.23						
571.0	34		33.40-34.60: Alluvium: SILT with gravel (ML), dark gray, wet.			
570.0			34.60-35.00: Alluvium: SAND (SP): fine, brown, moist.			
569.63	35		35.00-38.10: Wet.	26		
569.0	36					
568.0	37					
567.0	38					
566.53						
566.0	39		38.10-40.00: Alluvium: SILT with gravel (ML), black, wet.			
565.0						
SB-9 Terminated at 40 Ft						

Easting (ft) : 457307.42	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227873.59	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.15 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.0			0.00 - 0.70: Fill: Bottom ash, moist.			
	1		0.70 - 7.80: Fill: Fly ash, moist.	25		
617.0	2					
616.0	3					
615.0	4					
614.0	5					
613.0	6					
612.0	7					
611.0	8		7.80 - 26.00: Wet.	36	▼	
610.35						
610.0	9					
609.0						

Easting (ft) : 457307.42	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227873.59	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.15 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0			7.80 - 26.00: Wet. (continued)			
607.0	11			55		
606.0	12					
605.0	13					
604.0	14					
603.0	15			60		
602.0	16					
601.0	17					
600.0	18					
599.0	19					

Easting (ft) : 457307.42	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227873.59	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.15 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0			7.80 - 26.00: Wet. (continued)			
597.0	21			60		
596.0	22					
595.0	23					
594.0	24					
593.0	25					
592.15	26		26.00 - 30.00: Alluvium: SILT (ML), gray, moist.	60		
592.0						
591.0	27					
590.0	28					
589.0	29					

Easting (ft) : 457307.42	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227873.59	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.15 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0			30.00 - 35.00: Alluvium: CLAY (CL), soft, gray, moist.			
587.0	31			60		
586.0	32					
585.0	33					
584.0	34					
583.15	35		35.00 - 36.20: Alluvium: SILT (ML), gray, wet.			
583.0						
582.0	36		36.20 - 40.00: Alluvium: SILT (ML), brown, wet.			
581.0	37			60		
580.0	38					
579.0	39					
			SB - 10 Terminated at 40 Ft			



Easting (ft) : 457377.52	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227889.10	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.13 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
615.0			0.00 - 11.30: Fill: Fly ash, moist.			
614.0	1			25		
613.0	2					
612.0	3					
611.0	4					
610.0	5					
609.0	6					
608.0	7			36		
607.0	8					
606.0	9					

Easting (ft) : 457377.52	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227889.10	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.13 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
605.0			0.00 - 11.30: Fill: Fly ash, moist. (continued)			
604.0	11					
603.83			11.30 - 17.30: Wet.	55	▼	
603.0	12					
602.0	13					
601.0	14					
600.0	15					
599.0	16					
598.0	17					
597.83			17.30 - 20.00: Alluvium: SILT (ML), brown, moist.	60		
597.0	18					
596.0	19					

Easting (ft) : 457377.52	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227889.10	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.13 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
595.0			20.00 - 30.00: Alluvium: SILT (ML), brown, wet.			
594.0	21			60		
593.0	22					
592.0	23					
591.0	24					
590.0	25					
589.0	26					
588.0	27					
587.0	28					
586.0	29					
			SB - 11 Terminated at 30 Ft			



EHS Support, LLC

Monitoring Well Log - Borehole

SB-12


Easting (ft) : 457461.58	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227905.53	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
617.0 616.87			0.00 - 0.60: Fill: CLAY (CL), gray and brown, wood.			
	1		0.60 - 12.40: Fill: Fly ash, moist.	30		
616.0	2					
615.0	3					
614.0	4					
613.0	5					
612.0	6					
611.0	7					
610.0	8			23		
609.0	9					
608.0						

Easting (ft) : 457461.58	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227905.53	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
607.0	11		0.60 - 12.40: Fill: Fly ash, moist. (continued)	38		
606.0	12					
605.07			12.40 - 22.90: Fill: Fly ash, wet.			
605.0	13					
604.0	14					
603.0	15					
602.0	16					
601.0	17					
600.0	18			38		
599.0	19					
598.0						

Easting (ft) : 457461.58	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227905.53	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
597.0	21		12.40 - 22.90: Fill: Fly ash, wet. (continued)	36		
596.0	22					
595.0						
594.57	23		22.90 - 30.00: Alluvium: SILT (ML), brown.	55		
594.0	24					
593.0	25					
592.0	26					
591.0	27					
590.0	28					
589.0	29					
588.0						

SB - 12 Terminated at 30 Ft




Easting (ft) : 457549.47
Northing (ft) : 4227923.74
Ground Elevation : 618.43 (Ft)
Total Depth : 30 Ft BGL

Drill Rig : Geoprobe 3230DT
Driller Supplier : Enviroprobe Integrated Solutions
Logged By : Greg Sowder
Reviewed By : Andrew Fowler
Date : 06/11/2025

Job Number : LLC.06149.0000
Client : American Electric Power (AEP)
Project : Cabin Creek
Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.0 617.93			0.00 - 0.50: Fill: CLAY (CL), brown, wood.			
	1		0.50 - 13.80: Fill: Fly ash, moist.			
617.0	2			37		
616.0	3					
615.0	4					
614.0	5					
613.0	6					
612.0	7					
611.0	8			28		
610.0	9					
609.0						

Easting (ft) : 457549.47	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227923.74	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.43 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0	11		0.50 - 13.80: Fill: Fly ash, moist. (continued)	33		
607.0	12					
606.0	13					
605.0	14		13.80 - 19.60: Wet.			
604.63	15					
604.0	16					
603.0	17					
602.0	18					
601.0	19					
600.0						
599.0			19.60 - 25.00: Alluvium: SILT (ML), gray, wet.	45		

Easting (ft) : 457549.47	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227923.74	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.43 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	21		19.60 - 25.00: Alluvium: SILT (ML), gray, wet. (continued)	38		
597.0	22					
596.0	23					
595.0	24					
594.0	25		25.00 - 30.00: Alluvium: SILT (ML), brown, wet.	60		
593.43	26					
593.0	27					
592.0	28					
591.0	29					
590.0						
589.0						
			SB - 13 Terminated at 30 Ft			



EHS Support, LLC


Monitoring Well Log - Borehole

SB-14


Easting (ft) : 457633.09	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227941.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.07			0.00 - 0.80: Fill: CLAY (CL), brown, wood.			
618.0	1		0.80 - 13.80: Fill: Fly ash, moist.	38		
617.0	2					
616.0	3					
615.0	4					
614.0	5					
613.0	6					
612.0	7					
611.0	8			31		
610.0	9					
609.0						

Easting (ft) : 457633.09	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227941.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
			0.80 - 13.80: Fill: Fly ash, moist. (continued)				
608.0	11			30			
607.0	12						
606.0	13						
605.07	14		13.80 - 20.00: Wet.	41			
605.0							
604.0	15						
603.0	16						
602.0	17						
601.0	18						
600.0	19						
599.0							

Easting (ft) : 457633.09	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227941.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	21		20.00 - 25.00: Alluvium: SAND (SP), brown, wet, coal lenses at 23.2, 23.6, 23.9, and 24.1 ft.	38		
597.0	22					
596.0	23					
595.0	24					
594.0 593.87	25		25.00 - 30.00: Alluvium: SILT (ML), brown, wet.	60		
593.0	26					
592.0	27					
591.0	28					
590.0	29					
589.0			SB - 14 Terminated at 30 Ft			





Easting (ft) : 457712.94
Northing (ft) : 4227957.29
Ground Elevation : 598.38 (Ft)
Total Depth : 35 Ft BGL

Drill Rig : Geoprobe 3230DT
Driller Supplier : Enviroprobe Integrated Solutions
Logged By : Greg Sowder
Reviewed By : Andrew Fowler
Date : 06/11/2025

Job Number : LLC.06149.0000
Client : American Electric Power (AEP)
Project : Cabin Creek
Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.08			0.00-0.30: Fill: CLAY (CL), brown, moist.			
598.0			0.30-0.50: Fill: Bottom ash, moist.			
597.88			0.50-8.00: Fill: Fly ash, moist.			
	1			28		
597.0	2					
	3					
596.0	4					
	5					
595.0	6					
	7					
594.0	8		8.00-10.00: Fill: Bottom ash, moist.	36		
	9					
593.0						
592.0						
591.0						
590.38						
590.0						
589.0						

Easting (ft) : 457712.94	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227957.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 598.38 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
588.0	11		10.00-13.60: Alluvium: SAND (SP), brown, fine grained, moist.	36				
587.0	12							
586.0	13							
585.0			13.60-25.00: Alluvium: SILT (ML), reddish brown, moist.	29				
584.78	14							
584.0	15							
583.0	16							
582.0	17							
581.0	18							
580.0	19							
579.0								


Easting (ft) : 457712.94	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227957.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 598.38 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
578.0	21		13.60-25.00: Alluvium: SILT (ML), reddish brown, moist. (continued)	34		
577.0	22					
576.0	23					
575.0	24					
574.0	25		25.00-29.80: Alluvium: SILT (ML), gray, moist.	42		
573.38	26					
573.0	27					
572.0	28					
571.0	29					
570.0						
569.0						
568.58			29.80-30.00: Wet.		▼	



Easting (ft) : 457712.94	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227957.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 598.38 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/11/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
568.0	31		30.00-35.00: Alluvium: SILT (ML), brown, wet.	60		
567.0	32					
566.0	33					
565.0	34					
564.0						
			SB-15 Terminated at 35 Ft			

Easting (ft) : 457281.37	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227831.75	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 601.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
601.0	1		0.00 - 3.00: Fill: Bottom ash, moist.	41		
600.0	2					
599.0	3					
598.45	4		3.00 - 4.00: Fill: Fly ash, moist.	60		
598.0	5					
597.45	6		4.00 - 4.75: Fill: SAND (SP), brown, moist.			
597.0	7					
596.7	8		4.75 - 6.00: Fill: Bottom ash, moist.			
596.0	9					
595.45	10		6.00 - 9.90: Fill: Fly ash, moist.	49		
595.0	11					
594.0	12					
593.0	13					
592.0	14					

Easting (ft) : 457281.37	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227831.75	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 601.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
591.0	11		9.90 - 13.60: Fill: Bottom ash, moist. (continued)	49		
590.0	12					
589.0	13					
588.0	14		13.60 - 17.80: Alluvium: SILT (ML), gray, moist.	49		
587.85	15					
587.0	16					
586.0	17					
585.0	18		17.80 - 19.00: Alluvium: SILT (ML), reddish brown, moist.			
584.0	19		19.00 - 24.00: Alluvium SILT (ML), gray, moist.	52		
582.45						
582.0						


Easting (ft) : 457281.37	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227831.75	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 601.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
581.0	21		19.00 - 24.00: Alluvium SILT (ML), gray, moist. (continued)	52		
580.0	22					
579.0	23					
578.0	24		24.00 - 29.00: Alluvium: SILT (ML), brownish gray, moist.	54		
577.45	25					
577.0	26					
576.0	27					
575.0	28					
574.0	29		29.00 - 34.50: Alluvium: SILT (ML), gray, wet.	60	▼	
572.45						
572.0						


Easting (ft) : 457281.37	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227831.75	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 601.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
571.0	31		29.00 - 34.50: Alluvium: SILT (ML), gray, wet. (continued)	60		
570.0	32					
569.0	33					
568.0	34					
567.0 566.95	35		34.50 - 39.00: Alluvium: SILT with some sand (ML), dark gray, wet, sandstone fragments.	60		
566.0	36					
565.0	37					
564.0	38					
563.0	39		39.00 - 42.10: Alluvium: SILT with some sand (ML), dark gray, gravel lenses throughout, wet.	48		
562.0						



Easting (ft) : 457281.37	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227831.75	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 601.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
561.0	41		39.00 - 42.10: Alluvium: SILT with some sand (ML), dark gray, gravel lenses throughout, wet. (continued)	48		
560.0	42					
559.35	42		42.10 - 44.00: GRAVEL (GW), brown, wet, with cobbles.			
559.0	43					
558.0						
SB - 16 Terminated at 44 Ft						

Easting (ft) : 457325.90	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227816.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.0	1		0.00 - 6.80: Fill: Bottom ash, moist.	45		
617.0	2					
616.0	3					
615.0	4					
614.0	5					
613.0	6					
612.0	7		6.80 - 12.20: Fill: Fly ash, moist.	49		
611.0	8					
610.0	9					
609.0				54		

Easting (ft) : 457325.90	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227816.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0	11		6.80 - 12.20: Fill: Fly ash, moist. (continued)	54		
607.0	12					
606.34			12.20 - 19.00: Alluvium: SILT with little fine grained sand (ML), brown, moist.	56		
606.0	13					
605.0	14					
604.0	15					
603.0	16					
602.0	17					
601.0	18					
600.0	19					
599.54			19.00 - 29.00: Alluvium: SILT with little fine grained sand (ML), gray, moist.	45		
599.0						



Easting (ft) : 457325.90	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227816.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	21		19.00 - 29.00: Alluvium: SILT with little fine grained sand (ML), gray, moist. (continued)	45		
597.0	22					
596.0	23					
595.0	24					
594.0	25			54		
593.0	26					
592.0	27					
591.0	28					
590.0	29		29.00 - 30.20: Dark gray, wet.	60	▼	
589.54						
589.0						

Easting (ft) : 457325.90	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227816.92	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0	31		29.00 - 30.20: Dark gray, wet. (continued) 30.20 - 32.70: Gray.	60		
587.0	32					
586.0	33		32.70 - 34.00: Brown.			
585.0	34		34.00 - 35.80: Alluvium: SILT with little fine grained sand (ML), brown, wet.	54		
584.54	35					
584.0	36		35.80 - 39.00: Alluvium: SILT with little fine grained sand (ML), reddish brown, wet.			
583.0	37					
582.74	38					
582.0						
581.0						
580.0						
			SB - 17 Terminated at 39 Ft			

Easting (ft) : 457316.14	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227805.15	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
615.0	1		0.00 - 2.70: Fill: Fly ash, moist.	43		
614.0	2					
613.13			2.70 - 14.00: Alluvium: SILT (ML), brown, moist.	47		
613.0	3					
612.0	4					
611.0	5			49		
610.0	6					
609.0	7					
608.0	8					
607.0	9					
606.0						

Easting (ft) : 457316.14	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227805.15	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
605.0	11		2.70 - 14.00: Alluvium: SILT (ML), brown, moist. (continued)	49		
604.0	12					
603.0	13					
602.0	14		14.00 - 16.30: Alluvium: SILT (ML), loose, gray, moist.	49		
601.83						
601.0	15					
600.0	16		16.30 - 18.20: Dense.	49		
599.0	17					
598.0	18		18.20 - 18.80: Reddish brown, wet.		▼	
597.63						
597.0	19		18.80 - 19.80: Wet.	60		
596.0			19.80 - 21.20: Loose.			

Easting (ft) : 457316.14	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227805.15	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 615.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
595.0	21		19.80 - 21.20: Loose. (continued)			
594.63						
594.0	22		21.20 - 29.00: Alluvium: SILT (ML), loose, reddish brown, wet.	60		
593.0	23					
592.0	24					
591.0	25					
590.0	26			60		
589.0	27					
588.0	28					
587.0						
			SB - 17A Terminated at 29 Ft			




Easting (ft) : 457402.53	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227835.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.23 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
619.0			0.00 - 0.30: Fill: Mulch and bottom ash mixture, moist.			
			0.30 - 16.50: Fill: Fly ash, moist.			
618.0	1			36		
617.0	2					
616.0	3					
615.0	4					
614.0	5					
613.0	6			48		
612.0	7					
611.0	8					
610.0	9			42		


Easting (ft) : 457402.53	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227835.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.23 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
609.0			0.30 - 16.50: Fill: Fly ash, moist. (continued)			
608.0	11			42		
607.0	12					
606.0	13					
605.0	14					
604.0	15					
603.0	16					
602.73			16.50 - 26.70: Wet.	44	▼	
602.0	17					
601.0	18					
600.0	19			60		

Easting (ft) : 457402.53	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227835.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.23 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
599.0	21		16.50 - 26.70: Wet. (continued)	60		
598.0	22					
597.0	23					
596.0	24					
595.0	25					
594.0	26		26.70 - 28.20: Alluvium: SILT with some clay (ML), loose, gray, wet.	47		
593.0	27					
592.53	28					
592.0	29					
591.0			28.20 - 29.00: Moist.	54		
591.03						
590.23			29.00 - 34.00: Alluvium: SILT with some clay (ML), loose, brown, wet.			
590.0						

Easting (ft) : 457402.53	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227835.31	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.23 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/05/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
589.0 588.0 587.0 586.0	31 32 33		29.00 - 34.00: Alluvium: SILT with some clay (ML), loose, brown, wet. (continued)	54		
			SB - 18 Terminated at 34 Ft			

Easting (ft) : 457492.89	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227854.78	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.97 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
616.47			0.00 - 0.50: Fill: Mulch and bottom ash material, moist			
616.0	1		0.50 - 18.30: Fill: Fly ash, moist.	45		
615.0	2					
614.0	3					
613.0	4					
612.0	5					
611.0	6			58		
610.0	7					
609.0	8					
608.0	9			52		
607.0						

Easting (ft) : 457492.89	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227854.78	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.97 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
606.0	11		0.50 - 18.30: Fill: Fly ash, moist. (continued)	52		
605.0	12					
604.0	13					
603.0	14					
602.0	15					
601.0	16					
600.0	17					
599.0	18					
598.0	19		18.30 - 20.40: Wet.	52		
597.0						

Easting (ft) : 457492.89	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227854.78	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.97 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 29 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
596.57			18.30 - 20.40: Wet. (continued)			
596.0	21		20.40 - 24.00: Alluvium: SILT with some clay (ML), grayish brown, wet, with coal flecks.	52		
595.0	22					
594.0	23					
593.0 592.97	24		24.00 - 28.20: Alluvium: SILT with some clay and sand (ML), loose, grayish brown, wet.			
592.0	25					
591.0	26			52		
590.0	27					
589.0 588.77	28		28.20 - 29.00: Alluvium: CLAY with some silt and sand (CL), soft, gray, wet.			
588.0			SB - 19 Terminated at 29 Ft			

Easting (ft) : 457551.61	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227868.36	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 622.19 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
622.0			0.00-3.80: Fill: Fly ash, moist.			
621.0	1					
620.0	2			44		
619.0	3					
618.0	4		3.80-5.80: Fill: Bottom ash, moist.			
617.0	5					
616.0	6		5.80-23.00: Fill: Fly ash, moist.	47		
615.0	7					
614.0	8					
613.0	9			54		

Easting (ft) : 457551.61	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227868.36	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 622.19 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
612.0			5.80-23.00: Fill: Fly ash, moist. (continued)			
611.0	11			54		
610.0	12					
609.0	13					
608.0	14					
607.0	15					
606.0	16			54		
605.0	17					
604.0	18					
603.0	19			54		

Easting (ft) : 457551.61	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227868.36	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 622.19 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0			5.80-23.00: Fill: Fly ash, moist. (continued)			
601.0	21					
600.0	22			54		
599.19	23		23.00-25.00: Wet.		▼	
599.0	24					
598.0	25		25.00-29.00: Alluvium: Sandy SILT with some clay (ML), brown, wet.			
597.19	26			53		
597.0	27					
596.0	28					
595.0	29		29.00-32.10: Alluvium: SAND (SP), brown, medium grained, wet.			
594.0				60		
593.19						
593.0						

Easting (ft) : 457551.61	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227868.36	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 622.19 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR


Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0			29.00-32.10: Alluvium: SAND (SP), brown, medium grained, wet. (continued)			
591.0	31					
590.09	32		32.10-34.80: Alluvium: Silty CLAY (CL-ML), brown, wet.	60		
590.0						
589.0	33					
588.0	34					
587.0	35		34.80-37.00: Alluvium: Sandy SILT with some clay (ML), brown, moist.			
586.0	36			60		
585.19	37		37.00-39.00: Wet.			
584.0	38					
			SB-19A Terminated at 39 Ft			



Easting (ft) : 457581.09	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227876.34	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
			0.00 - 0.30: Top soil and mulch.	46				
			0.30 - 5.00: Fill: Fly ash, moist.					
617.0	1							
616.0	2							
615.0	3							
614.0	4							
613.0	5		5.00 - 6.10: Wet.	53				
612.0	6		6.10 - 20.40: Moist.					
611.0	7							
610.0	8							
609.0	9			53				
608.0								

Easting (ft) : 457581.09	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227876.34	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
			6.10 - 20.40: Moist. (continued)					
607.0	11			53				
606.0	12							
605.0	13							
604.0	14			50				
603.0	15							
602.0	16							
601.0	17			60				
600.0	18							
599.0	19							
598.0								

Easting (ft) : 457581.09	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227876.34	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			6.10 - 20.40: Moist. (continued)			
597.0	21		20.40 - 24.00: Alluvium: SILT with some clay (ML), loose, grayish brown, wet, with coal flecks.	60	▼	
596.0	22					
595.0	23					
594.0	24		24.00 - 24.60: Alluvium: SILT with some clay and sand (ML), loose, grayish brown, wet.			
593.71						
593.11	25		24.60 - 28.20: Wet.			
593.0	26			58		
592.0	27					
591.0	28		28.20 - 34.00: Alluvium: CLAY with some silt and sand (CL), soft, gray, wet.			
589.51	29			60		
589.0						
588.0						

Easting (ft) : 457581.09	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227876.34	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 617.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/04/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
587.0	31		28.20 - 34.00: Alluvium: CLAY with some silt and sand (CL), soft, gray, wet. (continued)	60		
586.0	32					
585.0	33					
584.0						
			SB - 20 Terminated at 34 Ft			






Easting (ft) : 457668.12	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227896.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.82 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59.5 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			0.00-0.30: Mulch.			
			0.30-0.80: Gravelly SILT (ML), gray.			
618.0	1		0.80-9.00: Fill: Bottom ash, wet.	44		
617.0	2					
616.0	3					
615.0	4					
614.0	5					
613.0	6			43		
612.0	7					
611.0	8					
610.0	9		9.00-14.00: Loose, wet.	54	▼	
609.0						



Easting (ft) : 457668.12	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227896.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.82 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59.5 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			9.00-14.00: Loose, wet. (continued)			
608.0	11			54		
607.0	12					
606.0	13					
605.0	14					
604.82	14		14.00-19.00: Dense.	51		
604.0	15					
603.0	16					
602.0	17					
601.0	18					
600.0	19					
599.82	19	19.00-22.70: Soft.	60			
599.0						


Easting (ft) : 457668.12	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227896.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.82 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59.5 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	21		19.00-22.70: Soft. (continued)	60		
597.0	22					
596.12			22.70-26.50: Alluvium: SAND (SP), brown, fine grained, wet.	46		
596.0	23					
595.0	24					
594.0	25					
593.0	26		26.50-27.80: Alluvium: SAND (SP), gray, fine grained, coal fragments.	46		
592.32	27					
591.0	28		27.80-29.00: Alluvium: SAND (SP), gray, fine grained.			
590.0	29					
589.82			29.00-34.00: Alluvium: Sandy SILT (ML), black, wet.	60		
589.0						

Easting (ft) : 457668.12	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227896.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.82 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59.5 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0	31		29.00-34.00: Alluvium: Sandy SILT (ML), black, wet. (continued)	60		
587.0	32					
586.0	33					
585.0	34		34.00-35.25: Alluvium: Sandy SILT (ML), black, wet.	60		
584.82	35		35.25-39.00: Alluvium: SAND (SP), black, fine grained, wet.			
584.0	36					
583.57	37					
583.0	38					
582.0	39		39.00-44.00: Alluvium: SAND (SP), brown, fine to medium grained, wet, heaving.	54		
581.0						
580.0						
579.82						
579.0						

Easting (ft) : 457668.12	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227896.21	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.82 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59.5 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
578.0	41		39.00-44.00: Alluvium: SAND (SP), brown, fine to medium grained, wet, heaving. (continued)	54		
577.0	42					
576.0	43					
575.0	44		44.00-49.00: Alluvium: SAND (SP), brown, fine grained, wet.	20		
574.0	45					
573.0	46					
572.0	47					
571.0	48					
570.0	49		49.00-50.70: Alluvium: SAND (SP), loose, gray, fine to medium grained, wet.	60		
569.0						

Easting (ft) : 457668.12 Northing (ft) : 4227896.21 Ground Elevation : 618.82 (Ft) Total Depth : 59.5 Ft BGL	Drill Rig : Geoprobe 3126GT Driller Supplier : Enviroprobe Integrated Solutions Logged By : Greg Sowder Reviewed By : Andrew Fowler Date : 06/02/2025	Job Number : LLC.06149.0000 Client : American Electric Power (AEP) Project : Cabin Creek Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR
---	--	--

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
568.12			49.00-50.70: Alluvium: SAND (SP), loose, gray, fine to medium grained, wet. (continued)			
568.0						
567.62	51		50.70-51.20: Alluvium: SILT (ML), dense, gray, moist.			
			51.20-52.30: Alluvium: Clayey SILT with medium sized gravel (ML), gray, wet.	60		
567.0	52					
566.52			52.30-54.00: Alluvium: Clayey SILT (ML), gray and brown, wet, sandstone fragments.			
566.0	53					
565.0						
564.82	54		54.00-56.00: Alluvium: SAND (SP), brown, wet.			
564.0	55					
563.0						
562.82	56		56.00-59.00: Alluvium: SAND (SP), brown, fine to medium grained, wet.	60		
562.0	57					
561.0	58					
560.0						
559.82	59		59.00-59.50: Rock: SANDSTONE, gray, refusal at 59.5.	6		
			SB-21 Refusal at 59.5 Ft			

Easting (ft) : 457747.64	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227913.47	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
613.0			0.00-0.30: SILT (ML), dark brown.			
			0.30-4.00: Fill: Gravelly SILT with sand (ML), dark gray, fly ash.			
612.0	1					
				31		
611.0	2					
610.0	3					
609.11	4		4.00-4.60: Fill: Bottom ash.			
608.51			4.60-11.40: Alluvium: SILT (ML), brown, moist.			
608.0	5					
				48		
607.0	6					
606.0	7					
605.0	8					
604.0	9					
				56		

Easting (ft) : 457747.64	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227913.47	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
603.0			4.60-11.40: Alluvium: SILT (ML), brown, moist. (continued)			
602.0	11					
601.71			11.40-23.50: Alluvium: SILT (ML), gray, moist.	56		
601.0	12					
600.0	13					
599.0	14					
598.0	15					
597.0	16			56		
596.0	17					
595.0	18					
594.0	19			55		

Easting (ft) : 457747.64	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227913.47	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
593.0			11.40-23.50: Alluvium: SILT (ML), gray, moist. (continued)	55		
592.0	21					
591.0	22					
590.0	23			35		
589.61			23.50-24.00: Alluvium: CLAY (CL), gray, firm, moist.			
589.11	24		24.00-28.50: Alluvium: SILT (ML), gray, gravels, moist.			
589.0				51		
588.0	25					
587.0	26					
586.0	27					
585.0	28					
584.61			28.50-29.00: Rock: SANDSTONE, yellowish gray, fragmented.			
584.11	29		29.00-32.80: Alluvium: CLAY with some silt (CL), brown, sandstone fragments, moist.			
584.0						

Easting (ft) : 457747.64	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227913.47	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 613.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/02/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
583.0			29.00-32.80: Alluvium: CLAY with some silt (CL), brown, sandstone fragments, moist. (continued)			
582.0	31			51		
581.0	32					
580.0	33		32.80-34.00: Alluvium: SAND (SP), gray - black, wet.			
579.11	34		34.00-39.00: Alluvium: SAND (SP), gray-dark gray, loose, wet.			
579.0				60		
578.0	35					
577.0	36					
576.0	37					
575.0	38					
			SB-22 Refusal at 39 Ft			

Easting (ft) : 457340.88	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227791.52	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD8 8)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
619.0 618.91			0.00 - 0.20: Alluvium: Topsoil.			
			0.20 - 3.20: Fill: Bottom ash, moist.			
618.0	1			39		
617.0	2					
616.0 615.91	3		3.20 - 3.60: Fill: SAND (SP), brown, moist.			
615.51	4		3.60 - 13.30: Fill: Fly ash, moist.			
615.0	5			56		
614.0	6					
613.0	7					
612.0	8					
611.0	9			44		
610.0						

Easting (ft) : 457340.88	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227791.52	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
609.0			3.60 - 13.30: Fill: Fly ash, moist. (continued)			
608.0	11			44		
607.0	12					
606.0	13					
605.11	14		13.30 - 14.00: Alluvium: SILT (ML), gray and red, mottled, moist.			
605.0			14.00 - 24.00: Alluvium: Silt with little fine grained sands (ML), moist, wet.			
604.0	15			58		
603.0	16					
602.0	17					
601.0	18					
600.0	19			54		

Easting (ft) : 457340.88	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227791.52	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.11 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
599.0			14.00 - 24.00: Alluvium: Silt with little fine grained sands (ML), moist, wet. (continued)			
598.0	21			54		
597.0	22					
596.0	23					
595.11	24		24.00 - 29.00: Alluvium: SILT with little clay (ML), reddish brown, wet.			
595.0	25			54		
594.0	26					
593.0	27					
592.0	28					
591.0	29		29.00 - 34.00: Alluvium: Silt (ML), reddish brown, wet.	60		
590.11						
590.0						

SB-23


Easting (ft) : 457340.88
Northing (ft) : 4227791.52
Ground Elevation : 619.11 (Ft)
Total Depth : 34 Ft BGL

Drill Rig : Geoprobe 3126GT
Driller Supplier : Enviroprobe Integrated Solutions
Logged By : Greg Sowder
Reviewed By : Andrew Fowler
Date : 06/06/2025



Job Number : LLC.06149.0000
Client : American Electric Power (AEP)
Project : Cabin Creek
Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
589.0			29.00 - 34.00: Alluvium: Silt (ML), reddish brown, wet. (continued)			
588.0	31			60		
587.0	32					
586.0	33					
			SB - 23 Terminated at 34 Ft			

Easting (ft) : 457394.74	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227772.22	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
			0.00 - 3.70: Fill: Bottom ash.					
621.0	1			32				
620.0	2							
619.0	3							
618.0	4							
617.74			3.70 - 3.80: Fill: SAND (SP), brown, moist.	58				
	4		3.80 - 15.90: Fill: Fly ash, moist.					
617.0	5							
616.0	6							
615.0	7							
614.0	8			58				
613.0	9							
612.0			58					

Easting (ft) : 457394.74	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227772.22	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
			3.80 - 15.90: Fill: Fly ash, moist. (continued)				
611.0	11			58			
610.0	12						
609.0	13						
608.0	14						
607.0	15						
606.0							
605.64	16		15.90 - 18.70: Wet.	59			
605.0	17						
604.0	18						
603.0							
602.54	19		18.70 - 19.00: Alluvium: SILT (ML), soft, brown, wet.	56			
					19.00 - 20.10: Alluvium: SILT (ML), soft, dark gray, wet.		
602.0							

Easting (ft) : 457394.74	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227772.22	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.54 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 34 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR


Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
601.0	21		19.00 - 20.10: Alluvium: SILT (ML), soft, dark gray, wet. (continued)	56		
600.0	22		20.10 - 29.50: Alluvium: SILT (ML), soft, grayish brown, wet.			
599.0	23					
598.0	24					
597.0	25			60		
596.0	26					
595.0	27					
594.0	28					
593.0	29			60		
592.0			29.50 - 34.00: Alluvium: SILT with fine grained sands (ML), soft, reddish brown, wet.			






Easting (ft) : 457485.85	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227803.20	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.69 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
616.0	1		0.00 - 5.00: Fill: Fly ash, wet.	45		
615.0	2					
614.0	3					
613.0	4					
612.0	5		5.00 - 15.00: Moist.	42		
611.69						
611.0	6					
610.0	7					
609.0	8					
608.0	9					
607.0						


Easting (ft) : 457485.85	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227803.20	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.69 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
			5.00 - 15.00: Moist. (continued)				
606.0	11			37			
605.0	12						
604.0	13						
603.0	14						
602.0	15			15.00 - 23.30: Wet.		55	
601.69							
601.0	16						
600.0	17						
599.0	18						
598.0	19						
597.0							

Easting (ft) : 457485.85	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227803.20	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.69 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
596.0	21		15.00 - 23.30: Wet. (continued)	60		
595.0	22					
594.0	23					
593.0	24		23.30 - 24.50: Alluvium: CLAY (CL), soft, gray, moist.	60		
592.19	25		24.50 - 25.00: Alluvium: SILT (ML), gray, moist.			
591.69	25		25.00 - 28.00: Wet.			
591.0	26					
590.0	27					
589.0	28		28.00 - 30.00: Brown.			
588.69	28					
588.0	29					
587.0						

Easting (ft) : 457485.85	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227803.20	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.69 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
586.0 585.0 584.0 583.0 582.0	31 32 33 34		30.00 - 35.00: Gray, wet.	60		
			SB - 25 Terminated at 35 Ft			




Easting (ft) : 457569.33
Northing (ft) : 4227826.12
Ground Elevation : 616.79 (Ft)
Total Depth : 30 Ft BGL

Drill Rig : Geoprobe 3230DT
Driller Supplier : Enviroprobe Integrated Solutions
Logged By : Greg Sowder
Reviewed By : Andrew Fowler
Date : 06/09/2025

Job Number : LLC.06149.0000
Client : American Electric Power (AEP)
Project : Cabin Creek
Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
616.49			0.00 - 0.30: CLAY (CL), gray, wood.			
616.0	1		0.30 - 7.40: Fill: Fly ash, moist.	43		
615.0	2					
614.0	3					
613.0	4					
612.0	5					
611.0	6					
610.0	7					
609.39			7.40 - 7.80: Wet.	47		
609.0	8		7.80 - 15.00: Moist.			
608.99						
608.0	9					
607.0						

Easting (ft) : 457569.33	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227826.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
606.0	11		7.80 - 15.00: Moist. (continued)	38		
605.0	12					
604.0	13					
603.0	14					
602.0	15		15.00 - 18.30: Wet.			
601.0	16			38		
600.0	17					
599.0	18					
598.0	19		18.30 - 20.00: Alluvium: SILT with fine grained sand (ML), gray, moist.			
597.0						




Easting (ft) : 457569.33	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227826.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
596.0	21		20.00 - 25.00: Alluvium: SILT (ML), gray, wet.	44		
595.0	22					
594.0	23					
593.0	24					
592.0	25		25.00 - 30.00: Wet.	60		
591.79						
591.0	26					
590.0	27					
589.0	28					
588.0	29					
587.0			SB - 26 Terminated at 30 Ft			



Easting (ft) : 457648.83	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227849.71	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.52 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
621.0			0.00 - 0.80: CLAY (CL), light gray.			
620.72						
620.42	1		0.80 - 1.10: Fill: Bottom ash, dry.			
			1.10 - 5.00: Fill: Fly ash.			
620.0	2					
				39		
619.0	3					
618.0	4					
617.0	5		5.00 - 14.00: Moist to wet.			
616.52						
616.0	6					
				50		
615.0	7					
614.0	8					
613.0	9					
612.0						

Easting (ft) : 457648.83	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227849.71	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.52 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
611.0	11		5.00 - 14.00: Moist to wet. (continued)	40		
610.0	12					
609.0	13					
608.0	14		14.00 - 22.50: Wet.			
607.52	15					
607.0	16					
606.0	17					
605.0	18					
604.0	19			44		


Easting (ft) : 457648.83	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227849.71	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 621.52 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
601.0	21		14.00 - 22.50: Wet. (continued)	40		
599.0	22					
599.02			22.50 - 25.00: Alluvium: SILT (ML), gray, wet, mottled black.	36		
598.0	23					
598.0	24					
597.0	25		25.00 - 30.00: Brown and gray, wet.			
596.52						
596.0	26					
595.0	27					
594.0	28					
593.0	29					
592.0						


SB - 27 Terminated at 30 Ft




Easting (ft) : 457720.61	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227871.76	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
620.0	1		0.00 - 5.00: Fill: Bottom ash, moist.	20		
619.0	2					
618.0	3					
617.0	4					
616.0	5					
615.47			5.00 - 15.00: Fill: Fly ash, moist.	23		
615.0	6					
614.0	7					
613.0	8					
612.0	9					
611.0						

Easting (ft) : 457720.61	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227871.76	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
610.0	11		5.00 - 15.00: Fill: Fly ash, moist. (continued)	40		
609.0	12					
608.0	13					
607.0	14					
606.0	15		15.00 - 19.00: Moist to wet.	42		
605.47	16					
605.0	17					
604.0	18					
603.0	19		19.00 - 20.00: Wet.			
601.47						
601.0						

Easting (ft) : 457720.61	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227871.76	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
600.0	21		20.00 - 22.20: Wet, bottom ash.	44		
599.0	22		22.20 - 24.50: Alluvium: SILT with fine grained sand (ML), gray, wet.			
598.27	23		24.50 - 25.00: Soft, moist.			
598.0	24		25.00 - 27.80: Wet.			
597.0	25		27.80 - 30.00: Alluvium: SILT with fine grained sands (ML), brown, wet.	58		
596.0	26					
595.97	27					
595.47	28					
595.0	29					
594.0						
593.0						
592.0						
591.0						


Easting (ft) : 457720.61	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227871.76	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.47 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
590.0	31		30.00 - 35.00: Alluvium: SILT with fine grained sand (ML), loose, soft, gray, wet.	53		
589.0	32					
588.0	33					
587.0	34					
586.0						
			SB - 28 Terminated at 35 Ft			


Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
614.26	0.00		0.00-0.30: CLAY (CL), brown.			
			0.30-0.60: Fill: Bottom ash, moist.			
614.0	1		0.60-4.60: Fill: Fly ash, moist.	46		
613.0	2					
612.0	3					
611.0	4					
610.26	5		4.60-7.30: Fill: SAND (SP), brown, moist.			
610.0	6					
609.0	7					
608.0	8		7.30-8.40: Fill: Bottom ash, moist to wet.	43		
607.0	9		8.40-13.20: Clayey SILT with gravel (ML), brown, moist.			
606.46						
606.0						
605.0						




Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
604.0	11		8.40-13.20: Clayey SILT with gravel (ML), brown, moist. (continued)	31				
603.0	12							
602.0	13							
601.66			13.20-14.60: Fill: SILT (ML), brown, moist.	17				
601.0	14							
600.26			14.60-25.00: Fill: Moist, bottom ash.					
600.0	15							
599.0	16							
598.0	17							
597.0	18							
596.0	19							
595.0								


Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
			14.60-25.00: Fill: Moist, bottom ash. (continued)				
594.0	21			12			
593.0	22						
592.0	23						
591.0	24						
590.0	25			25.00-30.00: Wet.		16	
589.0	26						
588.0	27						
587.0	28						
586.0	29						
585.0							


Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
584.0	31		30.00-32.90: Fill: SAND (SP), gray, wet.	60			
583.0	32						
582.0 581.96	33						
581.0	34		32.90-35.00: Alluvium: Sandy SILT (ML), gray, wet.				
580.0 579.86	35						
579.0	36		35.00-37.40: Alluvium: SAND (SP): gray, wet.	60			
578.0	37						
577.46			37.40-42.80: Alluvium: SAND (SP): gray, wet.				
577.0	38						
576.0	39						
575.0							

Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
574.0	41		37.40-42.80: Alluvium: SAND (SP): gray, wet. (continued)	50		
573.0	42					
572.0	43		42.80-45.00: Alluvium: SAND (SP), gray/brown, moist, sandstone fragments.			
571.0	44			60		
570.0	45		45.00-47.80: Alluvium: SAND (SP), brown, wet.			
569.0	46					
568.0	47					
567.0	48	47.80-48.30: Alluvium: SAND (SP), gray, moist, sandstone fragments.				
566.0	49	48.30-50.00: Alluvium: SAND (SP), brown, moist, sandstone fragments.				
565.0						

Easting (ft) : 457766.02	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227882.72	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.86 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
564.86						
564.0	51		50.00-51.50: Alluvium: SAND (SP), gray, wet.	36		
563.36			51.50-53.00: Alluvium: SAND (SP), brown, moist, sandstone fragments.			
563.0	52					
562.0						
			SB-29 Refusal at 53 Ft			

Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
612.0			0.00-2.60: Fill: Bottom ash, moist.			
611.0	1					
610.0	2					
609.62			2.60-3.90: Fill: Fly ash, moist.	36		
609.0	3					
608.32			3.90-5.00: Fill: Bottom ash, moist.			
608.0	4					
607.22			5.00-10.00: Wet.		▼	
607.0	5					
606.0	6					
605.0	7			17		
604.0	8					
603.0	9					

Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0			10.00-19.70: Moist.			
601.0	11			17		
600.0	12					
599.0	13					
598.0	14					
597.0	15			21		
596.0	16					
595.0	17					
594.0	18					
593.0	19					
592.52			19.70-20.00: Alluvium: SILT (ML), brown, moist.			

Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0	21		20.00-22.00: Wet.			
591.0						
590.22	22		22.00-42.60: Alluvium: SILT (ML), gray, wet.	56		
590.0						
589.0	23					
588.0	24					
587.0	25			58		
586.0	26					
585.0	27					
584.0	28					
583.0	29					


Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
582.0			22.00-42.60: Alluvium: SILT (ML), gray, wet. (continued)			
581.0	31					
580.0	32			57		
579.0	33					
578.0	34					
577.0	35					
576.0	36					
575.0	37			60		
574.0	38					
573.0	39					

Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
572.0	41		22.00-42.60: Alluvium: SILT (ML), gray, wet. (continued)	28		
571.0	42					
570.0						
569.62			42.60-50.00: Alluvium: SAND (SP), moist, sandstone fragments.	24		
569.0	43					
568.0	44					
567.0	45					
566.0	46					
565.0	47					
564.0	48					
563.0	49					


Easting (ft) : 457816.67	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227899.02	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.22 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 53 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
562.0 561.0 560.0	51 52		50.00-53.00: Alluvium: SAND (SP): reddish brown, moist to wet, sandstone fragments.	22		
			SB-30 Refusal at 53 Ft			

Easting (ft) : 457898.29	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227921.85	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
611.0	1		0.00 - 1.30: Fill: Bottom ash, moist.	48		
610.0	2		1.30 - 3.40: Fill: Coal fragments.			
609.0	3		3.40 - 4.10: Fill: SILT (ML), brownish orange, moist, sandstone fragments.			
608.0	4		4.10 - 5.00: Fill: SILT (ML), reddish brown, moist.			
607.35	5		5.00 - 19.80: Fill: Bottom ash, moist.	31		
607.0	6					
606.45	7					
606.0	8					
605.0	9					
604.0						
603.0						
602.0						

Easting (ft) : 457898.29	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227921.85	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
601.0	11		5.00 - 19.80: Fill: Bottom ash, moist. (continued)	30		
600.0	12					
599.0	13					
598.0	14					
597.0	15					
596.0	16					
595.0	17					
594.0	18					
593.0	19					
592.0						
			19.80 - 20.30: Alluvium: SILT (ML), brown, moist.	35		

Easting (ft) : 457898.29	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227921.85	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.45 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
591.0	21		19.80 - 20.30: Alluvium: SILT (ML), brown, moist. (continued)	60		
590.0	22		20.30 - 23.00: Alluvium: SILT with fine grained sand (ML), reddish brown, wet.			
589.0	23		23.00 - 23.90: Alluvium: SAND (SP), brown, wet.			
588.45	24		23.90 - 25.00: Alluvium: Sandy SILT (ML), brown, wet.	60		
588.0	25		25.00 - 28.90: Wet.			
587.0	26					
586.45	27			60		
586.0	28					
585.0	29		28.90 - 30.00: Alluvium: SAND (SP), gray, fine grained sand, wet.			
584.0			SB - 31 Terminated at 30 Ft			



Easting (ft) : 457976.91	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227944.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 593.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
593.0 592.99			0.00-0.50: SILT with sand and gravel (ML), brown, moist.			
	1		0.50-4.60: Fill: Bottom ash, moist.	28		
592.0	2					
591.0	3					
590.0	4					
589.0 588.89	5		4.60-8.40: Fill: Bottom ash, moist			
588.0	6					
587.0	7					
586.0	8			26		
585.09			8.40-9.00: Alluvium: Clayey SILT (ML), red, moist.			
584.49	9		9.00-10.00: Alluvium: SILT with gravel (ML), brown, moist, white sandstone fragments.			
584.0						

Easting (ft) : 457976.91	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227944.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 593.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
583.0	11		10.00-17.30: Alluvium: SILT (ML), brown, moist, coal fragments.	41		
582.0	12					
581.0	13					
580.0	14					
579.0	15					
578.0	16					
577.0	17					
576.19			17.30-18.60: Alluvium: SILT and gravel (ML), gray, wet.	34	▼	
576.0	18					
575.0	19		18.60-19.20: Alluvium: SILT and gravel (ML), black, wet.			
574.89						
574.29			19.20-20.00: Alluvium: SILT with fine grained sand (ML), gray, moist.			
574.0						

Easting (ft) : 457976.91	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227944.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 593.49 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
573.0	21 22 23		20.00-23.20: Wet.	44		
572.0						
571.0						
570.29						
570.0	24		23.20-25.00: Alluvium: GRAVEL (GW), dark gray, wet.			
569.0						
SB-32 Terminated at 25 Ft						

Easting (ft) : 457476.81	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227763.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.0			0.00 - 5.10: Fill: Bottom ash, moist.			
617.0	1					
616.0	2			40		
615.0	3					
614.0	4					
613.0	5		5.10 - 9.00: Fill: Fly ash, moist, sandstone fragments from 5.1' - 6.5'.			
612.0	6			53		
611.0	7					
610.0	8					
609.0	9		9.00 - 19.00: Fill: Fly ash, dark grey, moist.	58		

Easting (ft) : 457476.81	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227763.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0			9.00 - 19.00: Fill: Fly ash, dark grey, moist. (continued)			
607.0	11			58		
606.0	12					
605.0	13					
604.0	14					
603.0	15					
602.0	16			55		
601.0	17					
600.0	18					
599.06	19		19.00 - 27.60: Fill: Bottom ash, wet.	48	▼	

Easting (ft) : 457476.81	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227763.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0			19.00 - 27.60: Fill: Bottom ash, wet. (continued)			
597.0	21			48		
596.0	22					
595.0	23					
594.0	24					
593.0	25					
592.0	26			56		
591.0	27					
590.0	28		27.60 - 29.30: Fill: Fly ash, wet.			
589.0	29					
588.76			29.30 - 34.50: Alluvium: SILT (ML), gray, wet.	60		

Easting (ft) : 457476.81	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227763.29	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 39 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0			29.30 - 34.50: Alluvium: SILT (ML), gray, wet. (continued)			
587.0	31			60		
586.0	32					
585.0	33					
584.0	34					
583.56			34.50 - 38.50: Alluvium: CLAY (CH), soft, high plasticity, gray, moist.			
583.0	35			60		
582.0	36					
581.0	37					
580.0	38					
579.56			38.50 - 39.00: Alluvium: SILT with coarse grained sand (ML), dark gray, heaving sand.			
			SB - 33 Terminated at 39 Ft			



EHS Support LLC

Phone: (412) 449-9681


Monitoring Well Log - Borehole

SB-34



Easting (ft) : 457557.80	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227771.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.34 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
618.0	1		0.00-3.50: Fill: Bottom ash, dry.	42		
617.0	2					
616.0	3					
615.0	4		3.50-4.00: Fill: Fly ash, moist.			
614.84						
614.34	5		4.00-5.40: Moist to wet.	54		
614.0	6					
613.0	7		5.40-7.00: Sandstone fragments.			
612.94						
612.0	8					
611.34	9		7.00-16.00: Fill: Fly ash, dark gray, moist.	53		
611.0						
610.0						
609.0						

Easting (ft) : 457557.80	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227771.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.34 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0	11		7.00-16.00: Fill: Fly ash, dark gray, moist. (continued)	53		
607.0	12					
606.0	13					
605.0	14					
604.0	15					
603.0	16		16.00-17.80: Fill: SILT (ML), brown, moist.	54		
602.34	17					
602.0	18		17.80-18.60: Fill: SILT (ML), gray.			
601.0	19		18.60-20.00: Fill: Sandy SILT (ML), brown, moist.	55		
599.74						
599.0						


Easting (ft) : 457557.80	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227771.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.34 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	21		20.00-21.90: Fill: GRAVEL (GP), brown/gray, wet.	55		
597.0	22		21.90-24.00: Fill: Wet, bottom ash.			
596.44	23					
596.0	24		24.00-24.10: Alluvium: GRAVEL (GP), black, wet. 24.10-27.40: Alluvium: SILT (ML), gray, wet, coal fragments.	60		
595.0	25					
594.34 594.24	26					
594.0	27					
593.0	28					
592.0	29					
591.0	29		27.40-29.00: Alluvium: SILT (ML), gray, wet.	60		
590.94			29.00-34.00: Alluvium: SILT (ML), soft, dark gray, wet.			
590.0						
589.34						
589.0						


Easting (ft) : 457557.80	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227771.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.34 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0	31		29.00-34.00: Alluvium: SILT (ML), soft, dark gray, wet. (continued)	60		
587.0	32					
586.0	33					
585.0	34		34.00-41.20: Alluvium: SILT (ML), dark gray, wet, wood fragments at 37.2.	31		
584.34	35					
584.0	36					
583.0	37					
582.0	38					
581.0	39					
580.0						
579.0						

Easting (ft) : 457557.80	Drill Rig : Geoprobe 3126GT	Job Number : LLC.06149.0000
Northing (ft) : 4227771.26	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 618.34 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 44 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/06/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
578.0	41		34.00-41.20: Alluvium: SILT (ML), dark gray, wet, wood fragments at 37.2. (continued)			
577.0	42		41.20-44.00: Alluvium: GRAVEL (GP), wet.			
576.0	43					
575.0						
SB-34 Terminated at 44 Ft						


Easting (ft) : 457640.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227798.81	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.91 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
619.0	1		0.00-3.00: SILT with clay (ML), brown, moist.	32		
618.0	2					
617.0 616.91	3		3.00-7.60: Fill: Bottom ash, moist.			
616.0	4					
615.0	5			36		
614.0	6					
613.0	7					
612.31	8		7.60-9.00: Fill: Fly ash, moist to wet.			
612.0	9		9.00-9.20: SAND (SP), brown, wet.			
611.0 610.91			9.20-9.80: Fill: Fly ash, wet.			
610.11			9.80-10.00: Fill: Bottom ash, wet.			
610.0						


Easting (ft) : 457640.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227798.81	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.91 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
609.0	11		10.00-12.00: Moist.			
608.0 607.91	12		12.00-18.80: Fill: Fly ash, moist.	41		
607.0	13					
606.0	14					
605.0	15					
604.0	16					
603.0	17					
602.0	18					
601.0 601.11	19		18.80-23.60: Wet.	49	▼	
600.0						


Easting (ft) : 457640.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227798.81	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.91 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			18.80-23.60: Wet. (continued)	60		
599.0	21					
598.0	22					
597.0	23					
596.31						
596.0	24		23.60-25.00: SAND with gravel (SP), brown/black, wet.			
595.0	25		594.91	25.00-26.00: SILT with fine sand (ML), brown, wet.		
594.0	26		593.91	26.00-30.00: Fill: Bottom ash, wet.		
593.0	27				60	
592.0	28					
591.0	29					
590.0						

Easting (ft) : 457640.80	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227798.81	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 619.91 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
589.0	31		30.00-32.50: Alluvium: SILT (ML), gray, wet.	60		
588.0	32					
587.41			32.50-35.00: Alluvium: SILT (ML), brown, wet.			
587.0	33					
586.0	34					
585.0						
SB-35 Terminated at 35 Ft						


Easting (ft) : 457711.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.89	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
620.0	1		0.00-2.80: Fill: Silty SAND (SP), wet.	38				
619.0	2							
618.0	3		2.80-9.00: Fill: Bottom ash, moist.					
617.0	4			26				
616.0	5							
615.0	6							
614.0	7							
613.0	8							
612.0	9		9.00-9.30: Fill: SAND (SP), brown.					
611.71			9.30-12.80: Fill: Fly ash, moist.					
611.0								

Easting (ft) : 457711.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.89	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
610.0	11		9.30-12.80: Fill: Fly ash, moist. (continued)	31		
609.0	12					
608.0	13		12.80-13.20: Fill: SILT (ML), gray, moist.			
607.51			13.20-13.90: Fill: SILT (ML), brown, moist.			
607.0	14		13.90-14.10: Fill: SILT (ML), gray, moist.			
606.61			14.10-15.00: Fill: SILT (ML), brown, moist.	16		
606.0	15		15.00-19.20: Sandstone fragments.			
605.71	16					
605.0	17					
604.0	18					
603.0	19		19.20-23.30: Fill: Bottom ash, moist.			
602.0						
601.51						
601.0						

Easting (ft) : 457711.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.89	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
600.0	21		19.20-23.30: Fill: Bottom ash, moist. (continued)	22			
599.0	22						
598.0	23						
597.21			23.30-23.50: Wood fragments.				
597.0	24			23.50-25.00: Fill: Silty CLAY (CL), soft, mottled with black, moist.			17
596.0	25			25.00-28.50: Fill: SILT with little clay (ML), gray, moist.			
595.71							
595.0	26						
594.0	27						
593.0	28						
592.21				28.50-30.00: Fill: Bottom ash, moist.			
592.0	29						
591.0							


Easting (ft) : 457711.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.89	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 620.71 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/09/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			30.00-34.30: Fill: Bottom ash, wet.		▼	
590.0	31			17		
589.0	32					
588.0	33					
587.0	34					
586.0			34.30-35.00: Alluvium: SILT (ML), brown, wet.			
585.71	35		35.00-40.00: Alluvium: Sandy SILT (ML), brown/gray, wet.			
585.0	36					
584.0	37					
583.0	38					
582.0	39					
581.0						
SB-36 Terminated at 40 Ft						



Easting (ft) : 457818.22	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227847.73	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.78 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
611.48			0.00-0.30: CLAY with medium grained gravel (CL), brown.	16		
611.0	1		0.30-3.10: Silty SAND with medium grained gravel (SM), brown, moist.			
610.0	2					
609.0	3		3.10-8.60: Fill: Moist, bottom ash.	18		
608.68						
608.0	4					
607.0	5					
606.0	6					
605.0	7					
604.0	8					
603.18	9		8.60-14.40: Light brown, dry, sandstone fragments.			
603.0						
602.0						

Easting (ft) : 457818.22	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227847.73	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.78 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
601.0	11		8.60-14.40: Light brown, dry, sandstone fragments. (continued)	31				
600.0	12							
599.0	13							
598.0	14							
597.38			14.40-20.00: Fill: Bottom ash, moist.	16				
597.0	15							
596.0	16							
595.0	17							
594.0	18							
593.0	19							
592.0								

Easting (ft) : 457818.22	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227847.73	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.78 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			20.00-27.80: Wet.			
591.0	21			16		
590.0	22			18		
589.0	23					
588.0	24					
587.0	25					
586.0	26					
585.0	27			41		
584.0 583.98	28		27.80-30.00: Alluvium: Sandy SILT (ML), brown, wet.			
583.0	29					
582.0						


Easting (ft) : 457818.22	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227847.73	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.78 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
581.0	31		30.00-32.70: Alluvium: SILT with fine grained sand (ML), brown, wet.	60		
580.0	32					
579.0	33		32.70-35.00: Alluvium: Silty SAND (SM), gray.			
578.0	34					
577.0						
			SB-37 Terminated at 35 Ft			


Easting (ft) : 457833.51	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227948.56	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 602.55 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 10 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0	1		0.00-2.30: SILT (ML), brown, moist, rootlets.			
601.0	2					
600.25			2.30-3.90: SILT (ML), gray, wet.	46	▼	
600.0	3					
599.0	4		3.90-10.00: SILT with fine grained sand (ML), dark gray, wet.			
598.65						
598.0	5					
597.0	6					
596.0	7					
595.0	8			57		
594.0	9					
593.0						
SB-38 Terminated at 10 Ft						

Easting (ft) : 457887.89	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227863.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
609.0	1		0.00-2.50: Fill: Bottom ash, moist.	39				
608.0	2							
607.15			2.50-15.00: Fill: Fly ash, moist.					
607.0	3			27				
606.0	4							
605.0	5							
604.0	6							
603.0	7							
602.0	8							
601.0	9							
600.0								

Easting (ft) : 457887.89	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227863.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes	
			2.50-15.00: Fill: Fly ash, moist. (continued)				
599.0	11			19			
598.0	12						
597.0	13						
596.0	14						
595.0	15			15.00-18.80: Wet.		27	
594.65							
594.0	16						
593.0	17						
592.0	18						
591.0	19			18.80-22.00: Fill: Bottom ash, wet.			
590.85							
590.0							




Easting (ft) : 457887.89	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227863.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
589.0	21		18.80-22.00: Fill: Bottom ash, wet. (continued)	44		
588.0						
587.65	22		22.00-25.00: Alluvium: Clayey SILT (ML), soft, brown, wet.			
587.0	23					
586.0	24			60		
585.0	25		25.00-30.00: Alluvium: SILT (ML), brown, wet.			
584.65						
584.0	26					
583.0	27					
582.0	28					
581.0	29					
580.0						

Easting (ft) : 457887.89	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227863.61	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
579.65			30.00-34.60: Alluvium: SILT with sand (ML), brown.			
579.0	31					
578.0	32					
577.0	33			54		
576.0	34					
575.0			34.60-35.00: Alluvium: SAND (SP), brown, wet.			
575.05			SB-39 Terminated at 35 Ft			

Easting (ft) : 457955.56	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227880.69	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
609.0	1		0.00-2.80: Fill: Bottom ash and coal, moist.	52		
608.0	2					
607.0	3		2.80-7.20: Alluvium: Clayey SILT with medium sized gravel (CL - ML), brown/gray, wet, with coal fragments.	42		
606.0	4					
605.0	5					
604.0	6					
603.0	7		7.20-15.00: Alluvium: SILT (ML), reddish brown/gray, moist, sandstone fragments and bottom ash.			
602.0	8					
601.0	9					
600.0						

Easting (ft) : 457955.56	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227880.69	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
599.0	11		7.20-15.00: Alluvium: SILT (ML), reddish brown/gray, moist, sandstone fragments and bottom ash. (continued)	49		
598.0	12					
597.0	13					
596.0	14					
595.0	15		15.00-18.00: Wet.		▼	
594.0	16					
593.0	17					
592.0	18		18.00-19.20: Alluvium: GRAVEL with medium grained sand (GP), gray, wet.	36		
591.0	19		19.20-19.40: Alluvium: Silty CLAY (ML), gray, moist.			
590.0			19.40-20.00: Alluvium: GRAVEL (GP), brown, with medium grained sand, wet.			

Easting (ft) : 457955.56	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227880.69	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 609.87 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 30 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/13/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
589.67			20.00-20.20: Alluvium: Silty SAND (SM).	60		
			20.20-25.00: Alluvium: SILT with little clay (ML), soft, gray, moist.			
589.0	21					
588.0	22					
587.0	23			60		
586.0	24					
585.0	25		25.00-30.00: Alluvium: SILT with little clay (ML), soft, gray, wet.			
584.87						
584.0	26			60		
583.0	27					
582.0	28					
581.0	29					
580.0			SB-40 Terminated at 30 Ft			



Easting (ft) : 457803.27	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227793.32	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.72 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
			0.00-0.30: Mulch.			
616.0	1		0.30-14.80: Alluvium: SILT (ML), brown, moist.	28		
615.0	2					
614.0	3					
613.0	4					
612.0	5					
611.0	6					
610.0	7			37		
609.0	8					
608.0	9					
607.0						

Easting (ft) : 457803.27	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227793.32	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.72 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
606.0	11		0.30-14.80: Alluvium: SILT (ML), brown, moist. (continued)	41		
605.0	12					
604.0	13			49		
603.0	14					
602.0	15		14.80-15.00: Alluvium: Silty SAND (SM), brown, moist.	49		
601.72			15.00-20.00: Alluvium: SILT with some fine grained sand (ML), brown, moist.			
601.0	16			49		
600.0	17					
599.0	18			49		
598.0	19					
597.0						

Easting (ft) : 457803.27	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227793.32	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.72 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
596.0	21		20.00-28.20: Alluvium: Sandy SILT (ML), brown, moist.	55		
595.0	22					
594.0	23					
593.0	24					
592.0	25					
591.0	26					
590.0	27					
589.0	28					
588.52			28.20-31.50: Alluvium: CLAY with silt (CL), soft, gray, plastic, moist.	60		
588.0	29					
587.0						

Easting (ft) : 457803.27	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227793.32	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 616.72 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/10/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes		
586.0	31		28.20-31.50: Alluvium: CLAY with silt (CL), soft, gray, plastic, moist. (continued)	60				
585.22								
585.0	32		31.50-32.20: Alluvium: SILT with sand (ML), reddish brown, moist, sandstone fragments.					
584.52								
584.0								
583.82	33		32.20-32.90: Alluvium: Silty SAND (SM), gray, moist.					
583.12								
583.0								
582.52	34		32.90-33.60: Alluvium: SILT (ML), reddish brown, moist, sandstone fragments.					
582.0								
581.72	35		33.60-34.20: Alluvium: Silty SAND (SM), gray, moist.					
581.0				60				
580.0	36		34.20-35.00: Alluvium: SAND (SP) reddish brown, wet.					
579.0								
578.52	38		35.00-38.20: Wet.					
578.0								
577.8001								
577.0	39		38.20-38.80: Alluvium: CLAY with little silt (CL), soft, gray.					
			38.80-40.00: Alluvium: SAND (SP), reddish brown, wet.					
SB-41 Terminated at 40 Ft								

Easting (ft) : 457869.03	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227812.13	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
611.33			0.00-0.50: Fill GRAVEL (GP).	23		
611.0	1		0.50-5.00: Fill: Bottom ash, wet.			
610.0	2					
609.0	3					
608.0	4			16		
607.0	5		5.00-5.40: Wood (creosote).			
606.83			5.40-15.00: Fill: SILT (ML), brown, moist.			
606.0	6					
605.0	7			16		
604.0	8					
603.0	9					
602.0						

Easting (ft) : 457869.03	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227812.13	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
601.0	11		5.40-15.00: Fill: SILT (ML), brown, moist. (continued)	38		
600.0	12					
599.0	13					
598.0	14					
597.0 596.83	15		15.00-20.00: Fill: SILT (ML), brown, moist to wet.	40		
596.0	16					
595.0	17					
594.0	18					
593.0	19					
592.0						

Easting (ft) : 457869.03	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227812.13	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 611.83 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 25 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/17/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
591.83			20.00-25.00: Wet.			
591.0	21			57		
590.0	22					
589.0	23					
588.0	24					
587.0			SB-42 Terminated at 25 Ft			

Easting (ft) : 457941.59	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.90	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.39 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 15 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
9999999999			0.00-0.20: Fill: CLAY (CL), gray.			
608.0			0.20-8.40: Fill: Bottom ash, moist.			
	1			34		
607.0						
	2					
606.0						
	3					
605.0						
	4					
604.0						
	5					
603.0						
	6					
602.0						
	7					
601.0				29		
	8					
600.0 599.99			8.40-14.30: Fill: SILT (ML), brown, moist.			
	9					
599.0						

Easting (ft) : 457941.59	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227834.90	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.39 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 15 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0	11		8.40-14.30: Fill: SILT (ML), brown, moist. (continued)	43		
597.0	12					
596.0	13					
595.0	14					
594.09			14.30-15.00: Fill: SILT (ML), stained gray, moist to wet, odor present and sheen.			
594.0			SB-43 Terminated at 15 Ft			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
608.0			0.00-19.60: Fill: Bottom ash, moist.			
607.0	1					
606.0	2			45		
605.0	3					
604.0	4					
603.0	5					
602.0	6					
601.0	7			14		
600.0	8					
599.0	9					

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
598.0			0.00-19.60: Fill: Bottom ash, moist. (continued)			
597.0	11			14		
596.0	12					
595.0	13					
594.0	14					
593.0	15					
592.0	16					
591.0	17			18		
590.0	18					
589.0	19					
999999999			19.60-20.00: Alluvium: SILT (ML), gray, moist.			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
588.0			20.00-25.00: Alluvium: SILT with little clay (ML), gray, moist.			
587.0	21			54		
586.0	22					
585.0	23					
584.0	24					
583.06	25		25.00-30.00: Alluvium: Silty CLAY (CL), gray, moist.			
582.0	26			45		
581.0	27					
580.0	28					
579.0	29					


Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 608.06 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 35 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
578.06						
578.0			30.00-34.10: Alluvium: SILT with medium grained sand (ML), gray, wet.	60		
577.0	31					
576.0	32					
575.0	33					
574.0	34		34.10-35.00: Alluvium: SAND (SP) brown, wet.			
			SB-44 Terminated at 35 Ft			

Easting (ft) : 457915.44	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227784.91	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.26 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 15 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR	

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
614.0			0.00-0.50: Fill: GRAVEL (GP), gray.			
613.76			0.50-1.00: Fill: Silty CLAY (CL), brown, moist, with coal fragments.			
613.26	1		1.00-1.40: Fill: Bottom ash, moist.			
613.0			1.40-5.00: Alluvium: Clayey SILT (CL, brown, moist, sandstone fragments.	45		
612.86						
612.0	2					
611.0	3					
610.0	4					
609.26	5		5.00-7.90: Alluvium: SILT (ML), brown, moist.			
609.0						
608.0	6					
607.0	7					
606.36	8		7.90-10.00: Alluvium: SILT (ML), gray, moist, wood fragments.	32		
606.0						
605.0	9					

Easting (ft) : 457915.44	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227784.91	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.26 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 15 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR


Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.0 603.0 602.0 601.0 600.0	11 12 13 14		10.00-15.00: Alluvium: SILT (ML), gray, moist, petroleum odor.	45		
			SB-45 Terminated at 15 Ft			



Easting (ft) : 457984.16	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227799.16	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
612.49			0.00-0.30: Mulch.			
			0.30-14.20: Fill: Bottom ash, moist.			
612.0	1			24		
611.0	2					
610.0	3					
609.0	4					
608.0	5					
607.0	6					
606.0	7					
605.0	8			14		
604.0	9					
603.0						

Easting (ft) : 457984.16	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227799.16	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
602.0	11		0.30-14.20: Fill: Bottom ash, moist. (continued)	22		
601.0	12					
600.0	13					
599.0	14					
598.0	15		14.20-25.00: Alluvium: SILT (ML), brown, moist.	46		
597.0	16					
596.0	17					
595.0	18					
594.0	19					
593.0						

Easting (ft) : 457984.16	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227799.16	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
592.0	21		14.20-25.00: Alluvium: SILT (ML), brown, moist. (continued)	52		
591.0	22					
590.0	23					
589.0	24					
588.0 587.79	25		25.00-31.40: Alluvium: Clayey SILT (ML), brown, moist.	57		
587.0	26					
586.0	27					
585.0	28					
584.0	29					
583.0						

Easting (ft) : 457984.16	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227799.16	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 612.79 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 40 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/18/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
582.0	31		25.00-31.40: Alluvium: Clayey SILT (ML), brown, moist. (continued)	60		
581.39						
581.0	32		31.40-32.70: Alluvium: CLAY with little silt (CL), brown.			
580.0				60		
579.0	33		32.70-35.00: Alluvium: SILT with fine grained sand (ML), brown, wet.			
578.0	34					
577.9				60		
577.0	35		35.00-38.30: Alluvium: Silty SAND (SM), loose, brown, wet, sandstone fragments.			
576.0	36					
575.0				60		
574.9	37					
574.0	38					
573.0	39		38.30-40.00: Alluvium: SILT with sand (ML), gray, wet, sandstone fragments.			
			SB-46 Terminated at 40 Ft			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.35			0.00-0.30: Fill: Clay with gravel (CL), gray, moist.			
604.0	1		0.30-2.30: Fill: Bottom ash, moist.			
603.0	2					
602.35			2.30-8.90: Fill: Fly ash, moist.	51		
602.0	3					
601.0	4					
600.0	5					
599.0	6					
598.0	7					
597.0	8			39		
596.0			8.90-9.80: Fill: Bottom ash, moist.			
595.75	9					
595.0			9.80-12.10: Alluvium: SILT (ML), brown, moist.			
594.85						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
594.0	11		9.80-12.10: Alluvium: SILT (ML), brown, moist. (continued)			
593.0						
592.55	12		12.10-16.70: Reddish brown.	35		
592.0	13					
591.0	14					
590.0	15					
589.0	16					
588.99	17		16.70-20.00: Grayish brown.			
588.0						
587.0	18					
586.0	19					
585.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
584.0	21		20.00-25.00: Gray with sandstone fragments at 21.7 feet.			
583.0	22					
582.0	23					
581.0	24					
580.0	25		25.00-28.30: Soft, gray, wet.		▼	
579.65	26					
579.0	27					
578.0	28		28.30-28.80: Alluvium: CLAY with some silt (CL), soft, gray, wet.			
576.35	29		28.80-35.00: Alluvium: SILT with very fine sand (ML), soft, gray, wet.			
576.0						
575.85						
575.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
574.0	31		28.80-35.00: Alluvium: SILT with very fine sand (ML), soft, gray, wet. (continued)			
573.0	32					
572.0	33					
571.0	34					
570.0	35		35.00-42.50: With fine sand.			
569.65						
569.0	36					
568.0	37					
567.0	38					
566.0	39					
565.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
564.0	41		35.00-42.50: With fine sand. (continued)			
563.0	42					
562.15						
562.0	43		42.50-46.30: Grades to reddish brown, without sand.			
561.0	44					
560.0	45					
559.0	46					
558.35						
558.0	47		46.30-48.00: Alluvium: Clayey SILT (ML), soft, gray, wet.			
557.0	48					
556.65						
556.0	49		48.00-49.10: Alluvium: SILT with sand (ML), soft, brown, wet.			
555.55						
555.0			49.10-50.00: Alluvium: SAND (SP), gray, wet, with wood fragments.			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 604.65 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 59 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation (NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
554.65						
554.0	51		50.00-51.60: Alluvium: SILT (ML), soft, gray, wet.			
553.05						
553.0			51.60-51.80: Dark brown, with wood fragments.			
552.85						
552.35	52		51.80-52.30: Rock: SANDSTONE, highly weathered, low strength, gray, moist.			
552.0			52.30-53.90: Alluvium: SAND with gravel (SP), wet.			
551.0	53					
550.75			53.90-55.00: Alluvium: SAND (SP), brown, wet, sandstone fragments.			
550.0	54					
549.65			55.00-57.50: Alluvium: Silty SAND (SM).			
549.0	55					
548.0	56					
547.15			57.50-58.80: Weathered sandstone fragments, moist.			
547.0	57					
546.0	58					
545.85			58.80-59.00: Gray, weathered sandstone and siltstone fragments.			
			SB-47D Refusal at 59 Ft			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 591.96 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 32 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
591.0	1		0.00-2.80: Alluvium: SILT with medium sized sand and gravel (ML), brown, wet.	39		
590.0	2					
589.0	3		2.80-11.70: Alluvium: SILT with medium grained sand (ML), dark gray, wet.	40		
588.0	4					
587.0	5					
586.0	6					
585.0	7					
584.0	8					
583.0	9					
582.0						


Easting (ft) : 458016.38	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 591.96 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 32 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
581.0	11		2.80-11.70: Alluvium: SILT with medium grained sand (ML), dark gray, wet. (continued)	54		
580.26						
580.0	12		11.70-15.00: Alluvium: SILT with fine grained sand (ML), gray, wet.			
579.0	13			47		
578.0	14					
577.0	15		15.00-19.70: Wet.			
576.0	16					
575.0	17			47		
574.0	18					
573.0	19					
572.26				47		
572.0			19.70-23.80: Alluvium: SILT with fine grained sand (ML), light gray, wet.			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 591.96 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 32 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
571.0	21		19.70-23.80: Alluvium: SILT with fine grained sand (ML), light gray, wet. (continued)	18		
570.0	22					
569.0	23					
568.0	24		23.80-24.80: Sandstone fragments.	48		
567.0	25		24.80-27.50: Alluvium: SAND (SP), gray, wet.			
566.0	26					
565.0	27					
564.46	28		27.50-32.00: Alluvium: SAND (SP), brown, wet, sandstone fragments.			
564.0	29					
563.0						
562.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 7822DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 591.96 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 32 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
561.0 560.0	31		27.50-32.00: Alluvium: SAND (SP), brown, wet, sandstone fragments. (continued)	34		
			SB-48D Refusal at 32 Ft			

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.3 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 49 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
614.0 613.9			0.00-0.40: Clay (CL), dark gray/brown, moist, rootlets.			
			0.40-6.30: Fill: Fly ash, moist.			
613.0	1			47		
612.0	2					
611.0	3					
610.0	4					
609.0	5					
608.0 608	6					
			6.30-12.40: SILT with sand (ML), moist to wet.			
607.0	7			42		
606.0	8					
605.0	9					




Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.3 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 49 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
604.0	11		6.30-12.40: SILT with sand (ML), moist to wet. (continued)	41		
603.0	12					
602.0	13		12.40-15.00: Clayey SILT (ML), brown, moist.			
601.9	14			56		
601.0	15		15.00-26.30: SILT (ML), soft, brown, moist.			
600.0	16					
599.3	17					
599.0	18					
598.0	19					
597.0						
596.0						
595.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.3 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 49 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
594.0	21		15.00-26.30: SILT (ML), soft, brown, moist. (continued)	58		
593.0	22					
592.0	23					
591.0	24					
590.0	25					
589.0	26					
588.0	27		26.30-30.00: CLAY with little silt (CL), stiff, brown, medium plasticity, moist.	60		
587.0	28					
586.0	29					
585.0						

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.3 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 49 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
584.3						
584.0	31		30.00-31.80: Silty CLAY (CL), gray, plastic, moist.	55		
583.0						
582.5	32		31.80-34.00: SILT (ML), gray, soft, moist.			
582.0	33			28		
581.0						
580.3	34		34.00-35.00: SILT (ML), yellowish brown/gray, moist, sandstone fragments.			
580.0				28		
579.3	35		35.00-40.00: SAND (SP), gray/light brown, moist, sandstone fragments.			
579.0						
578.0	36					
577.0	37					
576.0	38					
575.0	39					

Easting (ft) : 458016.38	Drill Rig : Geoprobe 3230DT	Job Number : LLC.06149.0000
Northing (ft) : 4227857.12	Driller Supplier : Enviroprobe Integrated Solutions	Client : American Electric Power (AEP)
Ground Elevation : 614.3 (Ft)	Logged By : Greg Sowder	Project : Cabin Creek
Total Depth : 49 Ft BGL	Reviewed By : Andrew Fowler	Location : 15225 MacCorkle Ave SE, Cabin Creek, WV 25035, USA
	Date : 06/12/2025	Loc Comment : Ground elevation and coordinates extracted from 2018 LIDAR

Elevation(NAVD88)	Depth (ft)	Lithologic Column	Lithological Description	Recovery (Inches)	Water	Notes
574.3						
574.0	41		40.00-43.80: SAND (SP), brown, wet, sandstone fragments.	49		
573.0	42					
572.0	43					
571.0	44		43.80-45.50: Moist.			
570.5	45			42		
570.0	46		45.50-48.30: Clayey SILT (ML), gray, moist, sandstone fragments.			
569.0	47					
568.8	48		48.30-48.90: Clayey SAND (SP), light brown/brown, sandstone fragments.			
568.0						
567.0						
566.0			48.90-49.00: Rock: SANDSTONE, gray.			
566			SB-49D Refusal at 49 Ft			
565.4						

APPENDIX C

Geotechnical Boring Logs

RECORD OF BOREHOLE: A-1

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 05, 2025

END DATE: September 08, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 616.2 ft (Ground)

COORDINATES: Lat: 38.197944° Long: -81.486306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS			
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic							
1			CCR-SOIL MIX - (SM) SILTY SAND, fine to medium, non plastic fines, some fine gravel; dark gray; non-cohesive, moist, very loose to loose, some soil, grass roots, and tree branches/mulch present.	SM		0.0	S-1	DO	0	1-2-3	5						0.00 - 1.50 ft: Sample collected from hand digging.			
2																				
3																				
4										S-2	DO	45	1-1-2	3						
5																				
6			SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist to wet, very loose to loose.	ML		610.7 5.5														
7							S-3	DO	39	2-1-2	3									
8																				
9																				
10							S-4	DO	37	1-2-2	4									
11																				
12																				
13																				
14							S-5	DO	48	2-1-2	3									
15																				
16																				
17																				
18																				
19						- 19.0 ft: Split spoon sample wet.														
20			ALLUVIUM - (SM) SAND and SILT, fine to coarse, non plastic fines; light brown to dark brown; non-cohesive, wet, very loose to loose.	SM		596.4 19.8	S-6	DO	41	1-1-1	2									
21																				
22																				
23																				
24			- 23.5 to 25.0 ft: Some Silty Clay at top.					S-7	DO	100	2-2-3	5								
25																				

RECORD OF BOREHOLE: A-1

Sheet 2 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 05, 2025

END DATE: September 08, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 616.2 ft (Ground)

COORDINATES: Lat: 38.197944° Long: -81.486306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H (%)	O (%)	NP							
																		Plastic & Liquid Limits (%)	Water Content (%)	Nonplastic	
26	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	ALLUVIUM - (SM) SAND and SILT, fine to coarse, non plastic fines; light brown to dark brown; non-cohesive, wet, very loose to loose.	SM		586.2	S-8	DO	50	2-2-1	3	0	25	40	75	100	125	150			
27																					
28																					
29																					
30			End of hole at 30.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 18 ft and bentonite/cuttings to ground surface. Groundwater encountered at 19 ft below ground surface at the time of drilling.																		
31																					
32																					
33																					
34																					
35																					
36																					
37																					
38																					
39																					
40																					
41																					
42																					
43																					
44																					
45																					
46																					
47																					
48																					
49																					
50																					

Goldier Log Imperial / Soil-General 1 / Legacy Goldier - 3 Imperial US / Goldier US Auto (common in US) / 2005-12-04

RECORD OF BOREHOLE: A-2

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 08, 2025

END DATE: September 09, 2025

CONTRACTOR: Cascade




SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 618.0 ft (Ground)

COORDINATES: Lat: 38.198111° Long: -81.485361°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)									
												NP	Water Content (%)	Nonplastic							
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		Tree Mulch.	SM		0.0	S-1	DO	33	1-2-2	4										
CCR-SOIL MIX - (SM) SILTY SAND, fine to medium, non plastic fines, some fine gravel; dark gray banded light gray; non-cohesive, moist, loose, grass roots, branches and tree mulch.			617.8			O															
2																					
3			SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray to light gray; non-cohesive, moist, very loose to loose.	ML		615.5	S-2	DO	19	2-2-2	4										
4			- 2.5 to 8.0 ft: Trace tree branches and grass roots present.			2.5															
5																					
6																					
7																					
8																					
9																					
10																					
11																					
12																					
13																					
14							- 13.5 to 15.0 ft: Dark gray with light gray bands.														
15																					
16																					
17																					
18																					
19							- 18.5 to 19.8 ft: Dark gray with light gray bands and slightly wet.														
20					ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; light brown to brown; non-cohesive, moist to wet, very loose to loose.	SM		598.2	S-6	DO	50	2-3-3	6								
21					19.8																
22																					
23																					
24																					
25							S-7	DO	26	2-1-1	2										

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: A-2

Sheet 2 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 08, 2025

END DATE: September 09, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 618.0 ft (Ground)

COORDINATES: Lat: 38.198111° Long: -81.485361°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic								
26	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; light brown to brown; non-cohesive, moist to wet, very loose to loose.	SM			588.0	TO-2	TO	0							25.00 - 27.00 ft: Shelby tube attempted, however, shelly tube got stuck in the ground and could not be retrieved.				
27																					
28																					
29								S-8	DO	0	1-1.5	6									28.50 - 30.00 ft: No recovery, no material changes observed from Auger.
30			End of hole at 30.00 ft.																		
31			Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 18 ft and bentonite/cuttings to ground surface. Groundwater encountered at 20 ft below ground surface at the time of drilling.																		
32																					
33																					
34																					
35																					
36																					
37																					
38																					
39																					
40																					
41																					
42																					
43																					
44																					
45																					
46																					
47																					
48																					
49																					
50																					

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire

CHECKED: Naveen Kumar Ganji

DATE: Sep 08, 2025

DATE: Jan 28, 2026

RECORD OF BOREHOLE: A-3

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 10, 2025

CONTRACTOR: Cascade





SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.7 ft (Ground)

COORDINATES: Lat: 38.198139° Long: -81.483944°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)									
												NP	Water Content (%)	Nonplastic							
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR-SOIL MIX - (SM) gravelly SILTY SAND, fine to coarse, fine to coarse rounded to subrounded gravel, non plastic fines; grayish brown to gray; non-cohesive, moist, loose, grass roots and tree mulch present.	SM		0.0	S-1	DO	67	3-4.3	7	0	25	60	75	100	125	150			
2																					
3			SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, very loose to loose.	ML		617.2															
4																					
5																					
6																					
7																					
8																					
9																					
10																					
11																					
12																					
13																					
14					- 13.5 to 15.0 ft: Split spoon sample slightly wet.																
15																					
16																					
17																					
18																					
19					- 18.5 to 19.2 ft: Some fly ash observed.																
20					ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; light brown to grayish brown; non-cohesive, moist to wet, compact.	SM		600.4	S-6	DO	89	4-6.8	14	0	25	60	75	100		125	150
21																					
22																					
23						SM															
24																					
25					ALLUVIUM - (SC) CLAYEY SAND, fine to coarse, low plasticity fines; light brown to brown; cohesive, w ~ PL, soft.	SC		595.7	S-7	DO	78	3-4.6	10	0	25	60	75	100		125	150

5.00 - 7.00 ft: TO-1: Non-plastic.

18.50 - 20.00 ft: Samples collected as S-6A and S-6B.

10Sep25

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: A-3

Sheet 2 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 10, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.7 ft (Ground)

COORDINATES: Lat: 38.198139° Long: -81.483944°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic								
26	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	ALLUVIUM - (SC) CLAYEY SAND, fine to coarse, low plasticity fines; light brown to brown; cohesive, w ~ PL, soft.	SC		589.7	S-8	DO	67	2-1-1	2	1	O	25	40	75	100	125	150	28.50 - 30.00 ft: S-8: Non plastic.	
27																					
28																					
29																					
30	End of hole at 30.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 19 ft and bentonite/cuttings to ground surface. Groundwater encountered at 23.5 ft below ground surface at the time of drilling.																				
31																					
32																					
33																					
34																					
35																					
36																					
37																					
38																					
39																					
40																					
41																					
42																					
43																					
44																					
45																					
46																					
47																					
48																					
49																					
50																					

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: A-4

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: August 29, 2025

END DATE: September 04, 2025

CONTRACTOR: Cascade



SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 616.3 ft (Ground)

COORDINATES: Lat: 38.197417° Long: -81.485306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. ----- DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H						
												NP	Plastic & Liquid Limits (%)	Water Content (%)				Nonplastic
1	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	Tree Mulch. CCR-SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine to medium gravel; black to dark gray; non-cohesive, moist, loose to compact, roots and tree mulch present.	SM		0.0 616.0 0.2	S-1	DO	67	2-12	3							
2																		
3																		
4																		
5																		
6																		
7																		
8																		
9																		
10																		
11	Mud Rotary - 8.00-in Hole Dia.	- 18.5 to 20.0 ft: Trace fine gravel.	ML		607.0 9.3	S-4	DO	78	4-3-3	6								
12																		
13																		
14																		
15																		
16																		
17																		
18																		
19																		
20																		
21																		
22																		
23																		
24																		
25																		

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: A-4

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: August 29, 2025

END DATE: September 04, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 616.3 ft (Ground)

COORDINATES: Lat: 38.197417° Long: -81.485306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS
			DESCRIPTION	USCS	STRATA PLOT	ELEV. ----- DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H O NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic				
26	Geoprobe 8040 DT Mud Rotary - 8.00-in Hole Dia.		ALLUVIUM - (ML) SILT and SAND, non plastic fines, fine to coarse; brown to grayish brown; non-cohesive, wet, very loose to compact.	ML													
27																	
28																	
29																	
30																	
31																	
32																	
33																	
34																	
35																	
36	End of hole at 35.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 18 ft and bentonite/cuttings to ground surface.																
37																	
38																	
39																	
40																	
41																	
42																	
43																	
44																	
45																	
46																	
47																	
48																	
49																	
50																	

HAMMER TYPE: Automatic, 140lb, 30" drop



LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Aug 29, 2025
DATE: Jan 28, 2026

REV:

RECORD OF BOREHOLE: B-1

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 04, 2025

END DATE: September 05, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.0 ft (Ground)

COORDINATES: Lat: 38.197278° Long: -81.486639°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE			SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS			
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic						
1	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; dark gray to black; non-cohesive, moist, loose, roots and grasses present.	SM		0.0	S-1	DO	0	2-3	6								
2																			
3			SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray to light gray; non-cohesive, moist, very loose to loose, roots present. - 2.5 to 7.0 ft: Roots present.	ML		616.5 2.5	S-2	DO	45	2-2-3	5								
4																			
5																			
6																			
7							S-3	DO	67	1-2-3	5								
8																			
9							S-4	DO	33	1-1-2	3								
10																			
11																			
12	Mud Rotary - 8.00-in Hole Dia.	- 13.5 to 15.0 ft: Tree branch and leaf present.	ML		594.5 24.5	S-5	DO	33	2-1-1	2									
13																			
14																			
15																			
16																			
17																			
18																			
19						S-6	DO	100	1-0-0	0									
20																			
21																			
22		- 18.5 to 20.0 ft: Split spoon sample wet with light gray bands.	ML		594.5 24.5	S-7	DO	100	1-0-0	0									
23																			
24																			
25			DREDGE SPOIL, SAMPLED AS, (CL) SILTY CLAY, low plasticity, trace fine to medium sand; dark brown; cohesive, w ~ PL, very soft to soft.	CL															

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 04, 2025
DATE: Jan 28, 2026

Sheet 2 of 2

[illegible]

Golder Log Imperial / Soil-General 1 / Legacy Golder - 3 Imperial US / Golder US Auto (common in US) / 2025-12-04

RECORD OF BOREHOLE: B-2

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 10, 2025

CONTRACTOR: Cascade


SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 625.9 ft (Ground)

COORDINATES: Lat: 38.197056° Long: -81.484861°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS			
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	O NP	Plastic & Liquid Limits (%)				Water Content (%)	Nonplastic	
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, trace fine gravel; dark gray; non-cohesive, moist, loose, tree branches, and mulch present.	SM		0.0	S-1	DO	17	1-2-2	4									
2																				
3			SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose. - 2.5 to 8.0 ft: Trace soil present.	ML		623.4 2.5														
4							S-2	DO	17	3-1-1	2									
5																				
6																				
7																				
8																				
9																				
10										S-4	DO	72	1-2-2	4						
11																				
12																				
13																				
14										S-5	DO	55	1-2-2	4						
15																				
16																				
17																				
18																				
19										S-6	DO	67	1-4-3	7						
20																				
21																				
22																				
23																				
24										S-7	DO	67	2-1-2	3						
25																				

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 10, 2025
DATE: Jan 28, 2026

Sheet 2 of 2

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. ----- DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H O NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic					
26	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose.	ML														
27																		
28																		
29																		
30			DREDGE SPOIL, SAMPLED AS, (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; yellowish brown to grayish brown; non-cohesive, wet, very loose to loose, lenses of coal present.	SM														
31																		
32																		
33																		
34																		
35																		
36																		
37																		
38			ALLUVIUM - (ML) sandy SILT, non-plastic fines, fine to coarse; grayish brown to gray; non-cohesive, wet, very loose, trace clay.	ML														
39																		
40																		
41																		
42	End of hole at 40.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 28 ft and bentonite/cuttings to ground surface. Groundwater encountered at 28.5 ft below ground surface at the time of drilling.																	
43																		
44																		
45																		
46																		
47																		
48																		
49																		
50																		

Golder Log Imperial / Soil-General 1 / Legacy Golder - 3 Imperial US / Golder US Auto (common in US) / 2025-12-04

RECORD OF BOREHOLE: B-3

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: August 27, 2025

END DATE: August 29, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 617.4 ft (Ground)

COORDINATES: Lat: 38.197444° Long: -81.483944°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS																		
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic																						
1	Geoprobe 8040 DT Percussion - 3.62-in Hole Dia.		Tree Mulch.	SM		0.0	S-1	DO	17	1-2-3	5	0	25	40	75	100	125	150																	
			616.4																																
2			CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine to coarse gravel; dark gray; non-cohesive, moist, loose, soil inclusions. SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose to compact.																			1.0													
3					615.9																														
4			- 3.5 to 5.0 ft: Roots observed.		1.5				S-2	DO	33	3-4-5	9																						
5																																			
6																																			
7																																			
8																																			
9			- 8.5 to 10.0 ft: Tree mulch observed, potential artifact of drilling method.						S-4	DO	26	12-12-8	20																						
10																																			
11																																			
12																																			
13																																			
14										S-5	DO	100	16-30-24	54																					
15																																			
16																																			
17																																			
18																																			
19										S-6	DO	67	3-4-5	9																					
20																																			
21																																			
22																																			
23																																			
24										S-7	DO	100	1-2-2	4																					
25																																			

13.50 - 15.00 ft: High blow count, artifact of drilling method used.

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: B-3

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: August 27, 2025

END DATE: August 29, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 617.4 ft (Ground)

COORDINATES: Lat: 38.197444° Long: -81.483944°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS			
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%)					Water Content (%)		
													NP	Nonplastic				NP	Nonplastic	
26	Geoprobe 8040 DT Percussion - 3.62-in Hole Dia.		SLUICED CCR, SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose to compact.	ML																
27			ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; light brown; non-cohesive, wet, compact.	SM																
28																				
29																				
30									S-8	DO	89	6-8-9	17							
31																				
32																				
33																				
34						- 33.5 to 35.0 ft: Root present at bottom.				S-9	DO	67	6-9-8	17						
35																				
36																				
37							TO-1	TO	100											
38			End of hole at 37.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to 26 ft and bentonite/cuttings to ground surface. Groundwater encountered at 28.5 ft below ground surface at the time of drilling.																	
39																				
40																				
41																				
42																				
43																				
44																				
45																				
46																				
47																				
48																				
49																				
50																				

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire

CHECKED: Naveen Kumar Ganji

DATE: Aug 27, 2025

DATE: Jan 28, 2026

RECORD OF BOREHOLE: E-1

Sheet 1 of 2

CLIENT: AEP START DATE: September 12, 2025 ELEVATION: 618.0 ft (Ground)
 PROJECT: AEP Cabin Creek END DATE: September 15, 2025 COORDINATES: Lat: 38.197750° Long: -81.487944°
 PROJECT NO: US0041868.3924 COORD SYS: Geographical Coordinates
 LOCATION: Cabin Creek CONTRACTOR: Cascade
 SURVEYOR: Elevation From LiDAR Survey. HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)						
												NP	Water Content (%)	Nonplastic				
1	Geoprobe 8040 DT	Hollow Stem Auger (4.25"ID) - 8.00-in Hole Dia.	TOPSOIL - (ML) sandy SILT, non plastic, fine to coarse sand, some fine gravel; brown; non-cohesive, moist, compact, grass roots, leaves, and branches present. CCR - SOIL MIX - (SM) gravelly SILTY SAND, fine to coarse, non plastic fines, fine to coarse gravel; dark gray to black; non-cohesive, moist, compact, honeycombed slag gravel.	ML		0.0 617.5 0.5	S-1	DO	100	3-7-8	15	0	25	60	75	100	125	150
2			SM		614.0 4.0	S-2	DO	89	3-4-6	10	0	25	60	75	100	125	150	
3																		
4			ML		611.2 6.8	S-3	DO	67	2-4-10	14	0	25	60	75	100	125	150	
5																		
6			SM		609.2 8.8	S-4	DO	100	4-5-7	12	0	25	60	75	100	125	150	
7																		
8			ML		598.2 19.8	S-5	DO	100	1-2-1	3	0	25	60	75	100	125	150	
9																		
10			ML		598.2 19.8	S-6	DO	50	1-1-0	1	0	25	60	75	100	125	150	
11																		
12	Mud Rotary - 8.00-in Hole Dia.		EARTH FILL - (ML) SILT and SAND, non plastic fines, fine to coarse; brown to light brown; non-cohesive, wet, very loose, fine mica present.									0	25	60	75	100	125	150
13																		
14																		
15																		
16																		
17																		
18																		
19																		
20																		
21																		
22																		
23																		
24																		
25																		

Continued on Next Page

8.50 ft: Drill bit heated up while augering.

24.00 - 25.00 ft: Mud lost during drilling, no return.

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



LOGGED: Prakash Ghimire
 CHECKED: Naveen Kumar Ganji

DATE: Sep 12, 2025
 DATE: Jan 28, 2026

REV:

RECORD OF BOREHOLE: E-1

Sheet 2 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 12, 2025

END DATE: September 15, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 618.0 ft (Ground)

COORDINATES: Lat: 38.197750° Long: -81.487944°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS
			DESCRIPTION	USCS	STRATA PLOT	ELEV. ----- DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic				
26	Mud Rotary - 8.00-in Hole Dia.		EARTH FILL - (ML) SILT and SAND, non plastic fines, fine to coarse; brown to light brown; non-cohesive, wet, very loose, fine mica present.	ML				DO	45	0-0-0	0						
27																	
28																	
29							S-8	DO	28	1-2-2	4						
30																	
31																	
32			ALLUVIUM - (CL-ML) SILTY CLAY and SAND, low plasticity fines, fine to coarse; dark brown to grayish brown; cohesive, w ~ PL, firm, fine mica present.	CL-ML		586.2 31.8											
33																	
34																	
35							S-9	DO	100	1-2-4	6						
36																	
37																	
38	Geoprobe 8040 DT						TO-1	TO	92								
39																	
40																	
41	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; dark gray to black; non-cohesive, wet, loose, rounded natural to subangular coal gravel.	SM		578.5 39.5	S-10	DO	78	2-1-2	3						
42																	
43																	
44							S-11	DO	50	1-3-3	6						
45																	
46																	
47			ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; grayish brown; non-cohesive, wet, loose, trace shells, and coal pieces.			571.2 46.8											
48																	
49																	
50						568.0	S-12	DO	55	1-3-1	4						

RECORD OF BOREHOLE: E-2

Sheet 1 of 1

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 15, 2025

END DATE: September 16, 2025

CONTRACTOR: Cascade




SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.4 ft (Ground)

COORDINATES: Lat: 38.198056° Long: -81.487306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE			SAMPLES				WATER CONTENT					ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)									
												NP	Water Content (%)	Nonplastic							
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some gravel; dark gray to black; non-cohesive, moist, compact, coal pieces, tree branches, and organics present.	SM		0.0	S-1	DO	78	7-6-4	10										
2																					
3			CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray to light gray; non-cohesive, moist, compact, fly ash lenses.	ML		616.4 3.0	S-2	DO	78	3-5-9	14										
4																					
5																					
6																					
7																					
8																					
9			- 8.5 to 10.0 ft: Some fine to coarse coal gravel and lens of Silty Sand at top.																		
10																					
11																					
12																					
13																					
14																					
15							EARTH FILL - (SM) SAND and SILT, fine to coarse, non plastic fines; grayish brown to brown; non-cohesive, moist, loose to compact.	SM		605.2 14.2	S-5	DO	67	4-4-6	10						
16																					
17																					
18																					
19																					
20																					
21																					
22																					
23																					
24																					
25																					
			- 18.5 to 20.0 ft: Fine mica.																		

Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater not encountered, caved in at 20 ft below ground surface.

HAMMER TYPE: Automatic, 140lb, 30" drop

REV:

RECORD OF BOREHOLE: E-3

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 16, 2025

CONTRACTOR: Cascade




SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 617.9 ft (Ground)

COORDINATES: Lat: 38.198361° Long: -81.486306°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT					ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)							
												NP	Water Content (%)	Nonplastic					
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; dark gray to black; non-cohesive, moist, loose, grass roots, organics, coal, and honeycombed slag pieces.	SM		0.0	S-1	DO	78	3-4-3	7	H O NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic						
2																			
3																			
4																			
5				CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; gray to light gray; non-cohesive, moist, loose to compact.	ML		613.2 4.8	S-2	DO	55	2-3-3	6							
6																			
7																			
8																			
9				EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines; yellowish brown to brown; non-cohesive, moist, loose to compact.	SM		609.4 8.5	S-3	DO	72	4-7-10	17							
10																			
11																			
12																			
13																			
14																			
15																			
16																			
17																			
18																			
19																			
20																			
21																			
22																			
23																			
24																			
25																			

HAMMER TYPE: Automatic, 140lb, 30" drop



LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 16, 2025
DATE: Jan 28, 2026

REV:

RECORD OF BOREHOLE: E-4

Sheet 1 of 1

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 16, 2025

CONTRACTOR: Cascade


SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.0 ft (Ground)

COORDINATES: Lat: 38.198528° Long: -81.485444°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS		
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)							
												NP	Water Content (%)	Nonplastic					
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some medium gravel; dark gray to black; non-cohesive, moist, compact, tree branches, coal, and honeycombed slag pieces.	SM		0.0	S-1	DO	89	4-8-9	17								
2																			
3			CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to coarse sand; dark gray banded light gray; non-cohesive, moist, loose to compact, fly ash lenses.	ML		616.8 2.2													
4							S-2	DO	72	4-7-6	13								
5																			
6																			
7							S-3	DO	83	5-7-8	15								
8																			
9																			
10			- 9.5 to 10.0 ft: Lens of bottom ash (Silty Sand) with trace honeycombed slag gravel.				S-4	DO	55	3-3-2	5								
11																			
12																			
13																			
14			- 13.5 to 14.4 ft: Some fine honeycombed slag gravel.																
15			EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines; yellowish brown to light brown, ; non-cohesive, moist, loose to compact, fine mica and brown bands.	SM		604.6 14.4	S-5	DO	72	7-4-4	8								
16																			
17																			
18																			
19								S-6	DO	72	8-5-5	10							
20																			
21																			
22																			
23																			
24			- 24.0 ft: Split spoon sample slightly wet.					S-7	DO	78	2-2-3	5							
25						594.0													

End of hole at 25.00 ft.

Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater and cave in not observed.

HAMMER TYPE: Automatic, 140lb, 30" drop

REV:

LOGGED: Prakash Ghimire

CHECKED: Naveen Kumar Ganji

DATE: Sep 16, 2025

DATE: Jan 28, 2026

RECORD OF BOREHOLE: E-5

Sheet 1 of 1

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 16, 2025

CONTRACTOR: Cascade



SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.0 ft (Ground)

COORDINATES: Lat: 38.198722° Long: -81.484667°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%)								
													Water Content (%)	Nonplastic							
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine to coarse gravel; gray to grayish brown; non-cohesive, moist, compact, tree roots, branches, leaves, honeycombed slag, and natural gravel.	SM		0.0	S-1	DO	100	26-7	13	0	25	60	75	100	125	150	3.50 ft: Auger cuttings return slightly wet.		
2			CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose to compact.	ML		617.5	1.5														
3																					
4									S-2	DO	39	6-6-5	11								
5																					
6							- 6.0 to 7.5 ft: Lens of yellowish brown natural Silty Sand.														
7									S-3	DO	72	7-4-5	9								
8																					
9									S-4	DO	72	6-7-5	12				0				
10																					
11																					
12																					
13																					
14					- 13.5 to 14.2 ft: Trace fine honeycombed slag gravel.																
15					EARTH FILL - (SM) SILTY SAND, fine to coarse; yellowish brown to grayish brown; non-cohesive, moist, very loose to compact, fine mica.	SM		604.8	S-5	DO	67	5-5-4	9								
16								14.2													
17																					
18																					
19																					
20									S-6	DO	100	4-5-6	11				0				
21																					
22																					
23																					
24																					
25							S-7	DO	33	1-1-1	2										
						594.0															

RECORD OF BOREHOLE: E-6

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 17, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 624.2 ft (Ground)

COORDINATES: Lat: 38.198750° Long: -81.483639°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE					SAMPLES				WATER CONTENT		ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS																				
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic																							
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; dark gray; non-cohesive, moist, loose, tree roots, branches, and mulch present. CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose. - 3.5 to 5.0 ft: Roots present. - 6.0 to 7.5 ft: Roots present.	ML		0.0	S-1	DO	67	3-4	7	O	25																							
624.0						33			2-2-1	3	40																									
0.2																																				
615.3						S-2			DO	83	1-1-1		2				O	75																		
9			CCR (BOTTOM ASH), SAMPLED AS, (SM) SILTY SAND, fine to coarse, non plastic fines, trace fine gravel; grayish black; non-cohesive, moist, very loose to loose. - 13.5 to 15.0 ft: Thin mixed ash lens at top.	SM		8.9	S-4	DO	83	1-1-1	2	O	75																							
605.4						S-5			DO	72	1-3-4		7				40																			
19						EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines, trace fine gravel; yellowish brown to grayish brown; non-cohesive, moist, loose to compact, black bands. - 23.5 to 25.0 ft: Fine mica.					18.8		S-6				DO	100	3-9-12	21	O	75														
24													S-7				DO	89	3-4-4	8	O	40														

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: E-6

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 17, 2025

CONTRACTOR: Cascade


SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 624.2 ft (Ground)

COORDINATES: Lat: 38.198750° Long: -81.483639°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS			
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H O NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic							
26	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines, trace fine gravel; yellowish brown to grayish brown; non-cohesive, moist, loose to compact, black bands. - 28.5 to 30.0 ft: Grayish brown, and lens of coal.	SM		594.2	S-8	DO	67	4-22	4	25	50	75	100	125	150			
27																				
28																				
29																				
30			End of hole at 30.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater not encountered, caved in at 15 ft below ground surface.																	
31																				
32																				
33																				
34																				
35																				
36																				
37																				
38																				
39																				
40																				
41																				
42																				
43																				
44																				
45																				
46																				
47																				
48																				
49																				
50																				

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire

CHECKED: Naveen Kumar Ganji

DATE: Sep 17, 2025

DATE: Jan 28, 2026

RECORD OF BOREHOLE: E-7

Sheet 1 of 1

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

START DATE: September 17, 2025

END DATE: September 17, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 619.9 ft (Ground)

COORDINATES: Lat: 38.198306° Long: -81.482889°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS		
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic						
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; grayish brown to yellowish brown; non-cohesive, moist, compact, tree branches, mulch, and grass roots present.	SM		0.0	S-1	DO	67	2-8	10	O	25			3.00 ft: Auger cuttings return slightly wet.			
618.6																			
2			CCR (BOTTOM ASH), SAMPLED AS, (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; dark gray to grayish black; non-cohesive, moist, loose to compact, honeycombed slag, and coal pieces.			1.2													
3																			
4							S-2	DO	45	4-3-4	7								
5																			
6																			
7							S-3	DO	89	7-9-14	23								
8			EARTH FILL - (SM) SAND and SILT, fine to coarse, non plastic fines; yellowish brown to grayish brown; non-cohesive, moist, loose to compact, fine mica, some black spots.			612.4													
9						7.5													
10							S-4	DO	78	7-12-11	23								
11																			
12																			
13																			
14							S-5	DO	0	1-2-4	6								
15																			
16																			
17																			
18																			
19							- 18.5 to 20.0 ft: One decayed tree root.												
20						599.9	S-6	DO	78	3-4-5	9	O							
21			End of hole at 20.00 ft.																
22			Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater not encountered, caved in at 10 ft below ground surface.																
23																			
24																			
25																			

HAMMER TYPE: Automatic, 140lb, 30" drop



LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 17, 2025
DATE: Jan 28, 2026

REV:

RECORD OF BOREHOLE: E-8

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 11, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 618.8 ft (Ground)

COORDINATES: Lat: 38.197139° Long: -81.484139°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)						
												NP	Water Content (%)	Nonplastic				
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; grayish brown to dark gray; non-cohesive, moist, compact, tree roots, and branches present.	SM		0.0	S-1	DO	33	3-6-5	11							
2																		
3																		
4			EARTH FILL - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine to coarse gravel; grayish brown to yellowish brown; non-cohesive, moist, compact, tree roots and black spottings.		614.8 4.0	S-2	DO	61	6-7-10	17								
5																		
6			CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine gravel; grayish brown to dark gray; non-cohesive, moist, compact, tree roots and branches, honeycombed slag gravel.		612.8 6.0	S-3	DO	78	6-10-11	21								
7																		
8																		
9			- 8.5 to 9.5 ft: Trace coarse gravel, and ash inclusions. - 8.5 to 10.0 ft: Coal and honeycombed slag gravel.															
10			CCR (MIXED ASH), SAMPLED AS, (ML) sandy SILT, non plastic, fine to medium sand; dark gray banded light gray; non-cohesive, moist, loose.	ML	609.3 9.5	S-4	DO	72	7-4-5	9								
11																		
12																		
13																		
14																		
15			DREDGE SPOIL, SAMPLED AS, (SM) SILTY SAND, fine to coarse, non plastic fines; brown to yellowish brown; non-cohesive, moist to wet, loose. - 14.5 ft: Lens of Earthfill, and Split spoon sample slightly wet.	SM	604.3 14.5	S-5	DO	55	2-2-4	6								
16																		
17																		
18																		
19			- 18.5 to 20.0 ft: Some black bands, and fine mica present.				S-6	DO	45	2-2-2	4							
20																		
21																		
22			ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; grayish brown to light gray; non-cohesive, wet, very loose to compact, fine mica present.		597.0 21.8													
23																		
24									S-7	DO	55	5-6-8	14					
25																		

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

RECORD OF BOREHOLE: E-8

Sheet 2 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 11, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 618.8 ft (Ground)

COORDINATES: Lat: 38.197139° Long: -81.484139°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS	
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)						
												NP	Water Content (%)	Nonplastic				
26	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.		ALLUVIUM - (SM) SILTY SAND, fine to coarse, non plastic fines; grayish brown to light gray; non-cohesive, wet, very loose to compact, fine mica present. - 29.0 to 30.0 ft: Lens of low plasticity Silty Clay with some fine sand. - 30.0 ft: Lens of coal/ash at bottom of split spoon.	SM			S-8	DO	100	2-1-1	2	O	O					
27																		
28																		
29																		
30																		
31																		
32																		
33																		
34																		
35																		End of hole at 35.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater encountered at 29 ft below ground surface at the time of drilling.
36																		
37																		
38																		
39																		
40																		
41																		
42																		
43																		
44																		
45																		
46																		
47																		
48																		
49																		
50																		

HAMMER TYPE: Automatic, 140lb, 30" drop



LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 11, 2025
DATE: Jan 28, 2026

REV:

RECORD OF BOREHOLE: E-9

Sheet 1 of 2

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 11, 2025

CONTRACTOR: Cascade


SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 617.4 ft (Ground)

COORDINATES: Lat: 38.196806° Long: -81.485333°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT						ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																															
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	Plastic & Liquid Limits (%)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																						
												NP	Water Content (%)	Nonplastic																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				
1	Geoprobe 8040 DT Hollow Stem Auger (4.25" ID) - 8.00in Hole Dia.		CCR - SOIL MIX - (SM) SILTY SAND, fine to coarse, non plastic fines, some fine to coarse gravel; dark gray to grayish brown; non-cohesive, moist, compact, roots, and coal pieces present.	SM		0.0	S-1	DO	72	2-5-5	10																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																							

Continued on Next Page

HAMMER TYPE: Automatic, 140lb, 30" drop



REV:

LOGGED: Prakash Ghimire
CHECKED: Naveen Kumar Ganji

DATE: Sep 11, 2025
DATE: Jan 28, 2026

RECORD OF BOREHOLE: E-9

CLIENT: AEP

PROJECT: AEP Cabin Creek

PROJECT NO: US0041868.3924

LOCATION: Cabin Creek

DATE: September 11, 2025

CONTRACTOR: Cascade

SURVEYOR: Elevation From LiDAR Survey.

ELEVATION: 617.4 ft (Ground)

COORDINATES: Lat: 38.196806° Long: -81.485333°

COORD SYS: Geographical Coordinates

HORZ DATUM: NAD83

DEPTH (ft)	DRILL RIG	DRILL METHOD	MATERIAL PROFILE				SAMPLES				WATER CONTENT				ADDITIONAL LAB TESTING	GROUNDWATER OBSERVATIONS	ADDITIONAL OBSERVATIONS
			DESCRIPTION	USCS	STRATA PLOT	ELEV. DEPTH (ft)	NUMBER	TYPE	REC %	BLOWS	N-VALUE	H O NP	Plastic & Liquid Limits (%) Water Content (%) Nonplastic				
26	Geoprobe 8040 DT	Hollow Stem Auger (4.25" ID) - 8.00-in Hole Dia.	ALLUVIUM - (SM) SAND and SILT, fine to coarse, non plastic fines, trace fine rounded to subrounded gravel; grayish brown to dark gray; non-cohesive, wet, very loose, ash lenses with coal pieces.	SM			S-8	DO	72	2-21	3	0	O				
27																	
28																	
29																	
30			End of hole at 30.00 ft. Borehole terminated after drilling 10 ft below bottom of ash. Backfilled with bentonite up to ground surface and topped off with cuttings. Groundwater encountered at 23.5 ft below ground surface at the time of drilling.			587.4											
31																	
32																	
33																	
34																	
35																	
36																	
37																	
38																	
39																	
40																	
41																	
42																	
43																	
44																	
45																	
46																	
47																	
48																	
49																	
50																	

APPENDIX D

Geotechnical Laboratory Test Reports

**AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA**

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classification	As-R'c'd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
A-1	S-5	13.5-15.0'	Bag	-	70.2	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-1	S-7	23.5-25.0'	Bag	SM	29.5	NP	NP	NP	NP	100.0	49.7	10.3	-	-	2.71	-	-	-	-
A-2	S-1	0.0-1.5'	Bag	-	61.8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-2	S-5	13.5-15.0'	Bag	-	63.1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-2	S-7	23.5-25.0'	Bag	-	22.8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-3	S-1	0.0-1.5'	Bag	-	11.2	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-3	S-6A	18.5-20.0'	Bag	-	52.8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-3	S-7	23.5-25.0'	Bag	-	19.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-3	S-8	28.5-30.0'	Bag	-	21.9	NP	NP	NP	NP	-	-	-	-	-	-	-	-	-	-
A-4	S-1	0.0-1.5'	Bag	-	25.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-
A-4	S-7	23.5-25.0'	Bag	ML	34.5	NP	NP	NP	NP	100.0	60.2	9.8	-	-	2.62	-	-	-	-
B-1	S-3	6.0-7.5'	Bag	-	49.2	-	-	-	-	-	-	-	-	-	-	-	-	-	-
B-1	S-6	18.5-20.0'	Bag	-	99.2	-	-	-	-	-	-	-	-	-	-	-	-	-	-
B-1	S-8	28.5-30.0'	Bag	CL	51.4	45	24	21	1.30	100.0	96.1	-	-	-	-	-	-	-	-
B-2	S-7	23.5-25.0'	Bag	-	70.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-

ABBREVIATIONS: LIQUID LIMIT (LL)
PLASTIC LIMIT (PL)
PLASTICITY INDEX (PI)
LIQUIDITY INDEX (LI)
SPECIFIC GRAVITY (Gs)

NOTES: T = TRIAXIAL TEST
U = UNCONFINED COMPRESSION TEST
C = CONSOLIDATION TEST
DS = DIRECT SHEAR TEST

WATER CONTENT DETERMINATION

ASTM D2216

PROJECT TITLE
PROJECT NUMBER
REMARKS

AEP/CABIN CREEK/GA

US-0041868.3924

Sample Type	Bag	Bag	Bag	Bag	Bag
Borehole Number	A-1	A-2	A-2	A-2	A-3
Sample Number	S-5	S-1	S-5	S-7	S-1
Depth of Sample (ft)	13.5-15.0'	0.0-1.5'	13.5-15.0'	23.5-25.0'	0.0-1.5'
Weight of Wet Soil + Tare (gm)	233.45	141.22	244.61	267.95	268.42
Weight of Dry Soil + Tare (gm)	154.94	106.79	169.67	227.92	245.66
Weight of Tare (gm)	43.17	51.09	50.91	52.06	42.56
Weight of Water (gm)	78.51	34.43	74.94	40.03	22.76
Weight of Dry Soil (gm)	111.77	55.70	118.76	175.86	203.10
Water Content (%)	70.2	61.8	63.1	22.8	11.2

Sample Type	Bag	Bag	Bag	Bag	Bag
Borehole Number	A-3	A-3	A-4	B-1	B-1
Sample Number	S-6A	S-7	S-1	S-3	S-6
Depth of Sample (ft)	18.5-20.0'	23.5-25.0'	0.0-1.5'	6.0-7.5'	18.5-20.0'
Weight of Wet Soil + Tare (gm)	206.87	351.56	172.13	232.58	342.58
Weight of Dry Soil + Tare (gm)	150.17	302.22	147.55	172.92	197.43
Weight of Tare (gm)	42.84	51.65	51.88	51.75	51.17
Weight of Water (gm)	56.70	49.34	24.58	59.66	145.15
Weight of Dry Soil (gm)	107.33	250.57	95.67	121.17	146.26
Water Content (%)	52.8	19.7	25.7	49.2	99.2

Sample Type	Bag				
Borehole Number	B-2				
Sample Number	S-7				
Depth of Sample (ft)	23.5-25.0'				
Weight of Wet Soil + Tare (gm)	287.72				
Weight of Dry Soil + Tare (gm)	190.06				
Weight of Tare (gm)	51.79				
Weight of Water (gm)	97.66				
Weight of Dry Soil (gm)	138.27				
Water Content (%)	70.6				

TECH	JC
DATE	10/7/25
CHECK	
REVIEW	
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D421, D422, D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: A-1, S-7

Depth: 23.5-25.0'

TYPE: Bag



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			Particle Size	
		% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0	Coarse Gravel	0.0
1.5"	37.5	100.0		
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	100.0	Fine Gravel	0.0
#4	4.8	100.0		
#10	2.00	100.0	Coarse Sand	0.0
#20	0.85	100.0	Medium Sand	0.1
#40	0.43	99.9		
#60	0.25	95.9		
#100	0.15	77.4	Fine Sand	50.2
#140	0.106	62.1		
#200	0.034	49.7		


Hydrometer Analysis

(mm)	% Finer		
0.075	31.6	Fines Silt or Clay	49.7
0.022	25.7		
0.013	21.8		
0.0090	17.8		
0.0064	16.8		
0.0032	11.9		
0.0013	8.9		

DESCRIPTION: SAND and SILT, fine to medium; dark grayish brown.

USCS: SM

PLASTICITY CHART



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
29.5	NP	NP	NP	NP

LL (oven-dried)

< 0.75 = ORGANIC (OL OH)

TECH EK/TB/JC

DATE 10/7/25

CHECK REVIEW

APPROVE

SPECIFIC GRAVITY OF SOILS

ASTM D854

PYCNUMETER METHOD

PROJECT TITLE	AEP/CABIN CREEK/GA	SAMPLE ID	A-1, S-7
PROJECT NUMBER	US-0041868.3924	SAMPLE DEPTH	23.5-25.0'
TESTED FOR	Gs	SAMPLE TYPE	Bag

HYGROSCOPIC MOISTURE CONTENT OF MATERIAL PASSING THE #4 SIEVE

Weight of Soil and Tare, Initial (g)	92.86
Weight of Soil and Tare, Final (g)	92.60
Weight of Tare (g)	51.51
Weight of Moisture (g)	0.26
Weight of Dry Soil (g)	41.09
Hygroscopic Moisture Content	0.6%

Test Method

Method - B

Pycnometer Number

Weight of Pycnometer (g)	13
Volume of Pycnometer (mL)	177.86
Weight of Pycnometer and Water (g)	499.32
Mass of Pycnometer and Water at the Test Temperature (A)	676.10
Observed Temperature (Tb), for (Mb) (°C)	675.93
	23.1

Weight of Soil, Water & Pycnometer (g)

(B) 708.03

Temperature (°C)

23.1

Density of Water @ Tested Temperature (g/mL)

0.9975

Tare Number

-

Weight of Dry Soil Slurry plus Tare (g)

181.77

Weight of Tare (g)

131.00

Weight of Dry Soil (g)

(C) 50.77

Temperature Coefficient

0.9979

SPECIFIC GRAVITY (G)

2.71

$G @ 20^{\circ}C = [C/(A-(B-C))]*(K)$

METHOD - A

WET METHOD

METHOD OF AIR REMOVAL

METHOD - B

OVEN-DRIED METHOD

VACUUM

Maximum Particle Size of Reduced Sample	Specimen Dry Mass (g) when using 500 mL Pycnometer	
	(Minimum)	(Maximum)
No. 100	30	75
No. 40	40	100
No. 10	50	125
No. 4	75	200
3/8 in.	165	300

TECH CJ

DATE 10/8/25

CHECK *fl*

REVIEW *fl*

APPROVE

ATTERBERG LIMITS

ASTM D4318

PROJECT NAME: AEP/CABIN CREEK/GA

PROJECT NUMBER: US-0041868.3924

SAMPLE ID: A-3, S-8

SAMPLE DEPTH: 28.5-30.0'

SAMPLE TYPE: Bag

Sample Preparation:

Wet or Dry

Minus #40 Sieve

**AS-RECEIVED
MOISTURE**

PLASTIC LIMIT

LIQUID LIMIT

Number of Blows		
Wt. of Wet Soil & Tare (g)	25.20	26.02
Wt. of Dry Soil & Tare (g)	22.76	23.42
Weight of Tare (g)	11.37	11.41
Weight of Water (g)	2.44	2.60
Weight of Dry Soil (g)	11.39	12.01
Water Content %	21.4	21.6

12	12
24.44	21.72
21.32	19.09
6.65	6.69
3.12	2.63
14.67	12.40
21.3	21.2

191.61
168.44
62.45
23.17
105.99
21.9

PLASTIC LIMIT (PL)

LIQUID LIMIT (LL)


PLASTICITY INDEX (PI)

LIQUIDITY INDEX (LI)

NOTE:

DESCRIPTION:

USCS:



TECH TB

DATE 10/9/25


CHECK *[Signature]*

REVIEW *[Signature]*

APPROVE

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D421, D422, D4318

PROJECT NAME: **AEP/CABIN CREEK/GA**SAMPLE ID: **A-4, S-7**Depth: **23.5-25.0'**TYPE: **Bag**


COBBLES	Coarse GRAVEL	Fine GRAVEL	Coarse SAND	Medium SAND	Fine SAND	Silt or Clay FINES
---------	---------------	-------------	-------------	-------------	-----------	--------------------

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	
0.50"	12.7	100.0	
0.375"	9.5	100.0	
#4	4.8	100.0	
#10	2.00	99.9	
#20	0.85	99.8	
#40	0.43	99.4	
#60	0.25	98.1	
#100	0.15	87.5	
#140	0.106	72.0	
#200	0.033	60.2	

Hydrometer Analysis

(mm)	% Finer	
0.033	33.8	
0.021	27.8	
0.013	22.8	
0.0090	18.9	
0.0064	15.9	
0.0032	11.9	
0.0013	7.9	

DESCRIPTION: **SILT and SAND, fine to coarse; very dark grayish brown.**USCS: **ML****ATTERBERG LIMITS**

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
34.5	NP	NP	NP	NP

LL (oven-dried)
< 0.75 = ORGANIC
(OL OH)

TECH **EK/TB/JC**
 DATE **10/7/25**
 CHECK **[Signature]**
 REVIEW **[Signature]**
 APPROVE **[Signature]**

SPECIFIC GRAVITY OF SOILS

ASTM D854

PYCNOMETER METHOD

PROJECT TITLE	AEP/CABIN CREEK/GA	SAMPLE ID	A-4, S-7
PROJECT NUMBER	US-0041868.3924	SAMPLE DEPTH	23.5-25.0'
TESTED FOR	Gs	SAMPLE TYPE	Bag

HYGROSCOPIC MOISTURE CONTENT OF MATERIAL PASSING THE #4 SIEVE

Weight of Soil and Tare, Initial (g)	223.82
Weight of Soil and Tare, Final (g)	223.08
Weight of Tare (g)	51.10
Weight of Moisture (g)	0.74
Weight of Dry Soil (g)	171.98
Hygroscopic Moisture Content	0.4%

Test Method

Method - B

Pycnometer Number

Pycnometer Number	22
Weight of Pycnometer (g)	165.59
Volume of Pycnometer (mL)	499.43
Weight of Pycnometer and Water (g)	663.99
Mass of Pycnometer and Water at the Test Temperature (A)	663.79
Observed Temperature (Tb), for (Mb) (°C)	23.0

Weight of Soil, Water & Pycnometer (g)

(B) 711.97

Temperature (°C)

23.0

Density of Water @ Tested Temperature (g/mL)

0.9975

Tare Number

-

Weight of Dry Soil Slurry plus Tare (g)

217.87

Weight of Tare (g)

140.04

Weight of Dry Soil (g)

(C) 77.83

Temperature Coefficient

0.9979

SPECIFIC GRAVITY (G)

2.62

$G @ 20^{\circ}C = [C/(A-(B-C))]*(K)$

METHOD - A

WET METHOD

METHOD OF AIR REMOVAL

METHOD - B


OVEN-DRIED METHOD

VACUUM

Maximum Particle Size of Reduced Sample	Specimen Dry Mass (g) when using 500 mL Pycnometer	
	(Minimum)	(Maximum)
No. 100	30	75
No. 40	40	100
No. 10	50	125
No. 4	75	200
3/8 in.	165	300

TECH CJ

DATE 10/8/25

CHECK 

REVIEW

APPROVE

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: B-1, S-8

Depth: 28.5-30.0'


TYPE: Bag



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles		0.0
3.0"	75.0	100.0			
2.5"	63.5	100.0			
2.0"	50.0	100.0			
1.5"	37.5	100.0			
1.0"	25.0	100.0	Coarse Gravel		0.0
0.75"	19.0	100.0			
0.50"	12.7	100.0			
0.375"	9.5	100.0			
#4	4.8	100.0			
#10	2.00	100.0	Fine Gravel		0.0
#20	0.85	99.9	Coarse Sand		0.0
#40	0.43	99.8	Medium Sand		0.2
#60	0.25	99.4			
#100	0.15	97.8			
#140	0.11	96.9	Fine Sand		3.7
#200	0.08	96.1			



ATTERBERG LIMITS
Method - B (Dry preparation)

M _c	LL	PL	PI	LI
51.4	45	24	21	1.30

DESCRIPTION: SILTY CLAY, trace fine to coarse sand; very dark grayish brown.

USCS: CL

LL (oven-dried)
< 0.75 = ORGANIC (LO OH)

TECH: EK/JC
DATE: 10/7/25
CHECK: [Signature]
REVIEW: [Signature]
APPROVE: [Signature]

**AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA**

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classification	As-R'cvd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
B-2	S-8	28.5-30.0'	Bag	-	28.5	-	-	-	-	93.7	22.1	-	-	-	-	-	-	-	-
B-2	S-10	38.5-40.0'	Bag	-	30.4	-	-	-	-	100.0	67.8	-	-	-	-	-	-	-	-
B-3	S-2	3.5-5.0'	Bag	-	58.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-
B-3	S-8	28.5-30.0'	Bag	-	27.4	-	-	-	-	99.7	19.8	-	-	-	-	-	-	-	-
E-1	S-1	0.0-1.5'	Bag	-	17.8	-	-	-	-	76.1	18.9	-	-	-	-	-	-	-	-
E-1	S-6	18.5-20.0'	Bag	-	29.1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-1	S-7	25.0-26.5'	Bag	-	29.2	-	-	-	-	99.1	52.6	-	-	-	-	-	-	-	-
E-1	S-12	48.5-50.0'	Bag	-	32.8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-2	S-1	0.0-1.5'	Bag	-	19.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-2	S-3	6.0-7.5'	Bag	-	39.3	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-2	S-5	13.5-15.0'	Bag	-	13.9	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-2	S-7	23.5-25.0'	Bag	-	17.7	-	-	-	-	99.9	47.3	-	-	-	-	-	-	-	-
E-3	S-4	8.5-10.0'	Bag	-	8.1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-3	S-6	18.5-20.0'	Bag	-	14.9	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-4	S-1	0.0-1.5'	Bag	-	19.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-

ABBREVIATIONS: LIQUID LIMIT (LL)
PLASTIC LIMIT (PL)
PLASTICITY INDEX (PI)
LIQUIDITY INDEX (LI)
SPECIFIC GRAVITY (Gs)

NOTES: T = TRIAXIAL TEST
U = UNCONFINED COMPRESSION TEST
C = CONSOLIDATION TEST
DS = DIRECT SHEAR TEST

WATER CONTENT DETERMINATION

ASTM D2216

PROJECT TITLE
PROJECT NUMBER
REMARKS

AEP/CABIN CREEK/GA

US-0041868.3924

Sample Type	Bag	Bag	Bag	Bag	Bag
Borehole Number	B-3	E-1	E-1	E-2	E-2
Sample Number	S-2	S-6	S-12	S-1	S-3
Depth of Sample (ft)	3.5-5.0'	18.5-20.0'	48.5-50.0'	0.0-1.5'	6.0-7.5'
Weight of Wet Soil + Tare (gm)	185.83	287.01	290.32	213.06	245.67
Weight of Dry Soil + Tare (gm)	136.27	234.10	231.23	186.38	191.08
Weight of Tare (gm)	51.51	52.33	51.07	51.29	52.05
Weight of Water (gm)	49.56	52.91	59.09	26.68	54.59
Weight of Dry Soil (gm)	84.76	181.77	180.16	135.09	139.03
Water Content (%)	58.5	29.1	32.8	19.7	39.3

Sample Type	Bag	Bag	Bag	Bag	
Borehole Number	E-2	E-3	E-3	E-4	
Sample Number	S-5	S-4	S-6	S-1	
Depth of Sample (ft)	13.5-15.0'	8.5-10.0'	18.5-20.0'	0.0-1.5'	
Weight of Wet Soil + Tare (gm)	279.02	295.90	302.22	230.17	
Weight of Dry Soil + Tare (gm)	251.20	276.89	268.59	200.79	
Weight of Tare (gm)	51.65	41.22	43.34	51.46	
Weight of Water (gm)	27.82	19.01	33.63	29.38	
Weight of Dry Soil (gm)	199.55	235.67	225.25	149.33	
Water Content (%)	13.9	8.1	14.9	19.7	

Sample Type
Borehole Number
Sample Number
Depth of Sample (ft)
Weight of Wet Soil + Tare (gm)
Weight of Dry Soil + Tare (gm)
Weight of Tare (gm)
Weight of Water (gm)
Weight of Dry Soil (gm)
Water Content (%)


TECH	JC
DATE	10/7/25
CHECK	
REVIEW	
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: B-2, S-8
TYPE: Bag


Depth: 28.5-30.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	
0.50"	12.7	98.5	
0.375"	9.5	97.7	
#4	4.8	93.7	
#10	2.00	89.6	
#20	0.85	84.5	
#40	0.43	79.8	
#60	0.25	75.7	
#100	0.15	56.2	
#140	0.11	33.9	
#200	0.08	22.1	
		Fines	22.1



ATTERBERG LIMITS
Method - B (Dry preparation)

M _c	LL	PL	PI	LI
28.5				

LL (oven-dried)
< 0.75 = ORGANIC (OL OH)

TECH EK/JC
DATE 10/7/25
CHECK ☒
REVIEW ☒
APPROVE ☒


DESCRIPTION:
USCS:

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA
 SAMPLE ID: B-2, S-10
 TYPE: Bag


Depth: 38.5-40.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles		0.0
3.0"	75.0	100.0			
2.5"	63.5	100.0			
2.0"	50.0	100.0			
1.5"	37.5	100.0			
1.0"	25.0	100.0	Coarse Gravel		0.0
0.75"	19.0	100.0			
0.50"	12.7	100.0			
0.375"	9.5	100.0	Fine Gravel		0.0
#4	4.8	100.0			
#10	2.00	99.9	Coarse Sand		0.1
#20	0.85	99.7	Medium Sand		0.7
#40	0.43	99.3			
#60	0.25	98.5			
#100	0.15	92.9	Fine Sand		31.5
#140	0.11	80.1			
#200	0.08	67.8			
Fines					



ATTERBERG LIMITS
 Method - B (Dry preparation)

M_c	LL	PL	PI	LI
30.4				

LL (oven-dried)
 < 0.75 = ORGANIC (OL, OH)

TECH: EK/JC
 DATE: 10/7/25
 CHECK: ☒
 REVIEW: ☒
 APPROVE: ☒

DESCRIPTION:
 USCS:

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: B-3, S-8

Depth: 28.5-30.0'


TYPE: Bag



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)		% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0	Coarse Gravel	0.0
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	100.0		
#4	4.8	99.7	Fine Gravel	0.3
#10	2.00	99.0	Coarse Sand	0.7
#20	0.85	98.2	Medium Sand	2.1
#40	0.43	96.9		
#60	0.25	86.3		
#100	0.15	46.8	Fine Sand	77.2
#140	0.11	30.0		
#200	0.08	19.8		



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
27.4				

LL (oven-dried)

< 0.75 = ORGANIC (LO OH)

TECH EK/JC

DATE 10/7/25

CHECK

REVIEW

APPROVE

DESCRIPTION: -


USCS: -

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: E-1, S-1
TYPE: Bag


Depth: 0.0-1.5'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	Cobbles	0.0
3.0"	75.0		
2.5"	63.5		
2.0"	50.0		
1.5"	37.5		
1.0"	25.0	Coarse Gravel	7.8
0.75"	19.0		
0.50"	12.7		
0.375"	9.5	Fine Gravel	16.1
#4	4.8		
#10	2.00		
#20	0.85	Coarse Sand	18.9
#40	0.43		
#60	0.25		
#100	0.15	Medium Sand	20.2
#140	0.11		
#200	0.08		
		Fine Sand	18.1
		Fines	18.9



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
17.8				

DESCRIPTION:

USCS:

LL (oven-dried)

< 0.75 = ORGANIC (OL OH)

TECH EK/JC

DATE 10/7/25

CHECK

REVIEW

APPROVE

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-1, S-7

Depth: 25.0-26.5'


TYPE: Bag



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles		0.0
3.0"	75.0	100.0			
2.5"	63.5	100.0			
2.0"	50.0	100.0			
1.5"	37.5	100.0			
1.0"	25.0	100.0	Coarse Gravel		0.0
0.75"	19.0	100.0			
0.50"	12.7	100.0			
0.375"	9.5	100.0	Fine Gravel		0.9
#4	4.8	99.1			
#10	2.00	99.0			
#20	0.85	98.7	Coarse Sand		0.1
#40	0.43	98.1	Medium Sand		0.9
#60	0.25	93.0			
#100	0.15	76.3			
#140	0.11	63.6	Fine Sand		45.5
#200	0.08	52.6			



ATTERBERG LIMITS
Method - B (Dry preparation)

M _c	LL	PL	PI	LI
29.2				

LL (oven-dried)
< 0.75 = ORGANIC (OL OH)

DESCRIPTION:
USCS:


TECH EK/JC
DATE 10/7/25
CHECK ☒
REVIEW ☒
APPROVE ☒

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: E-2, S-7
TYPE: Bag


Depth: 23.5-25.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)		% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0	Coarse Gravel	0.0
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	100.0		
#4	4.8	99.9	Fine Gravel	0.1
#10	2.00	99.9	Coarse Sand	0.0
#20	0.85	99.8	Medium Sand	0.2
#40	0.43	99.7		
#60	0.25	98.0		
#100	0.15	76.2	Fine Sand	52.3
#140	0.11	59.3		
#200	0.08	47.3		



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
17.7				

LL (oven-dried)
< 0.75 = ORGANIC (OL OH)

DESCRIPTION:
USCS:

TECH: EK/JC
DATE: 10/7/25
CHECK:
REVIEW:
APPROVE:

**AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA**

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classification	As-R'cvd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
E-4	S-3	6.0-7.5'	Bag	-	40.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-4	S-6	23.5-25.0'	Bag	-	18.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-5	S-1	0.0-1.5'	Bag	-	15.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-5	S-4	8.5-10.0'	Bag	-	41.9	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-5	S-6	18.5-20.0'	Bag	-	13.1	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-6	S-2	3.5-5.0'	Bag	-	33.6	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-6	S-5	13.5-15.0'	Bag	-	35.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-6	S-7	23.5-25.0'	Bag	-	8.9	-	-	-	-	97.7	22.6	-	-	-	-	-	-	-	-
E-7	S-1	0.0-1.5'	Bag	-	15.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-7	S-6	18.5-20.0'	Bag	-	13.1	-	-	-	-	100.0	41.4	-	-	-	-	-	-	-	-
E-8	S-3	6.0-7.5'	Bag	-	20.4	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-8	S-5	13.5-15.0'	Bag	-	40.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-8	S-7	23.5-25.0'	Bag	-	27.8	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-8	S-8	28.5-30.0'	Bag	-	37.5	NP	NP	NP	NP	-	-	-	-	-	-	-	-	-	-
E-8	S-9	33.5-35.0'	Bag	-	26.2	-	-	-	-	99.6	22.7	-	-	-	-	-	-	-	-

ABBREVIATIONS: LIQUID LIMIT (LL)
PLASTIC LIMIT (PL)
PLASTICITY INDEX (PI)
LIQUIDITY INDEX (LI)
SPECIFIC GRAVITY (Gs)

NOTES: T = TRIAXIAL TEST
U = UNCONFINED COMPRESSION TEST
C = CONSOLIDATION TEST
DS = DIRECT SHEAR TEST

WATER CONTENT DETERMINATION

ASTM D2216

PROJECT TITLE
PROJECT NUMBER
REMARKS

AEP/CABIN CREEK/GA

US-0041868.3924

Sample Type	Bag	Bag	Bag	Bag	Bag
Borehole Number	E-4	E-4	E-5	E-5	E-5
Sample Number	S-3	S-6	S-1	S-4	S-6
Depth of Sample (ft)	6.0-7.5'	13.5-15.0'	0.0-1.5'	8.5-10.0'	18.5-20.0'
Weight of Wet Soil + Tare (gm)	269.71	292.71	251.28	245.37	352.64
Weight of Dry Soil + Tare (gm)	207.04	253.72	225.17	188.03	317.69
Weight of Tare (gm)	52.03	42.82	51.67	51.34	51.40
Weight of Water (gm)	62.67	38.99	26.11	57.34	34.95
Weight of Dry Soil (gm)	155.01	210.90	173.50	136.69	266.29
Water Content (%)	40.4	18.5	15.0	41.9	13.1
Sample Type	Bag	Bag	Bag	Bag	Bag
Borehole Number	E-6	E-6	E-7	E-8	E-8
Sample Number	S-2	S-5	S-1	S-3	S-5
Depth of Sample (ft)	3.5-5.0'	13.5-15.0'	0.0-1.5'	6.0-7.5'	13.5-15.0'
Weight of Wet Soil + Tare (gm)	175.98	190.89	224.39	234.97	244.17
Weight of Dry Soil + Tare (gm)	144.73	154.54	201.43	203.91	186.00
Weight of Tare (gm)	51.80	51.80	52.08	51.92	42.47
Weight of Water (gm)	31.25	36.35	22.96	31.06	58.17
Weight of Dry Soil (gm)	92.93	102.74	149.35	151.99	143.53
Water Content (%)	33.6	35.4	15.4	20.4	40.5
Sample Type	Bag				
Borehole Number	E-8				
Sample Number	S-7				
Depth of Sample (ft)	23.5-25.0'				
Weight of Wet Soil + Tare (gm)	331.77				
Weight of Dry Soil + Tare (gm)	270.92				
Weight of Tare (gm)	51.81				
Weight of Water (gm)	60.85				
Weight of Dry Soil (gm)	219.11				
Water Content (%)	27.8				

TECH	JC
DATE	10/7/25
CHECK	
REVIEW	
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-6, S-7

TYPE: Bag


Depth: 23.5-25.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size			Particle Size	
	(mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0		
1.0"	25.0	100.0	Coarse Gravel	0.0
0.75"	19.0	100.0		
0.50"	12.7	98.3		
0.375"	9.5	98.3		
#4	4.8	97.7		
#10	2.00	97.1	Fine Gravel	2.3
#20	0.85	96.7	Coarse Sand	0.6
#40	0.43	94.8	Medium Sand	2.2
#60	0.25	81.9		
#100	0.15	46.5		
#140	0.11	31.2		
#200	0.08	22.6		
			Fine Sand	72.3
			Fines	22.6



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
8.9				

LL (oven-dried)

< 0.75 = ORGANIC (OL OH)

TECH EK/JC

DATE 10/7/25

CHECK

REVIEW

APPROVE

DESCRIPTION: -

USCS: -

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-7, S-6

TYPE: Bag


Depth: 18.5-20.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			% Passing	Particle Size Classification Percentage	
12.0"	304.8	100.0	Cobbles		0.0
3.0"	75.0	100.0			
2.5"	63.5	100.0			
2.0"	50.0	100.0			
1.5"	37.5	100.0			
1.0"	25.0	100.0	Coarse Gravel		0.0
0.75"	19.0	100.0			
0.50"	12.7	100.0			
0.375"	9.5	100.0	Fine Gravel		0.0
#4	4.8	100.0			
#10	2.00	99.9	Coarse Sand		0.1
#20	0.85	99.8	Medium Sand		0.5
#40	0.43	99.4			
#60	0.25	92.2			
#100	0.15	65.5	Fine Sand		58.0
#140	0.11	51.1			
#200	0.08	41.4			



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
13.1				

LL (oven-dried)

< 0.75 = ORGANIC (LO OH)

TECH EK/JC

DATE 10/7/25

CHECK REVIEW

APPROVE

DESCRIPTION: -

USCS: -

ATTERBERG LIMITS

ASTM D4318

PROJECT NAME: AEP/CABIN CREEK/GA

PROJECT NUMBER: US-0041868.3924

SAMPLE ID: E-8, S-8

SAMPLE TYPE: Bag

SAMPLE DEPTH: 28.5-30.0'

Sample Preparation:

Wet or Dry

Dry

Minus #40 Sieve

Yes

AS-RECEIVED
MOISTURE

	PLASTIC LIMIT	
Number of Blows		
Wt. of Wet Soil & Tare (g)	28.82	25.80
Wt. of Dry Soil & Tare (g)	24.67	22.36
Weight of Tare (g)	11.11	11.21
Weight of Water (g)	4.15	3.44
Weight of Dry Soil (g)	13.56	11.15
Water Content %	30.6	30.9

	LIQUID LIMIT	
	10	10
	16.04	17.34
	13.27	14.27
	4.26	4.23
	2.77	3.07
	9.01	10.04
	30.7	30.6

351.90
272.93
62.22
78.97
210.71
37.5

PLASTIC LIMIT (PL)

NP

LIQUID LIMIT (LL)

NP

PLASTICITY INDEX (PI)

NP


LIQUIDITY INDEX (LI)

NP

NOTE:

DESCRIPTION -

USCS -



TECH	TB
DATE	10/9/25
CHECK	<i>[Signature]</i>
REVIEW	<i>[Signature]</i>
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-8, S-9

Depth: 33.5-35.0'


TYPE: Bag



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)		% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0	Coarse Gravel	0.0
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	100.0		
#4	4.8	99.6	Fine Gravel	0.4
#10	2.00	98.9	Coarse Sand	0.7
#20	0.85	98.3	Medium Sand	1.6
#40	0.43	97.4		
#60	0.25	86.1		
#100	0.15	50.9	Fine Sand	74.7
#140	0.11	33.3		
#200	0.08	22.7		
Fines				



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
26.2				

LL (oven-dried)

< 0.75 - ORGANIC (LOOH)

TECH EK/JC

DATE 10/7/25

CHECK

REVIEW

APPROVE

DESCRIPTION: -

USCS: -

**AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA**

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classification	As-R'cvd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
E-9	S-1	0.0-1.5'	Bag	-	30.1	-	-	-	-	87.4	25.7	-	-	-	-	-	-	-	-
E-9	S-2	3.5-5.0'	Bag	-	6.7	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-9	S-4	8.5-10.0'	Bag	-	38.5	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-9	S-6	18.5-20.0'	Bag	-	20.0	-	-	-	-	-	-	-	-	-	-	-	-	-	-
E-9	S-8	28.5-30.0'	Bag	-	45.5	-	-	-	-	95.8	38.7	-	-	-	-	-	-	-	-

ABBREVIATIONS: LIQUID LIMIT (LL)
 PLASTIC LIMIT (PL)
 PLASTICITY INDEX (PI)
 LIQUIDITY INDEX (LI)
 SPECIFIC GRAVITY (Gs)

NOTES: T = TRIAXIAL TEST
 U = UNCONFINED COMPRESSION TEST
 C = CONSOLIDATION TEST
 DS = DIRECT SHEAR TEST

WATER CONTENT DETERMINATION

ASTM D2216

PROJECT TITLE
PROJECT NUMBER
REMARKS

AEP/CABIN CREEK/GA

US-0041868.3924

Sample Type	Bag	Bag	Bag		
Borehole Number	E-9	E-9	E-9		
Sample Number	S-2	S-4	S-6		
Depth of Sample (ft)	3.5-5.0'	8.5-10.0'	18.5-20.0'		
Weight of Wet Soil + Tare (gm)	316.37	227.97	338.85		
Weight of Dry Soil + Tare (gm)	299.74	178.99	292.86		
Weight of Tare (gm)	51.61	51.85	62.53		
Weight of Water (gm)	16.63	48.98	45.99		
Weight of Dry Soil (gm)	248.13	127.14	230.33		
Water Content (%)	6.7	38.5	20.0		


Sample Type					
Borehole Number					
Sample Number					
Depth of Sample (ft)					
Weight of Wet Soil + Tare (gm)					
Weight of Dry Soil + Tare (gm)					
Weight of Tare (gm)					
Weight of Water (gm)					
Weight of Dry Soil (gm)					
Water Content (%)					

Sample Type					
Borehole Number					
Sample Number					
Depth of Sample (ft)					
Weight of Wet Soil + Tare (gm)					
Weight of Dry Soil + Tare (gm)					
Weight of Tare (gm)					
Weight of Water (gm)					
Weight of Dry Soil (gm)					
Water Content (%)					

TECH	JC
DATE	10/7/25
CHECK	
REVIEW	
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS
ASTM D6913 & D4318


PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: E-9, S-1
TYPE: Bag
Depth: 0.0-1.5'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size			Particle Size	
	(mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0	Coarse Gravel	0.0
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	98.4	Fine Gravel	12.6
#4	4.8	87.4		
#10	2.00	68.9		
#20	0.85	57.0	Coarse Sand	18.5
#40	0.43	49.7	Medium Sand	19.2
#60	0.25	42.9		
#100	0.15	34.6		
#140	0.11	29.5	Fine Sand	24.0
#200	0.08	25.7		



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
30.2				

LL (oven-dried)
< 0.75 = ORGANIC (OL OH)

TECH EK/JC
DATE 10/7/25
CHECK
REVIEW
APPROVE

DESCRIPTION:
USCS:

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-9, S-8

TYPE: Bag


Depth: 28.5-30.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0	
3.0"	75.0	100.0			
2.5"	63.5	100.0			
2.0"	50.0	100.0			
1.5"	37.5	100.0			
1.0"	25.0	100.0	Coarse Gravel	0.0	
0.75"	19.0	100.0			
0.50"	12.7	100.0			
0.375"	9.5	99.1	Fine Gravel	4.2	
#4	4.8	95.8			
#10	2.00	91.3			
#20	0.85	85.8	Coarse Sand	4.5	
#40	0.43	80.2			
#60	0.25	71.0			
#100	0.15	56.2	Medium Sand	11.0	
#140	0.11	46.9			
#200	0.08	38.7			
			Fines	38.7	



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
45.5				

LL (oven-dried)

< 0.75 = ORGANIC (OL OH)

TECH EK/JC

DATE 10/7/25

CHECK

REVIEW

APPROVE

DESCRIPTION: -

USCS: -

AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classification	As-R'c'd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
A-2	TO-1	10.0-12.0'	UD	ML	80.3	NP	NP	NP	NP	100.0	69.6	-	-	-	2.12	36.9	80.3	-	T
A-3	TO-1	5.0-7.0'	UD	ML	51.8	NP	NP	NP	NP	99.9	57.5	-	-	-	-	46.4	51.8	-	-
A-4	TO-1	15.0-17.0'	UD	ML	52.1	NP	NP	NP	NP	92.9	64.0	-	-	-	2.14	56.4	52.1	-	T
B-3	TO-1	35.0-37.0'	UD	(SM)	48.0	-	-	-	-	98.1	37.6	-	-	-	-	65.8	48.0	-	-
E-1	TO-1	35.0-37.0'	UD										-	-				-	T
E-3	TO-1	5.0-7.0'	UD	ML	35.3	NP	NP	NP	NP	98.9	78.6	-	-	-	-	60.0	24.9	-	-
E-9	TO-1	15.0-17.0'	UD										-	-				-	T, DS

ABBREVIATIONS: LIQUID LIMIT (LL)
PLASTIC LIMIT (PL)
PLASTICITY INDEX (PI)
LIQUIDITY INDEX (LI)
SPECIFIC GRAVITY (Gs)


NOTES: T = TRIAXIAL TEST
U = UNCONFINED COMPRESSION TEST
C = CONSOLIDATION TEST
DS = DIRECT SHEAR TEST

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA
 SAMPLE ID: A-2 TO-1
 TYPE: UD


Depth: 10.0-12.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	
0.50"	12.7	100.0	
0.375"	9.5	100.0	
#4	4.8	100.0	
#10	2.00	99.9	
#20	0.85	99.8	
#40	0.43	99.1	
#60	0.25	96.8	
#100	0.15	89.0	
#140	0.11	79.3	
#200	0.08	69.6	
		Fines	69.6



ATTERBERG LIMITS
 Method - B (Dry preparation)

M _c	LL	PL	PI	LI
80.3	NP	NP	NP	NP

LL (oven-dried)
 < 0.75 = ORGANIC
 (LO/OH)

TECH CJ/TT
 DATE 10/22/25
 CHECK
 REVIEW
 APPROVE

DESCRIPTION: sandy SILT, fine to coarse; black.

USCS: ML

Boring or Test Pit: A-2
Sample: TO-1
Depth: 10.0-12.0 ft
Point No.: 1

Boring or Test Pit: A-2
Sample: TO-1
Depth: 10.0-12.0 ft
Point No.: 2

Boring or Test Pit: A-2
Sample: TO-1
Depth: 10.0-12.0 ft
Point No.: 3

Initial
Length = 6.011 in
Diameter = 2.856 in
Wet Mass = 1.332 lb
Area = 6.406 in²
Volume = 38.508 in³
Specific Gravity = 2.12 (ASTM D854)
Dry Mass of Solids = 0.818 lb
Moisture Content = 62.7%
Wet Unit Weight = 59.8 pcf
Dry Unit Weight = 36.7 pcf
Void Ratio = 2.59
Percent Saturation = 51%

Initial
Length = 5.989 in
Diameter = 2.833 in
Wet Mass = 1.589 lb
Area = 6.304 in²
Volume = 37.752 in³
Specific Gravity = 2.12 (ASTM D854)
Dry Mass of Solids = 0.831 lb
Moisture Content = 91.1%
Wet Unit Weight = 72.7 pcf
Dry Unit Weight = 38.1 pcf
Void Ratio = 2.47
Percent Saturation = 78%

Initial
Length = 6.323 in
Diameter = 2.764 in
Wet Mass = 1.476 lb
Area = 6.000 in²
Volume = 37.939 in³
Specific Gravity = 2.12 (ASTM D854)
Dry Mass of Solids = 0.789 lb
Moisture Content = 87.0%
Wet Unit Weight = 67.2 pcf
Dry Unit Weight = 36.0 pcf
Void Ratio = 2.67
Percent Saturation = 69%

After Consolidation
Length = 5.943 in
Diameter = 2.763 in
Area = 5.996 in² (Method B)
Volume = 35.636 in³
Moisture Content = 109.8%
Wet Unit Weight = 83.3 pcf
Dry Unit Weight = 39.7 pcf
Void Ratio = 2.32
Percent Saturation = 100%

After Consolidation
Length = 5.863 in
Diameter = 2.763 in
Area = 5.995 in² (Method B)
Volume = 35.148 in³
Moisture Content = 105.2%
Wet Unit Weight = 83.9 pcf
Dry Unit Weight = 40.9 pcf
Void Ratio = 2.23
Percent Saturation = 100%

After Consolidation
Length = 6.175 in
Diameter = 2.671 in
Area = 5.604 in² (Method B)
Volume = 34.606 in³
Moisture Content = 110.8%
Wet Unit Weight = 83.1 pcf
Dry Unit Weight = 39.4 pcf
Void Ratio = 2.35
Percent Saturation = 100%

B Parameter = 1.00
Shear Rate = 0.089% /min.
t₅₀ = 0.15 min.
Strain at Failure = 8.0%

B Parameter = 1.00
Shear Rate = 0.092% /min.
t₅₀ = 0.14 min.
Strain at Failure = 10.0%

B Parameter = 0.99
Shear Rate = 0.092% /min.
t₅₀ = 0.14 min.
Strain at Failure = 12.5%

Cell Pressure = 74.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 14.0 psi

Cell Pressure = 88.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 28.0 psi

Cell Pressure = 102.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 42.0 psi

Notes: Sample description: ML - sandy SILT, fine to coarse; black.
Atterberg limits: LL = NP PL = NP PI = NP (ASTM D4318)
Percent finer: 3/4 in. = 100% No. 4 = 100% No. 200 = 70% (ASTM D422, refer to separate report for gradation curve)
Specimen type: ☒ Intact ☐ Reconstituted
Moisture from: ☐ Cuttings ☒ Entire specimen
Saturation method: ☒ Wet ☐ Dry
Failure criterion: ☒ (σ₁/σ₃)_{max} ☐ (σ₁-σ₃)_{max} % strain
Membrane effect: ☒ Corrected ☐ Not Corrected

WSP USA
Norcross, Georgia

Title:
ASTM D4767
CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT
SAMPLE AND TEST DATA

Job Short Title:
AEP/CABIN CREEK/GA

Sample:
A-2, TO-1, 10.0-12.0'



Technician:
CJ/FT
Check: **DA**

Reviewed:
Approved:



Start Date:
10/21/2025

Job Number:
US-0041868.3924

Figure:
1




WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-2, TO-1, 10.0-12.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed: <i>A</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
					Figure: 2



WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT DEVIATOR STRESS AND PRINCIPAL STRESS RATIO PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-2, TO-1, 10.0-12.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed:  Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
				Figure: 3	

Stress Path (p'-q) Plot




Confining Pressure (psi)	p at failure (psi)	p' at failure (psi)	q at failure (psi)
14.0	23.2	17.9	9.2
28.0	41.0	21.0	13.0
42.0	57.7	28.6	15.7

Effective		
α'	29.3	degree
a'	0.0	psi
Total		
α	10.7	degree
a	5.0	psi

Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT STRESS PATH PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-2, TO-1, 10.0-12.0'		Technician: CJ/FT Check: <i>[Signature]</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
				Figure: 4	

Mohr's Circle Diagram



Confining Pressure (psi)	σ'_1 at failure (psi)	σ'_3 at failure (psi)	σ_1 at failure (psi)	σ_3 at failure (psi)
14.0	27.1	8.7	32.4	14.0
28.0	34.0	8.0	54.0	28.0
42.0	44.3	12.9	73.4	42.0

Effective

$\phi' = 34.2$ degree

$c' = 0.0$ psi

Total

$\phi = 10.9$ degree

$c = 5.1$ psi


Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT MOHR'S CIRCLE DIAGRAM			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-2, TO-1, 10.0-12.0'		Technician: CJ/FT Check: <i>[Signature]</i>		Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025
				Job Number: US-0041868.3924	Figure: 5

14.0 psi

28.0 psi

42.0 psi



WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT						
Job Short Title: AEP/CABIN CREEK/GA		SPECIMENS PHOTOGRAPH - <table border="1"><tr><td>14.0</td><td>28.0</td><td>42.0</td></tr></table> psi				14.0	28.0	42.0
14.0	28.0	42.0						
Sample: A-2, TO-1, 10.0-12.0'		Technician: CJ/FT Check: <i>JA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924			
					Figure: 6			

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: A-3 TO-1

Depth: 5.0-7.0'


TYPE: UD



COBBLES	Coarse GRAVEL	Fine GRAVEL	Coarse SAND	Medium SAND	Fine SAND	Silt or Clay FINES
---------	---------------	-------------	-------------	-------------	-----------	--------------------

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	
0.50"	12.7	100.0	
0.375"	9.5	100.0	
#4	4.8	99.9	
#10	2.00	99.7	
#20	0.85	99.6	
#40	0.43	98.2	
#60	0.25	91.1	
#100	0.15	76.1	
#140	0.11	65.4	
#200	0.08	57.5	
		Fines	57.5



ATTERBERG LIMITS

Method - B (Dry preparation)

M _c	LL	PL	PI	LI
51.8	NP	NP	NP	NP

LL (oven-dried)

< 0.75 = ORGANIC (OL OH)

TECH TB/CJ/JC

DATE 10/9/25

CHECK

REVIEW

APPROVE

DESCRIPTION: SILT and fine SAND; black.

USCS: ML

OCTOBER 2025

US-0041868.3924

UNIT WEIGHT DETERMINATION

ASTM D7263

PROJECT NAME: AEP/CABIN CREEK/GA**SAMPLE ID:** A-3**TO-1****DEPTH:** 5.0-7.0'**TYPE:** UD

WEIGHT OF SOIL (g)	662.08
LENGTH OF SAMPLE (in)	5.664
DIAMETER OF SAMPLE (in)	2.837
AREA OF SAMPLE (in ²)	6.32
VOLUME OF SAMPLE (in ³)	35.80
VOLUME OF SAMPLE (cm ³)	586.65

WET UNIT WEIGHT (pcf)	70.5
-----------------------	------

WEIGHT WET SOIL & TARE (g)	380.30
WEIGHT DRY SOIL & TARE (g)	295.62
WEIGHT OF TARE (g)	132.23
WEIGHT OF WATER (g)	84.68
WEIGHT OF DRY SOIL (g)	163.39
WATER CONTENT (%)	51.8

DRY UNIT WEIGHT (pcf)	46.4
-----------------------	------


DESCRIPTION SILT and fine SAND; black.

USCS ML

TECH	CJ
DATE	10/9/25
CHECK	DA
REVIEW	✓
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS
ASTM D6913 & D4318


PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: A-4 TO-1
TYPE: UD
Depth: 15.0-17.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			Particle Size	
		% Passing	Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0	Coarse Gravel	0.0
1.0"	25.0	100.0		
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	98.7	Fine Gravel	7.1
#4	4.8	92.9		
#10	2.00	86.2	Coarse Sand	6.7
#20	0.85	81.4	Medium Sand	7.6
#40	0.43	78.6		
#60	0.25	75.7		
#100	0.15	71.6	Fine Sand	14.6
#140	0.11	68.0		
#200	0.08	64.0		



DESCRIPTION: sandy SILT, fine to coarse, some fine gravel; black.
USCS: ML

ATTERBERG LIMITS Method - B (Dry preparation)				
M _L	LL	PL	PI	LI
52.1	NP	NP	NP	NP
LL (oven-dried)				
< 0.75 = ORGANIC (OL OH)				
TECH FT/JC				
DATE 10/13/25				
CHECK <i>DA</i>				
REVIEW <i>[Signature]</i>				
APPROVE				

Boring or Test Pit: A-4
Sample: TO-1
Depth: 15.0-17.0 ft
Point No.: 1

Boring or Test Pit: A-4
Sample: TO-1
Depth: 15.0-17.0 ft
Point No.: 2

Boring or Test Pit: A-4
Sample: TO-1
Depth: 15.0-17.0 ft
Point No.: 3

Initial
Length = 6.004 in
Diameter = 2.859 in
Wet Mass = 1.956 lb
Area = 6.420 in²
Volume = 38.544 in³
Specific Gravity = 2.14 (ASTM D854)
Dry Mass of Solids = 1.356 lb
Moisture Content = 44.3%
Wet Unit Weight = 87.7 pcf
Dry Unit Weight = 60.8 pcf
Void Ratio = 1.19
Percent Saturation = 79%

Initial
Length = 5.770 in
Diameter = 2.861 in
Wet Mass = 1.832 lb
Area = 6.429 in²
Volume = 37.094 in³
Specific Gravity = 2.14 (ASTM D854)
Dry Mass of Solids = 1.244 lb
Moisture Content = 47.3%
Wet Unit Weight = 85.3 pcf
Dry Unit Weight = 57.9 pcf
Void Ratio = 1.30
Percent Saturation = 78%

Initial
Length = 5.925 in
Diameter = 2.851 in
Wet Mass = 1.818 lb
Area = 6.384 in²
Volume = 37.824 in³
Specific Gravity = 2.14 (ASTM D854)
Dry Mass of Solids = 1.104 lb
Moisture Content = 64.6%
Wet Unit Weight = 83.0 pcf
Dry Unit Weight = 50.4 pcf
Void Ratio = 1.64
Percent Saturation = 84%

After Consolidation
Length = 5.864 in
Diameter = 2.828 in
Area = 6.280 in² (Method B)
Volume = 36.825 in³
Moisture Content = 51.2%
Wet Unit Weight = 96.2 pcf
Dry Unit Weight = 63.6 pcf
Void Ratio = 1.09
Percent Saturation = 100%

After Consolidation
Length = 5.669 in
Diameter = 2.735 in
Area = 5.876 in² (Method B)
Volume = 33.313 in³
Moisture Content = 49.8%
Wet Unit Weight = 96.7 pcf
Dry Unit Weight = 64.5 pcf
Void Ratio = 1.07
Percent Saturation = 100%

After Consolidation
Length = 5.788 in
Diameter = 2.791 in
Area = 6.118 in² (Method B)
Volume = 35.411 in³
Moisture Content = 68.9%
Wet Unit Weight = 91.0 pcf
Dry Unit Weight = 53.9 pcf
Void Ratio = 1.47
Percent Saturation = 100%

B Parameter = 0.98
Shear Rate = 0.090% /min.
t₅₀ = 0.23 min.
Strain at Failure = 11.2%

B Parameter = 1.00
Shear Rate = 0.091% /min.
t₅₀ = 0.15 min.
Strain at Failure = 7.9%

B Parameter = 0.98
Shear Rate = 0.090% /min.
t₅₀ = 0.13 min.
Strain at Failure = 7.1%

Cell Pressure = 74.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 14.0 psi

Cell Pressure = 88.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 28.0 psi

Cell Pressure = 102.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 42.0 psi

Notes: Sample description: ML - sandy SILT, fine to coarse, some fine gravel; black.
Atterberg limits: LL = NP PL = NP PI = NP (ASTM D4318)
Percent finer: 3/4 in. = 100% No. 4 = 93% No. 200 = 64% (ASTM D422, refer to separate report for gradation curve)
Specimen type: ☒ Intact ☐ Reconstituted
Moisture from: ☐ Cuttings ☒ Entire specimen
Saturation method: ☒ Wet ☐ Dry
Failure criterion: ☒ (σ₁/σ₃)_{max} ☐ (σ₁-σ₃)_{max} % strain
Membrane effect: ☒ Corrected ☐ Not Corrected


WSP USA
Norcross, Georgia

Title:
ASTM D4767
CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT
SAMPLE AND TEST DATA

Job Short Title:
AEP/CABIN CREEK/GA

Sample:
A-4, TO-1, 15.0-17.0'



Technician:
FT/CJ
Check: DA

Reviewed:

Approved:



Start Date:
10/13/2025

Job Number:
US-0041868.3924

Figure:
1




WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS				
Job Short Title: AEP/CABIN CREEK/GA						
Sample: A-4, TO-1, 15.0-17.0'	Technician: FT/CJ	Reviewed: 	Start Date:	Job Number:	Figure:	
	Check: DA	Approved:	10/13/2025	US-0041868.3924	2	



WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT DEVIATOR STRESS AND PRINCIPAL STRESS RATIO PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-4, TO-1, 15.0-17.0'	Technician: FT/CJ Check: <i>DS</i>		Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/13/2025	Job Number: US-0041868.3924
					Figure: 3

Stress Path (p'-q) Plot




Confining Pressure (psi)	p at failure (psi)	p' at failure (psi)	q at failure (psi)
14.0	24.0	18.6	10.0
28.0	53.8	44.0	25.8
42.0	73.6	55.4	31.6

Effective		
α'	29.8	degree
a'	0.0	psi
Total		
α	23.9	degree
a	0.1	psi

Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT STRESS PATH PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-4, TO-1, 15.0-17.0'		Technician: FT/CJ Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/13/2025	Job Number: US-0041868.3924
				Figure: 4	

Mohr's Circle Diagram



Confining Pressure (psi)	σ'_1 at failure (psi)	σ'_3 at failure (psi)	σ_1 at failure (psi)	σ_3 at failure (psi)
14.0	28.5	8.6	33.9	14.0
28.0	69.8	18.2	79.7	28.0
42.0	86.9	23.8	105.1	42.0

Effective

$\phi' = 35.0$ degree

$c' = 0.0$ psi

Total


$\phi = 26.3$ degree

$c = 0.1$ psi


Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT MOHR'S CIRCLE DIAGRAM			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: A-4, TO-1, 15.0-17.0'		Technician: FT/CJ Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/13/2025	Job Number: US-0041868.3924
				Figure: 5	


14.0 psi



28.0 psi



42.0 psi




WSP USA Norcross, Georgia		Title: ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT			
Job Short Title: AEP/CABIN CREEK/GA		SPECIMENS PHOTOGRAPH - 14.0 28.0 42.0 psi			
Sample: A-4, TO-1, 15.0-17.0'		Technician: FT/CJ Check: DA	Reviewed:  Approved:	Start Date: 10/13/2025	Job Number: US-0041868.3924
				Figure: 6	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS

ASTM D6913 & D4318

PROJECT NAME: **AEP/CABIN CREEK/GA**
 SAMPLE ID: **B-3 TO-1**
 TYPE: **UD**


Depth: **35.0-37.0'**



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	Cobbles
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	Coarse Gravel
0.50"	12.7	100.0	
0.375"	9.5	100.0	
#4	4.8	98.1	Fine Gravel
#10	2.00	95.7	Coarse Sand
#20	0.85	91.9	
#40	0.43	88.1	Medium Sand
#60	0.25	85.0	
#100	0.15	73.1	
#140	0.11	53.1	
#200	0.08	37.6	Fine Sand
			Fines
			37.6



ATTERBERG LIMITS
 Method - B (Dry preparation)

M_c	LL	PL	PI	LI
48.0				

LL (oven-dried)
 < 0.75 = ORGANIC
 (OL OH)

DESCRIPTION: SAND and SILT, fine to coarse, trace fine gravel; very dark grayish brown.

USCS: (SM)

TECH CJ/TT
 DATE 10/23/25
 CHECK REVIEW
 APPROVE

UNIT WEIGHT DETERMINATION

ASTM D7263

PROJECT NAME: AEP/CABIN CREEK/GA**SAMPLE ID:** B-3**TO-1****DEPTH:** 35.0-37.0'**TYPE:** UD

WEIGHT OF SOIL (g)	291.28
LENGTH OF SAMPLE (in)	4.156
DIAMETER OF SAMPLE (in)	1.869
AREA OF SAMPLE (in ²)	2.74
VOLUME OF SAMPLE (in ³)	11.40
VOLUME OF SAMPLE (cm ³)	186.81

WET UNIT WEIGHT (pcf)	97.4
-----------------------	------

WEIGHT WET SOIL & TARE (g)	393.63
WEIGHT DRY SOIL & TARE (g)	310.70
WEIGHT OF TARE (g)	137.85
WEIGHT OF WATER (g)	82.93
WEIGHT OF DRY SOIL (g)	172.85
WATER CONTENT (%)	48.0

DRY UNIT WEIGHT (pcf)	65.8
-----------------------	------


DESCRIPTION SAND and SILT, fine to coarse, trace fine gravel; very dark grayish brown.

USCS (SM)

TECH	CJ
DATE	10/23/25
CHECK	DA
REVIEW	W
APPROVE	

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS
ASTM D6913 & D4318


PROJECT NAME: AEP/CABIN CREEK/GA
SAMPLE ID: E-3 TO-1
TYPE: UD
Depth: 5.0-7.0'



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)	% Passing	Classification	Percentage
12.0"	304.8	100.0	
3.0"	75.0	100.0	
2.5"	63.5	100.0	
2.0"	50.0	100.0	
1.5"	37.5	100.0	
1.0"	25.0	100.0	
0.75"	19.0	100.0	
0.50"	12.7	100.0	
0.375"	9.5	100.0	
#4	4.8	98.9	
#10	2.00	98.3	
#20	0.85	97.6	
#40	0.43	96.9	
#60	0.25	94.9	
#100	0.15	89.3	
#140	0.11	83.6	
#200	0.08	78.6	



ATTERBERG LIMITS
Method - B (Dry preparation)

M _c	LL	PL	PI	LI
35.3	NP	NP	NP	NP

DESCRIPTION: sandy SILT, fine to coarse, trace fine gravel; black, organics.

USCS: ML

LL (oven-dried)
 < 0.75 = ORGANIC (OL OH)

TECH CJ/TT
DATE 10/22/25
CHECK REVIEW
APPROVE

OCTOBER 2025

US-0041868.3924

UNIT WEIGHT DETERMINATION

ASTM D7263

PROJECT NAME: AEP/CABIN CREEK/GA**SAMPLE ID:** E-3**TO-1****DEPTH:** 5.0-7.0'**TYPE:** UD

WEIGHT OF SOIL (g)	256.14
LENGTH OF SAMPLE (in)	2.012
DIAMETER OF SAMPLE (in)	2.872
AREA OF SAMPLE (in ²)	6.48
VOLUME OF SAMPLE (in ³)	13.03
VOLUME OF SAMPLE (cm ³)	213.52

WET UNIT WEIGHT (pcf)	74.9
-----------------------	------

WEIGHT WET SOIL & TARE (g)	306.82
WEIGHT DRY SOIL & TARE (g)	255.97
WEIGHT OF TARE (g)	51.49
WEIGHT OF WATER (g)	50.85
WEIGHT OF DRY SOIL (g)	204.48
WATER CONTENT (%)	24.9

DRY UNIT WEIGHT (pcf)	60.0
-----------------------	------

DESCRIPTION sandy SILT, fine to coarse, trace fine gravel; black, organics.

USCS ML

TECH	CJ
DATE	10/22/25
CHECK	PA
REVIEW	L
APPROVE	

AEP/CABIN CREEK/GA
SUMMARY OF SOIL DATA

Borehole I.D.	Sample I.D.	Sample Depth	Sample Type	Soil Classi- fication	As-R'cvd Moisture Content %	Atterberg Limits				Grain Size Distribution			Compaction		Gs	Unit Weight		Permeability (cm/sec)	Additional Tests Conducted (See Notes)
										% Finer No. 4 Sieve	% Finer No. 200 Sieve	% Finer 0.002 mm	Max. Dry Density (pcf)	Optimum Moisture %		Dry Density (pcf)	Moisture Content %		
						LL	PL	PI	LI										
A-2	TO-1	10.0-12.0'	UD	ML	80.3	NP	NP	NP	NP	100.0	69.6	-	-	-	2.12	36.9	80.3	-	T
A-3	TO-1	5.0-7.0'	UD	ML	51.8	NP	NP	NP	NP	99.9	57.5	-	-	-	-	46.4	51.8	-	-
A-4	TO-1	15.0-17.0'	UD	ML	52.1	NP	NP	NP	NP	92.9	64.0	-	-	-	2.14	56.4	52.1	-	T
B-3	TO-1	35.0-37.0'	UD	(SM)	48.0	-	-	-	-	98.1	37.6	-	-	-	-	65.8	48.0	-	-
E-1	TO-1	35.0-37.0'	UD	CL-ML	22.6	23	18	5	0.91	99.9	56.6	-	-	-	2.72	104.1	22.6	-	T
E-3	TO-1	5.0-7.0'	UD	ML	35.3	NP	NP	NP	NP	98.9	78.6	-	-	-	-	60.0	24.9	-	-
E-9	TO-1	15.0-17.0'	UD	SM	28.0	NP	NP	NP	NP	98.6	39.9	-	-	-	-	72.6	27.0	-	T
E-9	TO-1	15.0-17.0'	UD	-	-	-	-	-	-	-	-	-	-	-	2.33	40.6	28.0	-	DS

ABBREVIATIONS: LIQUID LIMIT (LL)
PLASTIC LIMIT (PL)
PLASTICITY INDEX (PI)
LIQUIDITY INDEX (LI)
SPECIFIC GRAVITY (Gs)

NOTES: T = TRIAXIAL TEST
U = UNCONFINED COMPRESSION TEST
C = CONSOLIDATION TEST
DS = DIRECT SHEAR TEST

PARTICLE SIZE DISTRIBUTION & ATTERBERG LIMITS


ASTM D6913 & D4318

PROJECT NAME: AEP/CABIN CREEK/GA

SAMPLE ID: E-1 TO-1

Depth: 35.0-37.0'


TYPE: UD



COBBLES	Coarse	Fine	Coarse	Medium	Fine	Silt or Clay
	GRAVEL		SAND			FINES

U.S. Standard Sieves Sizes and Numbers

Particle Size (mm)			Particle Size	
	% Passing		Classification	Percentage
12.0"	304.8	100.0	Cobbles	0.0
3.0"	75.0	100.0		
2.5"	63.5	100.0		
2.0"	50.0	100.0		
1.5"	37.5	100.0		
1.0"	25.0	100.0	Coarse Gravel	0.0
0.75"	19.0	100.0		
0.50"	12.7	100.0		
0.375"	9.5	100.0	Fine Gravel	0.1
#4	4.8	99.9		
#10	2.00	99.6		
#20	0.85	99.3	Coarse Sand	0.2
#40	0.43	98.8	Medium Sand	0.8
#60	0.25	94.4		
#100	0.15	80.5	Fine Sand	42.2
#140	0.11	65.4		
#200	0.08	56.6		



ATTERBERG LIMITS

Method - B (Dry preparation)

M _L	LL	PL	PI	LI
22.6	23	18	5	0.91

 LL (oven-dried)
 < 0.75 = ORGANIC
 (OL/OH)

DESCRIPTION: SILTY CLAY and fine SAND; olive brown.

USCS: CL-ML

 TECH CJ/JC
 DATE 10/21/25
 CHECK [Signature]
 REVIEW [Signature]
 APPROVE [Signature]

Boring or Test Pit: E-1
Sample: TO-1
Depth: 15.0-17.0 ft
Point No.: 1

Boring or Test Pit: E-1
Sample: TO-1
Depth: 15.0-17.0
Point No.: 2

Boring or Test Pit: E-1
Sample: TO-1
Depth: 15.0-17.0
Point No.: 1

Initial

Length = 6.094 in
Diameter = 2.853 in
Wet Mass = 2.834 lb
Area = 6.393 in²
Volume = 38.958 in³
Specific Gravity = 2.72 (ASTM D854)
Dry Mass of Solids = 2.310 lb
Moisture Content = 22.7%
Wet Unit Weight = 125.7 pcf
Dry Unit Weight = 102.5 pcf
Void Ratio = 0.65
Percent Saturation = 94%

Length = 5.993 in
Diameter = 2.829 in
Wet Mass = 2.823 lb
Area = 6.286 in²
Volume = 37.670 in³
Specific Gravity = 2.72 (ASTM D854)
Dry Mass of Solids = 2.305 lb
Moisture Content = 22.5%
Wet Unit Weight = 129.5 pcf
Dry Unit Weight = 105.7 pcf
Void Ratio = 0.60
Percent Saturation = 102%

Length = 6.085 in
Diameter = 2.732 in
Wet Mass = lb
Area = in²
Volume = in³
Specific Gravity = (ASTM D854)
Dry Mass of Solids = lb
Moisture Content =
Wet Unit Weight = pcf
Dry Unit Weight = pcf
Void Ratio =
Percent Saturation =

After Consolidation

Length = 6.085 in
Diameter = 2.732 in
Area =
Volume =
Moisture Content =
Wet Unit Weight =
Dry Unit Weight =
Void Ratio =
Percent Saturation =

After Consolidation

Length = 5.847 in
Diameter = 2.766 in
Area = 6.011
Volume = 35.144
Moisture Content = 18.2%
Wet Unit Weight = 133.9
Dry Unit Weight = 113.3
Void Ratio = 0.49
Percent Saturation = 100%

After Consolidation

Length = 5.936 in
Diameter = 2.766 in
Area = 6.010 in² (Method B)
Volume = 35.681 in³
Moisture Content = 18.9%
Wet Unit Weight = 133.0 pcf
Dry Unit Weight = 111.9 pcf
Void Ratio = 0.51
Percent Saturation = 100%

B Parameter = 1.00
Shear Rate = 0.054% /min.
t₅₀ = 6.62 min.
Strain at Failure = 2.4%

B Parameter = 0.99
Shear Rate = 0.017% /min.
t₅₀ = 19.13 min.
Strain at Failure = 11.0%

B Parameter = 1.00
Shear Rate = 0.056% /min.
t₅₀ = 9.88 min.
Strain at Failure = 9.0%

Cell Pressure = 74.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 14.0 psi

Cell Pressure = 88.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 28.0 psi

Cell Pressure = 102.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 42.0 psi

Notes: Sample description: CL-ML - SILTY CLAY and fine SAND; olive brown.
Atterberg limits: LL = 23 PL = 18 PI = 5 (ASTM D4318)
Percent finer: 3/4 in. = 100.0% No. 4 = 99.9% No. 200 = 56.6% (ASTM D422, refer to separate report for gradation curve)
Specimen type: ☒ Intact ☐ Reconstituted
Moisture from: ☐ Cuttings ☒ Entire specimen
Saturation method: ☒ Wet ☐ Dry
Failure criterion: ☒ (σ₁/σ₃)_{max} ☐ (σ₁-σ₃)_{max} % strain
Membrane effect: ☒ Corrected ☐ Not Corrected

WSP USA
Norcross, Georgia

Title:
MODIFIED (Multi-Stage) - ASTM D4767
CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT
SAMPLE AND TEST DATA

Job Short Title:
AEP/CABIN CREEK/GA

Sample:
E-1, TO-1, 35.0-37.0'

Technician:
FT/CJ
Check: 



Reviewed:

Approved:



Start Date:
10/21/2025

Job Number:
US-0041868.3924

Figure:
1




WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-1, TO-1, 35.0-37.0'		Technician: FT/CJ Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
					Figure: 2



WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-1, TO-1, 35.0-37.0'		Technician: FT/CJ Check: DA	Reviewed: Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
				Figure: 3	

Stress Path (p'-q) Plot




Confining Pressure (psi)	p at failure (psi)	p' at failure (psi)	q at failure (psi)
14.0	19.1	11.0	5.1
28.0	42.4	23.9	14.4
42.0	67.9	41.6	25.9

Effective		
α'	31.3	degree
a'	0.0	psi
Total		
α	20.0	degree
a	0.0	psi

Note: The laboratory testing relates only to the sample tested. WSP neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT STRESS PATH PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-1, TO-1, 35.0-37.0'		Technician: FT/CJ Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
				Figure: 4	

Mohr's Circle Diagram



Confining Pressure (psi)	σ'_1 at failure (psi)	σ'_3 at failure (psi)	σ_1 at failure (psi)	σ_3 at failure (psi)
14.0	16.1	5.9	24.2	14.0
28.0	38.3	9.5	56.7	28.0
42.0	67.6	15.7	93.8	42.0

Effective

$\phi' = 37.5$ degree

$c' = 0.0$ psi

Total

$\phi = 21.4$ degree

$c = 0.0$ psi

Note: The laboratory testing relates only to the sample tested. WSP neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT MOHR'S CIRCLE DIAGRAM			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-1, TO-1, 35.0-37.0'		Technician: FT/CJ Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/21/2025	Job Number: US-0041868.3924
				Figure: 5	

28 psi



14 & 42 psi



WSP USA
Norcross, Georgia

Job Short Title:

AEP/CABIN CREEK/GA

Sample:

E-1, TO-1, 35.0-37.0'

Title:

MODIFIED (Multi-Stage) - ASTM D4767
CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT
SPECIMEN PHOTOGRAPHS - 2 Specimens

Technician:

FT/CJ

Check:

DA

Reviewed:

Approved:

Start Date:

10/21/2025

Job Number:

US-0041868.3924


Figure:

6

ASTM D6913 & D4318

Depth: 15.0-17.0'

TYPE: UD



The Plasticity Chart is a graph with Plasticity Index (PI) on the vertical axis (0 to 60) and Liquid Limit (LL) on the horizontal axis (0 to 110). It features three main boundary lines: a dashed U-line, a solid A-line, and a solid CL-line. The chart is divided into regions labeled with soil types: CH or OH (above U-line), MH or OH (between U and A lines), CL or OL (between A and CL lines), and ML or OL (below CL-line and to the right of the LL=25 vertical line). A vertical line is drawn at LL=50, and a horizontal line is drawn at PI=7. A shaded region is bounded by LL=10, LL=25, PI=4, and PI=7.

Method - B (Dry preparation)

LL (oven-dried)	
< 0.75 = ORGANIC (OL OH)	

WSP USA

Boring or Test Pit: E-9
Sample: TO-1
Depth: 15.0-17.0 ft
Point No.: 1

Boring or Test Pit:
Sample:
Depth:
Point No.:

Boring or Test Pit:
Sample:
Depth:
Point No.:

Initial

Length = 6.010 in
Diameter = 2.859 in
Wet Mass = 2.058 lb
Area = 6.420 in²
Volume = 38.583 in³
Specific Gravity = 2.33 (ASTM D854)
Dry Mass of Solids = 1.621 lb
Moisture Content = 27.0%
Wet Unit Weight = 92.2 pcf
Dry Unit Weight = 72.6 pcf
Void Ratio = 1.00
Percent Saturation = 63%

Length = 5.864
Diameter = 2.750
Wet Mass =
Area =
Volume =
Specific Gravity =
Dry Mass of Solids =
Moisture Content =
Wet Unit Weight =
Dry Unit Weight =
Void Ratio =
Percent Saturation =

Length = 5.676
Diameter = 2.795
Wet Mass =
Area =
Volume =
Specific Gravity =
Dry Mass of Solids =
Moisture Content =
Wet Unit Weight =
Dry Unit Weight =
Void Ratio =
Percent Saturation =

After Consolidation

Length = 5.864 in
Diameter = 2.750 in
Area = 5.941
Volume = 34.837
Moisture Content =
Wet Unit Weight =
Dry Unit Weight =
Void Ratio =
Percent Saturation =

After Consolidation

Length = 5.676 in
Diameter = 2.795 in
Area = 6.138
Volume = 34.837
Moisture Content =
Wet Unit Weight =
Dry Unit Weight =
Void Ratio =
Percent Saturation =

After Consolidation

Length = 5.484 in
Diameter = 2.844 in
Area = 6.352 in² (Method B)
Volume = 34.837 in³
Moisture Content = 34.6%
Wet Unit Weight = 108.3 pcf
Dry Unit Weight = 80.4 pcf
Void Ratio = 0.81
Percent Saturation = 100%

B Parameter = 1.00
Shear Rate = 0.091% /min.
t₅₀ = 0.59 min.
Strain at Failure = 3.2%

B Parameter = --
Shear Rate = 0.098% /min.
t₅₀ = 1.13 min.
Strain at Failure = 6.6%

B Parameter = --
Shear Rate = 0.101% /min.
t₅₀ = 2.80 min.
Strain at Failure = 9.9%

Cell Pressure = 74.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 14.0 psi

Cell Pressure = 88.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 28.0 psi

Cell Pressure = 102.0 psi
Back Pressure = 60.0 psi
Confining Pressure = 42.0 psi

Notes: Sample description: SM - SAND and SILT, fine to coarse, trace fine gravel; yellowish brown and black.

Atterberg limits:	LL = NP	PL = NP	PI = NP	(ASTM D4318)
Percent finer:	3/4 in. = 100%	No. 4 = 99%	No. 200 = 40%	(ASTM D422, refer to separate report for gradation curve)
Specimen type:	☒ Intact	☐ Reconstituted		
Moisture from:	☐ Cuttings	☒ Entire specimen		
Saturation method:	☒ Wet	☐ Dry		
Failure criterion:	☒ (σ ₁ /σ ₃) _{max}	☐ (σ ₁ -σ ₃) _{max}		% strain
Membrane effect:	☒ Corrected	☐ Not Corrected		

WSP USA
Norcross, Georgia

Title:

MODIFIED (Multi-Stage) - ASTM D4767
CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT
SAMPLE AND TEST DATA

Job Short Title:

AEP/CABIN CREEK/GA

Sample:

E-9, TO-1, 15.0-17.0'

Technician:

CJ/FT

Check:

DA

Reviewed:

Approved:

Start Date:



10/22/2025

Job Number:



US-0041868.3924

Figure:

1




WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-9, TO-1, 15.0-17.0'		Technician: CJ/FT Check: <i>JA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/22/2025	Job Number: US-0041868.3924
					Figure: 2



WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT q AND EXCESS PORE PRESSURE PLOTS				
Job Short Title: AEP/CABIN CREEK/GA						
Sample: E-9, TO-1, 15.0-17.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/22/2025	Job Number: US-0041868.3924	Figure: 3

Stress Path (p'-q) Plot




Confining Pressure (psi)	p at failure (psi)	p' at failure (psi)	q at failure (psi)
14.0	16.6	9.2	2.6
28.0	40.5	25.0	12.5
42.0	58.9	41.1	16.9

Effective	
α'	23.4 degree
a'	0.0 psi
Total	
α	16.1 degree
a	0.0 psi

Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT STRESS PATH PLOT			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-9, TO-1, 15.0-17.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/22/2025	Job Number: US-0041868.3924
				Figure: 4	

Mohr's Circle Diagram



Confining Pressure (psi)	σ'_1 at failure (psi)	σ'_3 at failure (psi)	σ_1 at failure (psi)	σ_3 at failure (psi)
14.0	11.8	6.7	19.1	14.0
28.0	37.5	12.5	53.0	28.0
42.0	58.0	24.2	75.8	42.0

Effective
 $\phi' = 25.6$ degree
 $c' = 0.0$ psi

Total
 $\phi = 16.8$ degree
 $c = 0.0$ psi

Note: The laboratory testing relates only to the sample tested. WSP USA neither accepts responsibility for nor makes claims to the final use and purpose of the material.

WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT MOHR'S CIRCLE DIAGRAM			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-9, TO-1, 15.0-17.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/22/2025	Job Number: US-0041868.3924
				Figure: 5	





WSP USA Norcross, Georgia		Title: MODIFIED (Multi-Stage) - ASTM D4767 CONSOLIDATED UNDRAINED TRIAXIAL COMPRESSION TEST REPORT SPECIMEN PHOTOGRAPH - Single Specimen			
Job Short Title: AEP/CABIN CREEK/GA					
Sample: E-9, TO-1, 15.0-17.0'		Technician: CJ/FT Check: <i>DA</i>	Reviewed: <i>[Signature]</i> Approved:	Start Date: 10/22/2025	Job Number: US-0041868.3924
					Figure: 6

DIRECT SHEAR

ASTM D3080

PROJECT NAME: AEP/CABIN CREEK/GA
 PROJECT NUMBER: US-0041868.3924
 SAMPLE ID: E-9 TO-1

DEPTH: 15.0-17.0'



Peak
 $f = 25.9$ ⁰
 $C = 0$ psf

Post Peak
 $f = 23.0$ ⁰
 $C = 0$ psf

SPECIMEN 1	
Normal Stress (psf)	2000
t_{50} (min)	1.17
Speed (in/min)	0.003
Sample Diameter (in)	2.50
Moisture Content (%)	28.0
Wet Density (pcf)	55.6
Dry Density (pcf)	43.4
Void Ratio	2.35
Saturation (%)	27.8
Horizontal Displacement (in)	Shear Stress (psf)
0.000	0
0.002	103
0.004	106
0.006	106
0.008	106
0.010	123
0.015	214
0.020	287
0.030	329
0.050	405
0.075	461
0.100	508
0.125	554
0.150	587
0.175	707
0.200	716
0.225	695
0.250	660
0.300	596

716
Max Shear Stress

SPECIMEN 2	
Normal Stress (psf)	4000
t_{50} (min)	0.69
Speed (in/min)	0.005
Sample Diameter (in)	2.50
Moisture Content (%)	28.0
Wet Density (pcf)	49.5
Dry Density (pcf)	38.6
Void Ratio	2.76
Saturation (%)	23.6
Horizontal Displacement (in)	Shear Stress (psf)
0.000	0
0.002	326
0.004	428
0.006	499
0.008	554
0.010	590
0.015	669
0.020	719
0.030	792
0.050	901
0.075	986
0.100	1059
0.125	1124
0.150	1170
0.175	1173
0.200	1173
0.225	1165
0.250	1153
0.300	1124

1173
Max Shear Stress

SPECIMEN 3	
Normal Stress (psf)	6000
t_{50} (min)	0.62
Speed (in/min)	0.005
Sample Diameter (in)	2.50
Moisture Content (%)	28.0
Wet Density (pcf)	50.8
Dry Density (pcf)	39.7
Void Ratio	2.67
Saturation (%)	24.5
Horizontal Displacement (in)	Shear Stress (psf)
0.000	0
0.002	552
0.004	777
0.006	1062
0.008	1253
0.010	1452
0.015	1781
0.020	2056
0.030	2423
0.050	2966
0.075	3209
0.100	3333
0.125	3500
0.150	3503
0.175	3488
0.200	3470
0.225	3253
0.250	3206
0.300	3013

3503
Max Shear Stress

REMARKS

DESCRIPTION SAND and SILT, fine to coarse, trace fine gravel; yellowish brown and black.

USCS SM

TECH FT

DATE 10/30/25

CHECK DA

REVIEW L

APROVE



wsp.com


ATTACHMENT C

DESIGN DRAWINGS



Top to cut 1:2 slope down to
El. 575' then level to
northerly edge of cut.

Normal Pool El. 590'




Soundings within dredged
area obtained by Field Survey

PLAN

0 100 200 300

Scale



SECTION A-A

0 25 50 75 100 ft

Scale

NOTES

Ref: U.S. Engineers Survey Sheet 15,
Cabin Creek is located 74.3 miles above the mouth
of the Kanawha River.
Elevations are referred to M.S.L. Sandy Hook
Datum.

Normal Pool of the Kanawha River is 590'.
High Water of the Kanawha River is 617.6'.
Dredged material, where suitable, to be used for
construction of dike. Remainder to be deposited
on island or in Back Channel within proposed
dike.

PROPOSED FLY ASH STORAGE
AT CABIN CREEK ISLAND

CABIN CREEK POWER PLANT

Application By:

Appalachian Electric Power Company.

Cabin Creek, West Virginia.

October 21, 1954


Revised 2-13-56

J. G. F.


Application By:
 Appalachian Electric Power Company
 Cabin Creek, West Virginia
 October 24, 1958

Revised 1-6-58


DETAIL OF OVERFLOW OUTLET
 IN FLY ASH STORAGE AREA
 AT CABIN CREEK ISLAND
 CABIN CREEK POWER PLANT
 D-1 NA 5-1-1153



PLAN




DETAIL OF CONCRETE PLANK




SECTION C-C


Planks installed
 as required




SECTION D-D



SECTION A-A (ENLARGED)
Typical For Stations 0+00-6+50



SECTION B-B
Typical For Stations 6+50-13+00





Application By:
 Appalachian Electric Power Company
 Cabin Creek, West Virginia
 January 6, 1956

PROPOSED FLY ASH STORAGE
 AT CABIN CREEK ISLAND
 CABIN CREEK POWER PLANT
 JAN 13 1956

SCHEDULE OF RIVER OUTFALLS

OUTFALL NO.	SERVICE	SIZE	CONSTRUCTION	INVERT ELEVATION AT DISCHARGE	LOCATION	REMARKS
1	FLY ASH STORAGE AREA OVERFLOW	24"	CONCRETE PIPE	590.0'	SEE THIS DWG. H/3	INTERMITTENT FLOW NEAR SKIMMER FOR SOLIDS RETENTION AT OVERFLOW
2	STORM DRAIN & SANITARY DRAIN	30"	TILE PIPE	ABOVE 590.0'	SEE THIS DWG. D/3	UNCONTAMINATED STORM WATER & TREATED SANITARY WASTES
3 & 3A	STORM DRAINS	8"	TILE PIPE	ABOVE 590.0'	SEE THIS DWG. D/3	UNCONTAMINATED STORM WATER (2 PIPES)
4	STORM DRAIN	20"	TILE PIPE	ABOVE 590.0'	SEE THIS DWG. D/3	UNCONTAMINATED STORM WATER
5	STORM DRAIN & SANITARY DRAIN	24"	TILE PIPE	ABOVE 590.0'	SEE THIS DWG. D/8	UNCONTAMINATED STORM WATER & TREATED SANITARY WASTES
6	STORM DRAIN, FILTER BACKWASH DRAIN & BAKER ROOM DRAIN	20"	TILE PIPE	591.16'	SEE THIS DWG. D/7	UNCONTAMINATED STORM WATER & INTERMITTENT DISCHARGE OF PROCESS WASTES FROM FILTERS
7	BOTTOM ASH PIT OVERFLOW	30"	TILE PIPE	595.0'	SEE THIS DWG. D/4	NEAR SKIMMER FOR SOLIDS RETENTION AT OVERFLOW
8	STORM DRAIN, SANITARY DRAIN, BAKER BUILDING DISCHARGE	24"	TILE PIPE	598.0'	SEE THIS DWG. F/5	UNCONTAMINATED STORM WATER, TREATED SANITARY WASTES, UNTREATED PROCESS WASTES
9A, 9B, 9C, 9D, 9E	STORM DRAINS	4"	IRON PIPE	ABOVE 590.0'	SEE THIS DWG. G/4, H/4	UNCONTAMINATED STORM WATER (5 PIPES)
10	ALTERNATE EMERGENCY DRAIN FROM EVAPORATOR	6"	STEEL PIPE	590.0'	SEE THIS DWG. G/5 300' WEST M.P. 74.5	EMERGENCY PROCESS DRAIN UNTREATED PROCESS WASTES
11	CIRCULATING WATER DISCHARGE	54"	IRON PIPE	576.92'	SEE THIS DWG. G/5 330' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #9
11A	CIRCULATING WATER DISCHARGE	54"	IRON PIPE	576.92'	SEE THIS DWG. G/5 300' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #5
12	EMERGENCY SUMP DRAIN	14"	STEEL PIPE	596.0'	SEE THIS DWG. G/5 290' WEST M.P. 74.5	UNCONTAMINATED TURBINE ROOM FLOOR DRAINS
13	CIRCULATING WATER DISCHARGE	54"	IRON PIPE	576.92'	SEE THIS DWG. G/5 280' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #8
13A	CIRCULATING WATER DISCHARGE	54"	IRON PIPE	576.92'	SEE THIS DWG. G/5 250' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #8
14	TURBINE ROOM SUMP PUMP DISCHARGE	8"	STEEL PIPE	587.67'	SEE THIS DWG. G/5 270' WEST M.P. 74.5	INTERMITTENT DISCHARGE UNTREATED PROCESS WASTES
14A	TURBINE ROOM SUMP PUMP DISCHARGE	8"	STEEL PIPE	580.0'	SEE THIS DWG. H/5 100' WEST M.P. 74.5	INTERMITTENT DISCHARGE UNTREATED PROCESS WASTES
15	CIRCULATING WATER DISCHARGE	48"	IRON PIPE	566.67'	SEE THIS DWG. H/5 190' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #6 INACTIVE - COLD RESERVE
16	CIRCULATING WATER DISCHARGE	36"	IRON PIPE	566.67'	SEE THIS DWG. H/5 175' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #5 INACTIVE - COLD RESERVE
17	TURBINE ROOM SUMP DISCHARGE	10"	STEEL PIPE	600.0'	SEE THIS DWG. H/5 150' WEST M.P. 74.5	INACTIVE - NO FLOW #3.5.4 TURBINE DEACTIVATED
18	CIRCULATING WATER DISCHARGE	42"	STEEL PIPE	574.92'	SEE THIS DWG. H/5 145' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #4 INACTIVE - COLD RESERVE
19	CIRCULATING WATER DISCHARGE	42"	STEEL PIPE	574.92'	SEE THIS DWG. H/5 140' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER CONDENSER #3 INACTIVE - COLD RESERVE
20	CIRCULATING WATER INTAKE SCREEN WASH WATER TROUGH	20"	STEEL TROUGH	ABOVE 590.0'	SEE THIS DWG. H/5 100' WEST M.P. 74.5	THE RETURN TO THE RIVER OF RIVER TRASH WASHED OFF THE INTAKE SCREENS
21	CIRCULATING WATER DISCHARGE	6"	STEEL PIPE	592.0'	SEE THIS DWG. J/6 30' WEST M.P. 74.5	UNCONTAMINATED COOLING WATER FROM TRANSFORMERS
22	STORM DRAIN	18"	TILE PIPE	ABOVE 590.0'	SEE THIS DWG. M/7 500' EAST M.P. 74.5	UNCONTAMINATED STORM WATER
23	STORM DRAIN & SANITARY DRAIN	10"	TILE PIPE	ABOVE 590.0'	775' EAST M.P. 74.5	UNCONTAMINATED STORM WATER & TREATED SANITARY WASTES
24	STORM DRAIN & SANITARY DRAIN	24"	CONCRETE PIPE	590.3'	3300' WEST M.P. 74.5	UNCONTAMINATED STORM WATER & SANITARY WASTES FROM VILLAGE OF CABIN CREEK
25	STORM DRAIN & SANITARY DRAIN	24"	CONCRETE PIPE	590.3'	1600' WEST M.P. 74.5	UNCONTAMINATED STORM WATER & SANITARY WASTES FROM VILLAGE OF CABIN CREEK
26	STORM DRAIN FROM COAL PILE	24"	CORRUGATED STEEL PIPE	603.0'	1500' WEST M.P. 74.5	STORM WATER RUNOFF FROM COAL STORAGE AREA
27	STORM DRAIN FROM COAL PILE	24"	OPEN CONCRETE TROUGH	595.0'	800' WEST M.P. 74.5	STORM WATER RUNOFF FROM COAL STORAGE AREA
28	STORM DRAIN FROM COAL PILE	24"	OPEN CONCRETE TROUGH	595.0'	800' WEST M.P. 74.5	STORM WATER RUNOFF FROM COAL STORAGE AREA
29	FLOOR DRAINS & SANITARY DRAIN	6"	STEEL PIPE	ABOVE 590.0'	230' WEST M.P. 74.5	UNCONTAMINATED FLOOR DRAINS & SANITARY WASTES FROM VILLAGE OF CABIN CREEK



12/1/70	3	ADDED: ARMY CORPS OF ENGINEERS DISCH. SERIAL NOS FOR OUTFALLS H/1, H/1A, H/1B, H/1C, H/1D, H/1E, H/1F, H/1G, H/1H, H/1I, H/1J, H/1K, H/1L, H/1M, H/1N, H/1O, H/1P, H/1Q, H/1R, H/1S, H/1T, H/1U, H/1V, H/1W, H/1X, H/1Y, H/1Z, H/2, H/2A, H/2B, H/2C, H/2D, H/2E, H/2F, H/2G, H/2H, H/2I, H/2J, H/2K, H/2L, H/2M, H/2N, H/2O, H/2P, H/2Q, H/2R, H/2S, H/2T, H/2U, H/2V, H/2W, H/2X, H/2Y, H/2Z, H/3, H/3A, H/3B, H/3C, H/3D, H/3E, H/3F, H/3G, H/3H, H/3I, H/3J, H/3K, H/3L, H/3M, H/3N, H/3O, H/3P, H/3Q, H/3R, H/3S, H/3T, H/3U, H/3V, H/3W, H/3X, H/3Y, H/3Z, H/4, H/4A, H/4B, H/4C, H/4D, H/4E, H/4F, H/4G, H/4H, H/4I, H/4J, H/4K, H/4L, H/4M, H/4N, H/4O, H/4P, H/4Q, H/4R, H/4S, H/4T, H/4U, H/4V, H/4W, H/4X, H/4Y, H/4Z, H/5, H/5A, H/5B, H/5C, H/5D, H/5E, H/5F, H/5G, H/5H, H/5I, H/5J, H/5K, H/5L, H/5M, H/5N, H/5O, H/5P, H/5Q, H/5R, H/5S, H/5T, H/5U, H/5V, H/5W, H/5X, H/5Y, H/5Z, H/6, H/6A, H/6B, H/6C, H/6D, H/6E, H/6F, H/6G, H/6H, H/6I, H/6J, H/6K, H/6L, H/6M, H/6N, H/6O, H/6P, H/6Q, H/6R, H/6S, H/6T, H/6U, H/6V, H/6W, H/6X, H/6Y, H/6Z, H/7, H/7A, H/7B, H/7C, H/7D, H/7E, H/7F, H/7G, H/7H, H/7I, H/7J, H/7K, H/7L, H/7M, H/7N, H/7O, H/7P, H/7Q, H/7R, H/7S, H/7T, H/7U, H/7V, H/7W, H/7X, H/7Y, H/7Z, H/8, H/8A, H/8B, H/8C, H/8D, H/8E, H/8F, H/8G, H/8H, H/8I, H/8J, H/8K, H/8L, H/8M, H/8N, H/8O, H/8P, H/8Q, H/8R, H/8S, H/8T, H/8U, H/8V, H/8W, H/8X, H/8Y, H/8Z, H/9, H/9A, H/9B, H/9C, H/9D, H/9E, H/9F, H/9G, H/9H, H/9I, H/9J, H/9K, H/9L, H/9M, H/9N, H/9O, H/9P, H/9Q, H/9R, H/9S, H/9T, H/9U, H/9V, H/9W, H/9X, H/9Y, H/9Z, H/10, H/10A, H/10B, H/10C, H/10D, H/10E, H/10F, H/10G, H/10H, H/10I, H/10J, H/10K, H/10L, H/10M, H/10N, H/10O, H/10P, H/10Q, H/10R, H/10S, H/10T, H/10U, H/10V, H/10W, H/10X, H/10Y, H/10Z, H/11, H/11A, H/11B, H/11C, H/11D, H/11E, H/11F, H/11G, H/11H, H/11I, H/11J, H/11K, H/11L, H/11M, H/11N, H/11O, H/11P, H/11Q, H/11R, H/11S, H/11T, H/11U, H/11V, H/11W, H/11X, H/11Y, H/11Z, H/12, H/12A, H/12B, H/12C, H/12D, H/12E, H/12F, H/12G, H/12H, H/12I, H/12J, H/12K, H/12L, H/12M, H/12N, H/12O, H/12P, H/12Q, H/12R, H/12S, H/12T, H/12U, H/12V, H/12W, H/12X, H/12Y, H/12Z, H/13, H/13A, H/13B, H/13C, H/13D, H/13E, H/13F, H/13G, H/13H, H/13I, H/13J, H/13K, H/13L, H/13M, H/13N, H/13O, H/13P, H/13Q, H/13R, H/13S, H/13T, H/13U, H/13V, H/13W, H/13X, H/13Y, H/13Z, H/14, H/14A, H/14B, H/14C, H/14D, H/14E, H/14F, H/14G, H/14H, H/14I, H/14J, H/14K, H/14L, H/14M, H/14N, H/14O, H/14P, H/14Q, H/14R, H/14S, H/14T, H/14U, H/14V, H/14W, H/14X, H/14Y, H/14Z, H/15, H/15A, H/15B, H/15C, H/15D, H/15E, H/15F, H/15G, H/15H, H/15I, H/15J, H/15K, H/15L, H/15M, H/15N, H/15O, H/15P, H/15Q, H/15R, H/15S, H/15T, H/15U, H/15V, H/15W, H/15X, H/15Y, H/15Z, H/16, H/16A, H/16B, H/16C, H/16D, H/16E, H/16F, H/16G, H/16H, H/16I, H/16J, H/16K, H/16L, H/16M, H/16N, H/16O, H/16P, H/16Q, H/16R, H/16S, H/16T, H/16U, H/16V, H/16W, H/16X, H/16Y, H/16Z, H/17, H/17A, H/17B, H/17C, H/17D, H/17E, H/17F, H/17G, H/17H, H/17I, H/17J, H/17K, H/17L, H/17M, H/17N, H/17O, H/17P, H/17Q, H/17R, H/17S, H/17T, H/17U, H/17V, H/17W, H/17X, H/17Y, H/17Z, H/18, H/18A, H/18B, H/18C, H/18D, H/18E, H/18F, H/18G, H/18H, H/18I, H/18J, H/18K, H/18L, H/18M, H/18N, H/18O, H/18P, H/18Q, H/18R, H/18S, H/18T, H/18U, H/18V, H/18W, H/18X, H/18Y, H/18Z, H/19, H/19A, H/19B, H/19C, H/19D, H/19E, H/19F, H/19G, H/19H, H/19I, H/19J, H/19K, H/19L, H/19M, H/19N, H/19O, H/19P, H/19Q, H/19R, H/19S, H/19T, H/19U, H/19V, H/19W, H/19X, H/19Y, H/19Z, H/20, H/20A, H/20B, H/20C, H/20D, H/20E, H/20F, H/20G, H/20H, H/20I, H/20J, H/20K, H/20L, H/20M, H/20N, H/20O, H/20P, H/20Q, H/20R, H/20S, H/20T, H/20U, H/20V, H/20W, H/20X, H/20Y, H/20Z, H/21, H/21A, H/21B, H/21C, H/21D, H/21E, H/21F, H/21G, H/21H, H/21I, H/21J, H/21K, H/21L, H/21M, H/21N, H/21O, H/21P, H/21Q, H/21R, H/21S, H/21T, H/21U, H/21V, H/21W, H/21X, H/21Y, H/21Z, H/22, H/22A, H/22B, H/22C, H/22D, H/22E, H/22F, H/22G, H/22H, H/22I, H/22J, H/22K, H/22L, H/22M, H/22N, H/22O, H/22P, H/22Q, H/22R, H/22S, H/22T, H/22U, H/22V, H/22W, H/22X, H/22Y, H/22Z, H/23, H/23A, H/23B, H/23C, H/23D, H/23E, H/23F, H/23G, H/23H, H/23I, H/23J, H/23K, H/23L, H/23M, H/23N, H/23O, H/23P, H/23Q, H/23R, H/23S, H/23T, H/23U, H/23V, H/23W, H/23X, H/23Y, H/23Z, H/24, H/24A, H/24B, H/24C, H/24D, H/24E, H/24F, H/24G, H/24H, H/24I, H/24J, H/24K, H/24L, H/24M, H/24N, H/24O, H/24P, H/24Q, H/24R, H/24S, H/24T, H/24U, H/24V, H/24W, H/24X, H/24Y, H/24Z, H/25, H/25A, H/25B, H/25C, H/25D, H/25E, H/25F, H/25G, H/25H, H/25I, H/25J, H/25K, H/25L, H/25M, H/25N, H/25O, H/25P, H/25Q, H/25R, H/25S, H/25T, H/25U, H/25V, H/25W, H/25X, H/25Y, H/25Z, H/26, H/26A, H/26B, H/26C, H/26D, H/26E, H/26F, H/26G, H/26H, H/26I, H/26J, H/26K, H/26L, H/26M, H/26N, H/26O, H/26P, H/26Q, H/26R, H/26S, H/26T, H/26U, H/26V, H/26W, H/26X, H/26Y, H/26Z, H/27, H/27A, H/27B, H/27C, H/27D, H/27E, H/27F, H/27G, H/27H, H/27I, H/27J, H/27K, H/27L, H/27M, H/27N, H/27O, H/27P, H/27Q, H/27R, H/27S, H/27T, H/27U, H/27V, H/27W, H/27X, H/27Y, H/27Z, H/28, H/28A, H/28B, H/28C, H/28D, H/28E, H/28F, H/28G, H/28H, H/28I, H/28J, H/28K, H/28L, H/28M, H/28N, H/28O, H/28P, H/28Q, H/28R, H/28S, H/28T, H/28U, H/28V, H/28W, H/28X, H/28Y, H/28Z, H/29, H/29A, H/29B, H/29C, H/29D, H/29E, H/29F, H/29G, H/29H, H/29I, H/29J, H/29K, H/29L, H/29M, H/29N, H/29O, H/29P, H/29Q, H/29R, H/29S, H/29T, H/29U, H/29V, H/29W, H/29X, H/29Y, H/29Z, H/30, H/30A, H/30B, H/30C, H/30D, H/30E, H/30F, H/30G, H/30H, H/30I, H/30J, H/30K, H/30L, H/30M, H/30N, H/30O, H/30P, H/30Q, H/30R, H/30S, H/30T, H/30U, H/30V, H/30W, H/30X, H/30Y, H/30Z, H/31, H/31A, H/31B, H/31C, H/31D, H/31E, H/31F, H/31G, H/31H, H/31I, H/31J, H/31K, H/31L, H/31M, H/31N, H/31O, H/31P, H/31Q, H/31R, H/31S, H/31T, H/31U, H/31V, H/31W, H/31X, H/31Y, H/31Z, H/32, H/32A, H/32B, H/32C, H/32D, H/32E, H/32F, H/32G, H/32H, H/32I, H/32J, H/32K, H/32L, H/32M, H/32N, H/32O, H/32P, H/32Q, H/32R, H/32S, H/32T, H/32U, H/32V, H/32W, H/32X, H/32Y, H/32Z, H/33, H/33A, H/33B, H/33C, H/33D, H/33E, H/33F, H/33G, H/33H, H/33I, H/33J, H/33K, H/33L, H/33M, H/33N, H/33O, H/33P, H/33Q, H/33R, H/33S, H/33T, H/33U, H/33V, H/33W, H/33X, H/33Y, H/33Z, H/34, H/34A, H/34B, H/34C, H/34D, H/34E, H/34F, H/34G, H/34H, H/34I, H/34J, H/34K, H/34L, H/34M, H/34N, H/34O, H/34P, H/34Q, H/34R, H/34S, H/34T, H/34U, H/34V, H/34W, H/34X, H/34Y, H/34Z, H/35, H/35A, H/35B, H/35C, H/35D, H/35E, H/35F, H/35G, H/35H, H/35I, H/35J, H/35K, H/35L, H/35M, H/35N, H/35O, H/35P, H/35Q, H/35R, H/35S, H/35T, H/35U, H/35V, H/35W, H/35X, H/35Y, H/35Z, H/36, H/36A, H/36B, H/36C, H/36D, H/36E, H/36F, H/36G, H/36H, H/36I, H/36J, H/36K, H/36L, H/36M, H/36N, H/36O, H/36P, H/36Q, H/36R, H/36S, H/36T, H/36U, H/36V, H/36W, H/36X, H/36Y, H/36Z, H/37, H/37A, H/37B, H/37C, H/37D, H/37E, H/37F, H/37G, H/37H, H/37I, H/37J, H/37K, H/37L, H/37M, H/37N, H/37O, H/37P, H/37Q, H/37R, H/37S, H/37T, H/37U, H/37V, H/37W, H/37X, H/37Y, H/37Z, H/38, H/38A, H/38B, H/38C, H/38D, H/38E, H/38F, H/38G, H/38H, H/38I, H/38J, H/38K, H/38L, H/38M, H/38N, H/38O, H/38P, H/38Q, H/38R, H/38S, H/38T, H/38U, H/38V, H/38W, H/38X, H/38Y, H/38Z, H/39, H/39A, H/39B, H/39C, H/39D, H/39E, H/39F, H/39G, H/39H, H/39I, H/39J, H/39K, H/39L, H/39M, H/39N, H/39O, H/39P, H/39Q, H/39R, H/39S, H/39T, H/39U, H/39V, H/39W, H/39X, H/39Y, H/39Z, H/40, H/40A, H/40B, H/40C, H/40D, H/40E, H/40F, H/40G, H/40H, H/40I, H/40J, H/40K, H/40L, H/40M, H/40N, H/40O, H/40P, H/40Q, H/40R, H/40S, H/40T, H/40U, H/40V, H/40W, H/40X, H/40Y, H/40Z, H/41, H/41A, H/41B, H/41C, H/41D, H/41E, H/41F, H/41G, H/41H, H/41I, H/41J, H/41K, H/41L, H/41M, H/41N, H/41O, H/41P, H/41Q, H/41R, H/41S, H/41T, H/41U, H/41V, H/41W, H/41X, H/41Y, H/41Z, H/42, H/42A, H/42B, H/42C, H/42D, H/42E, H/42F, H/42G, H/42H, H/42I, H/42J, H/42K, H/42L, H/42M, H/42N, H/42O, H/42P, H/42Q, H/42R, H/42S, H/42T, H/42U, H/42V, H/42W, H/42X, H/42Y, H/42Z, H/43, H/43A, H/43B, H/43C, H/43D, H/43E, H/43F, H/43G, H/43H, H/43I, H/43J, H/43K, H/43L, H/43M, H/43N, H/43O, H/43P, H/43Q, H/43R, H/43S, H/43T, H/43U, H/43V, H/43W, H/43X, H/43Y, H/43Z, H/44, H/44A, H/44B, H/44C, H/44D, H/44E, H/44F, H/44G, H/44H, H/44I, H/44J, H/44K, H/44L, H/44M, H/44N, H/44O, H/44P, H/44Q, H/44R, H/44S, H/44T, H/44U, H/44V, H/44W, H/44X, H/44Y, H/44Z, H/45, H/45A, H/45B, H/45C, H/45D, H/45E, H/45F, H/45G, H/45H, H/45I, H/45J, H/45K, H/45L, H/45M, H/45N, H/45O, H/45P, H/45Q, H/45R, H/45S, H/45T, H/45U, H/45V, H/45W, H/45X, H/45Y, H/45Z, H/46, H/46A, H/46B, H/46C, H/46D, H/46E, H/46F, H/46G, H/46H, H/46I, H/46J, H/46K, H/46L, H/46M, H/46N, H/46O, H/46P, H/46Q, H/46R, H/46S, H/46T, H/46U, H/46V, H/46W, H/46X, H/46Y, H/46Z, H/47, H/47A, H/47B, H/47C, H/47D, H/47E, H/47F, H/47G, H/47H, H/47I, H/47J, H/47K, H/47L, H/47M, H/47N, H/47O, H/47P, H/47Q, H/47R, H/47S, H/47T, H/47U, H/47V, H/47W, H/47X, H/47Y, H/47Z, H/48, H/48A, H/48B, H/48C, H/48D, H/48E, H/48F, H/48G, H/48H, H/48I, H/48J, H/48K, H/48L, H/48M, H/48N, H/48O, H/48P, H/48Q, H/48R, H/48S, H/48T, H/48U, H/48V, H/48W, H/48X, H/48Y, H/48Z, H/49, H/49A, H/49B, H/49C, H/49D, H/49E, H/49F, H/49G, H/49H, H/49I, H/49J, H/49K, H/49L, H/49M, H/49N, H/49O, H/49P, H/49Q, H/49R, H/49S, H/49T, H/49U, H/49V, H/49W, H/49X, H/49Y, H/49Z, H/50, H/50A, H/50B, H/50C, H/50D, H/50E, H/50F, H/50G, H/50H, H/50I, H/50J, H/50K, H/50L, H/50M, H/50N, H/50O, H/50P, H/50Q, H/50R, H/50S, H/50T, H/50U, H/50V, H/50W, H/50X, H/50Y, H/50Z, H/51, H/51A, H/51B, H/51C, H/51D, H/51E, H/51F, H/51G, H/51H, H/51I, H/51J, H/51K, H/51L, H/51M, H/51N, H/51O, H/51P, H/51Q, H/51R, H/51S, H/51T, H/51U, H/51V, H/51W, H/51X, H/51Y, H/51Z, H/52, H/52A, H/52B, H/52C, H/52D, H/52E, H/52F, H/52G, H/52H, H/52I, H/52J, H/52K, H/52L, H/52M, H/52N, H/52O, H/52P, H/52Q, H/52R, H/52S, H/52T, H/52U, H/52V, H/52W, H/52X, H/52Y, H/52Z, H/53, H/53A, H/53B, H/53C, H/53D, H/53E, H/53F, H/53G, H/53H, H/53I, H/53J, H/53K, H/53L, H/53M, H/53N, H/53O, H/53P, H/53Q, H/53R, H/53S, H/53T, H/53U, H/53V, H/53W, H/53X, H/53Y, H/53Z, H/54, H/54A, H/54B, H/54C, H/54D, H/54E, H/54F, H/54G, H/54H, H/54I, H/54J, H/54K, H/54L, H/54M, H/54N, H/54O, H/54P, H/54Q, H/54R, H/54S, H/54T, H/54U, H/54V, H/54W, H/54X, H/54Y, H/54Z, H/55, H/55A, H/55B, H/55C, H/55D, H/55E, H/55F, H/55G, H/55H, H/55I, H/55J, H/55K, H/55L, H/55M, H/55N, H/55O, H/55P, H/55Q, H/55R, H/55S, H/55T, H/55U, H/55V, H/55W, H/55X, H/55Y, H/55Z, H/56, H/56A, H/56B, H/56C, H/56D, H/56E, H/56F, H/56G, H/56H, H/56I, H/56J, H/56K, H/56L, H/56M, H/56N, H/56O, H/56P, H/56Q, H/56R, H/56S, H/56T, H/56U, H/56V, H/56W, H/56X, H/56Y, H/56Z, H/57, H/57A, H/57B, H/57C, H/57D, H/57E, H/57F, H/57G, H/57H, H/57I, H/57J, H/57K, H/57L, H/57M, H/57N, H/57O, H/57P, H/57Q, H/57R, H/57S, H/57T, H/57U, H/57V, H/57W, H/57X, H/57Y, H/57Z, H/58, H/58A, H/58B, H/58C, H/58D, H/58E, H/58F, H/58G, H/58H, H/58I, H/58J, H/58K, H/58L, H/58M, H/58N, H/58O, H/58P, H/58Q, H/58R, H/58S, H/58T, H/58U, H/58V, H/58W, H/58X, H/58Y, H/58Z, H/59, H/59A, H/59B, H/59C, H/59D, H/59E, H/59F, H/59G, H/59H, H/59I, H/59J, H/59K, H/59L, H/59M, H/59N, H/59O, H/59P, H/59Q, H/59R, H/59S, H/59T, H/59U, H/59V, H/59W, H/59X, H/59Y, H/59Z, H/60, H/60A, H/60B, H/60C, H/60D, H/60E, H/60F, H/60G, H/60H, H/60I, H/60J, H/60K, H/60L, H/60M, H/60N, H/60O, H/60P, H/60Q, H/60R, H/60S, H/60T, H/60U, H/60V, H/60W, H/60X, H/60Y, H/60Z, H/61, H/61A, H/61B, H/61C, H/61D, H/61E, H/61F, H/61G, H/61H, H/61I, H/61J, H/61K, H/61L, H/61M, H/61N, H/61O, H/61P, H/61Q, H/61R, H/61S, H/61T, H/61U, H/61V, H/61W, H/61X, H/61Y, H/61Z, H/62, H/62A, H/62B, H/62C, H/62D, H/62E, H/62F, H/62G, H/62H, H/62I, H/62J, H/62K, H/62L, H/62M, H/62N, H/62O, H/62P, H/62Q, H/62R, H/62S, H/62T, H/62U, H/62V, H/62W, H/62X, H/62Y, H/62Z, H/63, H/63A, H/63B, H/63C, H/63D, H/63E, H/63F, H/63G, H/63H, H/63I, H/63J, H/63K, H/63L, H/63M, H/63N, H/63O, H/63P, H/63Q, H/63R, H/63S, H/63T, H/63U, H/63V, H/63W, H/63X, H/63Y, H/63Z, H/64, H/64A, H/64B, H/64C, H/64D, H/64E, H/64F, H/64G, H/64H, H/64I, H/64J, H/64K, H/64L, H/64M, H/64N, H/64O, H/64P, H/64Q, H/64R, H/64S, H/64T, H/64U, H/64V, H/64W, H/64X, H/64Y, H/64Z, H/65, H/65A, H/65B, H/65C, H/65D, H/65E, H/65F, H/65G, H/65H, H/65I, H/65J, H/65K, H/65L, H/65M, H/65N, H/65O, H/65P, H/65Q, H/65R, H/65S, H/65T, H/65U, H/65V, H/65W, H/65X, H/65Y, H/65Z, H/66, H/66A, H/66B, H/66C, H/66D, H/66E, H/66F, H/66G, H/66H, H/66I, H/66J, H/66K, H/66L, H/66M, H/66N, H/66O, H/66P, H/66Q, H/66R, H/66S, H/66T, H/66U, H/66V, H/66W, H/66X, H/66Y, H/66Z, H/67, H/67A, H/67B, H/67C, H/67D, H/67E, H/67F, H/67G, H/67H, H/67I, H/67J, H/67K, H/67L, H/67M, H/67N, H/67O, H/67P, H/67Q, H/67R, H/67S, H/67T, H/67U, H/67V, H/67W, H/67X, H/67Y, H/67Z, H/68, H/68A, H/68B, H/68C, H/68D, H/68E, H/68F, H/68G, H/68H, H/68I, H/68J, H/68K, H/68L, H/68M, H/68N, H/68O, H/68P, H/68Q, H/68R, H/68S, H/68T, H/68U, H/68V, H/68W, H/68X, H/68Y, H/68Z, H/69, H/69A, H/69B, H/69C, H/69D, H/69E, H/69F, H/69G, H/69H, H/69I, H/69J, H/69K, H/69L, H/69M, H/69N, H/69O, H/69P, H/69Q, H/69R, H/69S, H/69T, H/69U, H/69V, H/69W, H/69X, H/69Y, H/69Z, H/70, H/70A, H/70B, H/70C, H/70D, H/70E, H/70F, H/70G, H/70H, H/70I, H/70J, H/70K, H/70L, H/70M, H/70N, H/70O, H/70P, H/70Q, H/70R, H/70S, H/70T, H/70U, H/70V, H/70W, H/70X, H/70Y, H/70Z, H/71, H/71A, H/71B, H/71C, H/71D, H/71E, H/71F, H/71G, H/71H, H/71I, H/71J, H/71K, H/71L, H/71M, H/71N, H/71O, H/71P, H/71Q, H/71R, H/71S, H/71T, H/71U, H/71V, H/71W, H/71X, H/71Y, H/71Z, H/72, H/72A, H/72B, H/72C, H/72D, H/72E, H/72F, H/72G, H/72H, H/72I, H/72J, H/72K, H/72L, H/72M, H/72N, H/72O, H/72P, H/72Q, H/72R, H/72S, H/72T, H/72U, H/72V, H/72W, H/72X, H/72Y, H/72Z, H/73, H/73A, H/73B, H/73C, H/73D, H/73E, H/73F, H/73G, H/73H, H/73I, H/73J, H/73K, H/73L, H/73M, H/73N, H/73O, H/73P, H/73Q, H/73R, H/73S, H/73T, H/73U, H/73V, H/73W, H/73X, H/73Y, H/73Z, H/74, H/74A, H/74B, H/74C, H/74D, H/74E, H/74F, H/74G, H/74H, H/74I, H/74J, H/74K, H/74L, H/74M, H/74N, H/74O, H/74P, H/74Q, H/74R, H/74S, H/74T, H/74U, H/74V, H/74W, H/74X, H/74Y, H/74Z, H/75, H/75A, H/75B, H/75C, H/75D, H/75E, H/75F, H/75G, H/75H, H/75I, H/75J, H/75K, H/75L, H/75M, H/75N, H/75O, H/75P, H/75Q, H/75R, H/75S, H/75T, H/75U, H/75V, H/75W, H/75X, H/75Y, H/75Z, H/76, H/76A, H/76B, H/76C, H/76D, H/76E, H/76F, H/76G, H/76H, H/76I, H/76J, H/76K, H/76L, H/76M, H/76N, H/76O, H/76P, H/76Q, H/76R, H/76S, H/76T, H/76U, H/76V, H/76W, H/76X, H/76Y, H/76Z, H/77, H/77A, H/77B, H/77C, H/77D, H/77E, H/77F, H/77G, H/77H, H/77I, H/77J, H/77K, H/77L, H/77M, H/77N, H/77O, H/77P, H/77Q, H/77R, H/77S, H/77T, H/77U, H/77V, H/77W, H/77X, H/77Y, H/77Z, H/78, H/78A, H/78B, H/78C, H/78D, H/78E, H/78F, H/78G, H/78H, H/78I, H/78J, H/78K, H/78L, H/78M, H/78N, H/78O, H/78P, H/78Q, H/78R, H/78S, H/78T, H/78U, H/78V, H/78W, H/78X, H/78Y, H/78Z, H/79, H/79A, H/79
---------	---	---

